


2-2000

Lower Elkhorn Natural Resources District Cooperative Agreement, Field Summary Report 1998-1999

Susan Olafsen Lackey
University of Nebraska-Lincoln, slackey1@unl.edu

Follow this and additional works at: <http://digitalcommons.unl.edu/conservationsurvey>

 Part of the [Geology Commons](#), [Geomorphology Commons](#), [Hydrology Commons](#), [Paleontology Commons](#), [Sedimentology Commons](#), [Soil Science Commons](#), and the [Stratigraphy Commons](#)

Lackey, Susan Olafsen, "Lower Elkhorn Natural Resources District Cooperative Agreement, Field Summary Report 1998-1999" (2000). *Conservation and Survey Division*. 316.
<http://digitalcommons.unl.edu/conservationsurvey/316>

This Article is brought to you for free and open access by the Natural Resources, School of at DigitalCommons@University of Nebraska - Lincoln. It has been accepted for inclusion in Conservation and Survey Division by an authorized administrator of DigitalCommons@University of Nebraska - Lincoln.


**Lower Elkhorn Natural Resources
District
Cooperative Agreement**

**Field Summary Report
1998-1999**

February 2000

**Conservation & Survey Division
UN-L**

Susan Olafsen Lackey



University of
Nebraska
Lincoln

Institute of Agriculture and Natural Resources

Institute of Agriculture and Natural Resources
Conservation and Survey Division
601 East Benjamin Avenue, Suite 104
Norfolk, NE 68701-0812
Telephone (402) 370-4007
FAX (402) 370-4010

Geological and Natural Resources Surveys



2/21/00

Lower Elkhorn Natural Resources District
601 East Benjamin Ave, Suite 101
Norfolk, NE 68702

RE: Phase II Monitoring Well Network, Of the November 1998
Cooperative Agreement between the NRD and CSD.

Dear Sirs:

Attached is a copy of the Field Summary Report, 1998 to 1999, for the above referenced project. Four copies have been provided to the NRD, three bound copies and one in a 3-ring notebook for production of additional copies. A thank-you letter and site information packets were sent to individual land owners last fall.

The report is organized with summary maps and tables in the front. Individual site information follows the summary data. Sites are organized by well number with a blue cover page for each site. Site data include; 7.5-minute Quad Map, Final Test-Hole Log, Geophysical Log, Aerial Photo, Well Registrations, and Well Completion Diagrams.

Seventeen test-holes were drilled, sampled, and electric logged. The total test-hole footage was 4124 feet. Thirty-five monitoring wells were drilled, constructed, and developed. Individual well depths ranged from 30-feet to 320-feet. Total well footage was 4962 feet.

Sixteen pressure transducers, purchased by the NRD in 1998, were installed by CSD in July. Thirty-five dedicated pumps have been purchased under the agreement and will be installed in March and April.

Cost breakdowns will be provided to the NRD subcommittee in March.

Sincerely,

Susan Olafsen Lackey
Hydrogeologist

TABLE OF CONTENTS

Map:	1998 and 1999 Test-Hole Locations
Table:	1998 and 1999 Test-Hole Data
Table:	1998 and 1999 Test-Hole Correlation Data
Map:	Pierce County Plat with Test-Hole Numbers
Map:	Madison County Plat with Test-Hole Numbers
Map:	Stanton County Plat with Test-Hole Numbers
Map:	1998 and 1999 Monitoring Well Locations
Table:	1998 and 1999 Monitoring Well Location Data (2 pages)
Table:	1998 and 1999 Monitoring Well Data (2 pages)
Map:	Pierce County Plat with Monitoring Well Numbers
Map:	Madison County Plat with Monitoring Well Numbers
Map:	Stanton County Plat with Monitoring Well Numbers
Log	1999 Daily Field Activities (5 pages)


Site Information organized by Well Number on Blue Cover Page

7.5-minute Quad Map.....	Site Location
Final Test-Hole Log	
Geophysical Log	
Aerial Photo.....	Well Locations
Well Registrations.....	2 pages each Well
Well Completion Diagrams.....	1 page each Wells

#1 Wells:	Gutzman Site	T26N, R1W, Sec 30, NE	Pierce Co
	#1 Middle.....	North	
	#1 Deep.....	South	
#2 Wells:	Von Rentzel Site	T27N, R2W, Sec 1, NW	Pierce Co
	#2 Middle.....	West	
	#2 Deep.....	East	
#3 Wells:	Gansebom Site	T28N, R3W, Sec 22, NW	Pierce Co
	#3 Shallow.....	North	
	#3 Middle.....	South	
	#3 Deep.....	Center	
#4 Wells:	Hilkeman Site	T25N, R1W, Sec 18, NW	Pierce Co
	#4 Shallow.....	West	
	#4 Middle.....	Center	
	#4 Deep.....	East	
#5 Wells:	School/Wagner Site	T25N, R4W, Sec 16, SE	Pierce Co
	#5 Middle.....	East	
	#5 Deep.....	West	

#6 Wells:	Nuesch Site	T26N, R4W, Sec 36, SW	Pierce Co
	#6 Shallow.....	North	
	#6 Middle.....	Center	
	#6 Deep.....	South	
#7 Wells:	Renter Site	T27N, R4W, Sec 15, NE	Pierce Co
	#7 Middle.....	South	
	#7 Deep.....	North	
#8 Wells:	Gubbels Site	T27N, R2W, Sec 22, NW	Pierce Co
	#8 Middle.....	North	
	#8 Deep.....	South	
#9 Wells:	Broderson Site	T27N, R1W, Sec 17, SE	Pierce Co
	#9 Middle.....	South	
	#9 Deep.....	North	
#10 Wells:	Koehn Site	T26N, R2W, Sec 5, NW	Pierce Co
	#10 Shallow.....	West	
	#10 Middle.....	East	
#11 Wells:	Flesner Site	T26N, R3W, Sec 15, SW	Pierce Co
	#11 Middle.....	North	
	#11 Deep.....	South	
#12 Wells:	Uecker Site	T24N, R3W, Sec 17, SW	Madison Co
	#12 Shallow.....	South	
	#12 Deep.....	Center	
	#12 DeepDeep.....	North	
#13 Well:	Stolle Site	T24N, R3W, Sec 29, NW	Madison Co
	#13 Shallow		
#14 Wells:	Pojar Site	T22N, R2W, Sec 8, NE	Madison Co
	#14 Shallow.....	South	
	#14 Deep.....	North	
#15 Wells:	Dicke Site	T22N, R1E, Sec 18, SW	Stanton Co
	#15 Shallow.....	South	
	#15 Middle.....	North	
#16 Well:	Johnson Site	T23N, R1E, Sec 20, SE	Stanton Co
	#16 Middle		
#17 Well:	Nixon Site	T23N, R1E, Sec 16, SW	Stanton Co
	#17 Middle		

1998 & 1999 LOWER ELKHORN NRD
TEST-HOLE DRILLING



★ TEST HOLE LOCATION
& NUMBER

7/8/99
CSD/Sol

**1998 and 1999 Lower Elkhorn NRD
Test-Hole Data**

Conservation & Survey Division

Sol 11/8/99

Test Hole	Owner	Legal Description	Qtrs	Foot N/S	Foot E/W	Topo Elev	7.5' Quad	Total Depth
1-LE-98*	Gutzman	26N-1W-30-NE	adaa	-1333	-33	1605	Weetown	228
2-LE-98*	VonRentzel	27N-2W-1-NW	bbbb	-40	110	1725	Osmond	274
1-LE-99	Hilkeman	25N-1W-18-NW	baba	-87	1662	1560	Weetown	220
2-LE-99	Broderson	27N-1W-17-SE	dcdc	48	-1770	1662	Randolph SW	270
3-LE-99	Gubbels	27N-2W-22-NW	bbbb	-89	35	1732	Osmond	320
4-LE-99	Koehn	26N-2W-5-NW	baab	-16	2099	1600	Osmond	140
5-LE-99	Nuesch	26N-4W-36-SW	ccbc	949	33.5	1705	Pierce NW	319
6-LE-99	School	25N-4W-16-SE	dddd	16	-141	1830	Tilden NE	427
7-LE-99	Gansebom	28N-3W-22-NW	bbbc	-494	23	1673	Midland	160
8-LE-99	Renter	27N-4W-15-NE	abbb	-45.5	-2634	1675	Plainview	210
9-LE-99	Flesner	26N-3W-15-SW	cccb	353	50	1753	Pierce NW	362
10-LE-99	Eucker	24N-3W-17-SW	cccc	99	29	1630	Meadow Grove	239
11-LE-99	Stolle	24N-3W-29-NW	bccc	-2500	35	1612	Meadow Grove	160
12-LE-99	Pojar	22N-2W-8-NE	adda	-1989	-33	1755	Battle Creek	400
13-LE-99	Dicke	22N-1E-18-SW	cbbc	2168	26	1610	Madison NE	245
14-LE-99	Johnson	23N-1E-20-SE	dbbb	2501	2612	1492	Madison NE	80
15-LE-99	Nixon	23N-1E-16-SW	ccbb	1292	36	1485	Madison NE	70

* Field #1-LE-98 = Report #13-A-98 Field #2-LE-98 = Report #14

1998 and 1999 Lower Elkhorn NRD

Correlation Table

Conservation & Survey Division

Sol 11/8/99

Test Hole	Site #	Owner	Legal Description	Drill Date	Total Depth	7.5' Quad	Topo Elev	Well #
1-LE-98*	3-98	Gutzman	26N-1W-30-NE	6/22/98	228	Weetown	1605	1
2-LE-98*	5-98	VonRentzel	27N-2W-1-NW	6/25/98	274	Osmond	1725	2
1-LE-99	9-99	Hilkeman	25N-1W-18-NW	4/12/99	220	Weetown	1560	4
2-LE-99	8-99	Broderson	27N-1W-17-SE	4/13/99	270	Randolph SW	1662	9
3-LE-99	3-99	Gubbels	27N-2W-22-NW	4/14/99	320	Osmond	1732	8
4-LE-99	4-99	Koehn	26N-2W-5-NW	4/20/99	140	Osmond	1600	10
5-LE-99	6-99	Nuesch	26N-4W-36-SW	4/20/99	319	Pierce NW	1705	6
6-LE-99	7-99	School	25N-4W-16-SE	4/26/99	427	Tilden NE	1830	5
7-LE-99	2-99	Gansebom	28N-3W-22-NW	4/27/99	160	Midland	1673	3
8-LE-99	1-99	Renter	27N-4W-15-NE	5/13/99	210	Plainview	1675	7
9-LE-99	5-99	Flesner	26N-3W-15-SW	5/21/99	362	Pierce NW	1753	11
10-LE-99	10-99	Eucker	24N-3W-17-SW	6/2/99	239	Meadow Grove	1630	12
11-LE-99	11-99	Stolle	24N-3W-29-NW	6/3/99	160	Meadow Grove	1612	13
12-LE-99	13-99	Pojar	22N-2W-8-NE	6/8/99	400	Battle Creek	1755	14
13-LE-99	16-99	Dicke	22N-1E-18-SW	6/10/99	245	Madison NE	1610	15
14-LE-99	15-99	Johnson	23N-1E-20-SE	6/23/99	80	Madison NE	1492	16
15-LE-99	14-99	Nixon	23N-1E-16-SW	6/24/99	70	Madison NE	1485	17


* Field #1-LE-98 = Report #13-A-98 Field #2-LE-98 = Report #14-A-98

MADISON COUNTY

T 24 N

T 23 N

T 22 N



TEST - HOLE
NUMBER

CSO/501 7/7/99

R4W

R3W

R2W



R1W

STANTON COUNTY


TEST - HOLE
NUMBER

CSD/Sol

7/1/99



1998 & 1999 LOWER ELKHORN NRD
MONITORING WELL NETWORK



★ MONITORING WELL(S) LOCATION
& WELL NUMBER(S)

7/2/99
CSO/Sol

**1998 and 1999 Lower Elkhorn NRD
Monitoring Well Location Data**

Pierce County

Well #	Owner	Legal	Feet N/S	Feet E/W	Grnd Elev	MP AGS (Not final)
1M (N)	Gutzman	26N-1W-30-NE	-1319	-34.5	1605	2.6
1D (S)			-1333	-33		2.9
2M (W)	VonRentzel	27N-2W-1-NW	-40.5	94	1725	2.5
2D (E)			-40	110		3.9
3S (N)	Gansebom	28N-3W-22-NW	-511	33	1673	3.5
3M (S)			-472	33		3
3D (C)			-498	34		4
4S (W)	Hilkeman	25N-1W-18-NW	-69	1590	1560	3
4M (C)			-70	1603		4
4D (E)			-71.5	1616		3
5M (E)	School	25N-4W-16-SE	23.5	-97	1830	3
5D (W)			22.5	-152		4
6S (N)	Nuesch	26N-4W-36-SW	965	22	1705	4
6M (C)			953	23		4
6D (S)			940	23		3.5
7S (S)	Renter	27N-4W-15-NE	-56.5	-2633	1675	3
7D (N)			-45.5	-2634		3.2
8M (N)	Gubbels	27N-2W-22-NW	-105	35	1735	3.2
8D (S)			-116	36		3
9M (S)	Broderson	27N-1W-17-SE	40	-1759	1665	3
9D (N)			45	-1758		3
10S (W)	Koehn	26N-2W-5-NW	-4	2123	1600	3
10M (E)			-4	2129		4
11M (N)	Flesner	26N-3W-15-SW	379	51	1745	1+added
11D (S)			353	50		3

1998 and 1999 Lower Elkhorn NRD
Monitoring Well Location Data
(Continued)

Madison County

Well #	Owner	Legal	Feet N/S	Feet E/W	Grnd Elev	MP AGS (not final)
12S (S)	Uecker	24N-3W-17-SW	79	27	1630	3.2
12D (C)			85	29		3
12DD (N)			98	28		3.2
13S	Stolle	24N-3W-29-NW	-2500	35	1612	5
14S (S)	Pojar	22N-2W-8-NE	-1993	-32	1755	3.2
14M (N)			-1989	-33		3.5

Conservation & Survey Division

Sol 8/11/99

Stanton County

Well #	Owner	Legal	Feet N/S	Feet E/W	Grnd Elev	MP AGS (not final)
15S (S)	Dicke	22N-1E-18-SW	2168	26	1605	3
15M (N)			-2195	28		1.6
16M	Johnson	23N-1E-20-SE	2501	-2612	1490	3.2
17M	Nixon	23N-1E-16-SW	1292	36	1485	4.5

Conservation & Survey Division

Sol 8/11/99

**1998 and 1999 Lower Elkhorn NRD
Monitoring Well Network
Well Data Table**

Pierce County

Well # Setting	Total Depth	Screen Length	Gravel Pack Top	Min WL Depth	Max WL Depth	Top of Ogallal	Top of Bedrock	Water Source
1M (No)	66.5	10	52.5	31	33	138.0	194.0	P-P S&G
1D (So)	154.5	5	145	31	34		Kn	To
2M (W)	179	10	144	84	110	200.0	>274	P-P S&G
2D (E)	254	5	244	84	106			To
3S (No)	30	10	17	9	18	60.0	139.0	WT
3M (So)	72.5	10	58	9	19		Kp	
3D (Ctr)	132	5	122	10	21			To
4S (W)	30.5	10	17	8	13	105.0	192	WT
4M (Ctr)	77	10	60	6	12		Kn	P-P S&G
4D (E)	156	5	146	6	12			To
5M (E)	167.5	10	150	119		180.0	+/-415	P-P S&G
5D (W)	262	5	252	120			Kp	To
6S (No)	66	10	52	7	11	165.0	+/-317	P-P S&G
6M (Ctr)	160	10	145	10	20		Kn	P-P S&G
6D (So)	281	5	270	13				To
7S (So)	47	10	31	3		90.0	190.0	P-P S&G
7D (No)	152	5	143	2			Kp	To
8M (No)	136	10	121	94	96	160.0	310.0	P-P S&G
8D (So)	200	5	190	94	99		Kp	To
9M (So)	120	10	106	54	59	155.0	244.5	P-P S&G
9D (No)	188	5	177	54	59		Kn	To
10S (W)	32	10	17	4		96.0	117.0	P-P S&G
10M (E)	91.5	5	83.5	3			Kp	P-P S&G
11M (No)	270	10	243+	112		267.0	+/-360	P-P S&G
11D (So)	321	5	>300	112			Kn?	To

**1998 and 1999 Lower Elkhorn NRD
Monitoring Well Network
Well Data Table
(Continued)**

Madison County

Well # Setting	Total Depth	Screen Length	Gravel Pack Top	Min WL Depth	Max WL Depth	Top of Ogalla	Top of Bedrock	Water Source
12S (So)	42	10	27	19		44.5	216.0	P-P S&G
12D (Ctr)	133	5	122	19			Kn	To
12DD (No)	180	5	168	21				To
13S	33	10	17	1		69.5	135 (Kn)	P-P S&G
14S (So)	154	10	139	111		305.0	375.0	P-P S&G
14M (No)	294	5	278	121			Kn	P-P S&G

Conservation & Survey Division

Sol

8/11/99

Stanton County

Well # Setting	Total Depth	Screen Length	Gravel Pack Top	Min WL Depth	Max WL Depth	Top of Ogalla	Top of Bedrock	Water Source
15S (So)	155	10	140.5	80		176.0	235.0	P-P S&G
15M (No)	214	5	196	72			Kn	To
16M	43	10	29	5		None	47 (Kn)	P-P S&G
17M	46	10	32	3		None	52 (Kn)	P-P S&G

Conservation & Survey Division

Sol

8/11/99

csd/sol 7/7/99

The map displays a portion of a larger survey or land grant area, characterized by a grid of numbered sections. The grid is bounded by numbers 1 through 36 on all four sides. Key locations include:


- Towns and Settlements:** DRY CREEK, NORTH, PLEASANTON, and parts of other nearby communities are visible.
- Geographical Features:** The OHIO RIVER flows along the southern edge. Other features include HILL, VALLEY, and various smaller creeks and roads.
- Grid System:** The grid consists of 6x6 blocks of sections, each numbered sequentially from 1 to 36.
- Annotations:** Handwritten notes and symbols are present, including "DRY CREEK", "NORTH", "PLEASANTON", and various circled numbers and letters.

MADISON COUNTY

T 24 N

T 23 N

T 22 N



WELL NUMBERS

CSO/SOI 7/7/99

R4W

R3W



R2W

R1W

STANTON COUNTY

WELL NUMBERS

CSD/Sol 7/7/99



DAILY FIELD LOG (LOWER ELKHORN NRD – 1999)

Grosch Irrigation: Dale Wiles, Project Manager
Bret Sholes, Driller
Randy Stahlecker, Helper
Ben Sholes, Driller/helper
Jeff Wiles, Protective cover crew chief
CSD: Sue Lackey, Leonard Boryca, additional geologists

APRIL 12 Monday

Site #9(Hilkeman), Test Hole #1-LE-99 (TD=220'), caliper uncalibrated
Joe Mason, Geologist, assisted in logging the test holes

APRIL 13 Tuesday

Moved to Site #8 (Broderson), Test Hole #2-LE-99 (TD=270')

APRIL 14 Wednesday

Moved to Site #3 (Gubbels), Test Hole #3-LE-99--hit rock @133'
(rained & snowed out)

APRIL 15 Thursday No Drill--Wet

APRIL 16 Friday No Drill

.....

APRIL 19 Monday

Completed Test hole #3-LE-99 (TD=320'). About two hrs to drill through boulder
Moved equipment and set up to drill at Site #4 (Koehn),
Jim Goeke, Hydrogeologist, assisted in logging the test holes

APRIL 20 Tuesday

Site #4 (Koehn), Test Hole # 4-LE-99 (TD=140'). Moved to site #6
Site #6 (Nuesch) Test Hole #5-LE-99 (TD=319)

APRIL 21 Wednesday

????Rained out, Mud Pump troubles--Parts

APRIL 22 Thursday No Drill—Wait on Parts

APRIL 23 Friday No Drill

.....

APRIL 26 Monday

Moved to Site #7 (School) Test Hole #6-LE-99 (TD=427')
Jim Roberts assisted in logging the test holes and installing monitoring wells.

APRIL 27 Tuesday

Moved Site #2 (Gansebom) Test Hole #7-LE-99 (TD=160')

APRIL 28 Wednesday

Site #2 -- Well # 3M(South) Screen 61-71'

APRIL 29 Thursday

Site #2-- Well #3S(North)—Screen 20-30'
Well #3D(Center)--Screen 126-131'
Grout machine troubles—Plugged on Shallow well.
Moved equipment to Site #9

APRIL 30 Friday

Site #9 Well #4S(West)—Screen 20-30',
Well #4M(Center)—Screen 66-76' &
Well #4D (East)—Screen 151-156'

.....
MAY 3 Monday

Moved to Site #7 Well #5M(East)—Screen 157-167'

MAY 4 Tuesday

Site #7 Drilled & installed casing & filter pack in Deep Well (287-292'). Failed, could not get the grout down, tremie max depth 130 feet (possible Clay/silt squeezing) Formation from above caving to 273(last measurement) Tried to wash tremie in and put 2 batches grout in but rest came to surface. Decided to wait to see if grout would settle to bottom.

MAY 5 Wednesday

Moved to Site #6(Nuesch) Well #6S(North)—Screen 56-66'
@ 2:00 called due to rain, high winds, and mud pump problems.
Site #7 Grout settled only 30 feet. Flagged Sites 10 & 11

MAY 6 Thursday No Drill

Located sites 12, 13 & 16 with skip

May 7 Friday No Drill

Site #6 Set up to install other Monitoring wells at but Mud pump troubles again.
Developed 6S—1 hour. Checked Approach on Site #5, none.

.....
MAY 10 Monday

Site #6 Well #6M(Center)—Screen 149-159' Set up the de-sander

MAY 11 Tuesday

Site #6 Well #6D(South)--Screen 275-280'
Flagged Site #14. Checked utilities at Site #11

MAY 12 Wednesday

Site #6 Developed wells #6M—1 hour & #6D--.5 hours
Site #7 Redrilled Well #5D(West)—Screen 256-261'
Reflagged site #14. Checked utilities on Site 10--None

MAY 13 Thursday

Moved from Site #7 to Site #1 (Renter), Test Hole #8-LE-99 (TD=212')

MAY 14 Friday

Site #1 Well #7D(North)—Screen 145-150'

Well #7S(South)—Screen 35-45'

Set up at Site #3 to install monitoring wells

.....

MAY 17 Monday

Site #3 Well #8M(North)—Screen 124.5-134.5'

MAY 18 Tuesday

Site #3 Well #8D(South)—Screen 195-200'

Moved to Site #8

MAY 19 Wednesday

Site #8 Well #9D(North)—Screen 180-185'

Fixed Swivel

Drilled 20-feet on Well #9M

Mark Kuzila on-site

MAY 20 Thursday

Site #8 Well 9M (South)—Screen 110-120'

Site #4 Well #10S(West)—Screen 21-31'

Well #10M(East)—Screen 86-91'

Moved to Site #5

MAY 21 Friday

Site #5 (Flesner) Test Hole #9-LE-99 (TD=362),. A lot of cracks and rocks, could hardly keep up mixing mud.

.....

MAY 24 Monday

Site #5 Monitoring well failed, casing hard to get in, decided to ream out.

MAY 25 Tuesday

Site #5 Well # 11D(South)—Screen 315-320'

Marv Carlson, Geologist, assisted

MAY 26 Wednesday

Site #5 Well #11M(North)—Screen 255.5-265.5'

MAY 27 Thursday

Site #5 Developed 11M--.5 hours #11D--.5 hours

While moving to Site #7 to pull failed monitoring well, the rig broke down.

Site #2 Gas Lines hit installing covers (East side of North & Center wells)

MAY 28 Friday

Grosch developed #5 wells & abandoned first 5D well (Ben stitches)

.....

JUNE 1 Tuesday

Moved rig from Site #7 to Site #10

JUNE 2 Wednesday

Site #10 (Uecker), Test hole #10-LE-99 (TD=239), (Lost a lot of water in Kn)
Well #12DD(North)—Screen 174-179'

JUNE 3 Thursday

Site #10 Well 12D(Center)—Screen 127-132'
Well 12S(South)—Screen 31.5-41.5'
Site #11 (Stolle) Test hole #11-LE-99 (TD=160)

JUNE 4 Friday

Site #11 Well #13S—Screen 20-30'.
Rained during the night, equipment stuck in meadow.

.....

JUNE 7 Monday

Site #11. Troubles all day long. Farmer to come and pull equipment from the wet meadow. Moved to Site #13 brought cat from O'Neill to level site

JUNE 8 Tuesday

Site #13 (Pojar) Test Hole #12-LE-99, (TD=400')

JUNE 9 Wednesday

Site #13 Well #14D(North)—Screen 285-290'
Drilled 160' on shallow well, on hold due to lightening

JUNE 10 Thursday

Site #13 Well 14S(South)—Screen 144-154'
Had to pull rig out of Alfalfa with cat
Site #16(Dicke) Test hole #13-LE-99 (TD=245')

JUNE 11 Friday

Site #16 Well 15S(South)—Screen 143.5-153.5' (target was middle well)
Stormy weather, lightning, rain which delayed drilling in the morning. Drilling very slow due clay and collar buildup

.....

JUNE 14 - JUNE 18.

Well driller on vacation. No drilling activity.

.....

21 JUNE Monday

Site #16. While preparing to move to the rig, the well driller injured. Finished setting up at the site & assisted fixing the drilling equipment and pickup

22 JUNE Tuesday

Site #16 Well #15M(North)—Screen 204-209'
Developed 15S—1 hour & 15M-- .5 hours
Moved to Site #15

23 JUNE Wednesday

Site #15 (Johnson) Test Hole #14-LE-99 (TD=80),
Well #16M—Screen 32-42' developed
Moved to Site #14

24 JUNE Thursday


Site #14 (Nixon), Test hole #15-LE-99 (TD=70'),
Well #17M—Screen 35.5-45.5 developed.

Number 1 Wells

TH # 13-A-98

#1 WELLS

GUTZMAN SITE



T 26N R1W SECTION 30 NE

WEETOWN QJAD

Test Hole #13-A-98(E-log)
(26N-1W-30adaa)
Pierce County

Location: NE NE SE NE Sec. 30, T. 26 N., R. 1 W., approximately
 1,333 feet south and 33 feet west of the northeast corner.
 Ground elevation: 1,605 ft. (t). (Weetown, 7.5 min. quadrangle)
 Depth to water: 31.2 ft.(8-14-98) Wells installed.

Depth, in feet
 From To

Quaternary System, undifferentiated:

Soil; silt, very sandy, black; sand is very fine to fine.....	0.0	3.0
Sand, very silty; sand is very fine to medium, with little coarse.....	3.0	5.0
Silt, very sandy, slightly clayey, dark brownish gray; sand is very fine to fine; some coarser.....	5.0	12.0
Sand, slightly silty; sand is very fine to medium, trace coarse to very coarse, and rare fine gravel.	12.0	15.0
Sand, slightly silty; sand is very fine to medium, little coarse to very coarse; rare very fine gravel; contains some chert, dark silicatess and rare fossil fragments.....	15.0	18.0
Sand, very fine to coarse.....	18.0	33.0
Sand, very fine to medium, little coarse.....	33.0	38.0
Sand, very fine to very coarse.....	38.0	41.0
Sand, very fine to coarse.....	41.0	48.0
Sand, very fine to very coarse.....	48.0	58.0
Sand, very fine to medium, little coarse sand to fine gravel.....	58.0	59.0
Sand, very fine to medium, little coarse.....	59.0	63.0
Sand, very fine to coarse, little very coarse.....	63.0	68.0
Sand, gravelly, silty; very fine sand to very fine gravel.....	68.0	78.0
Sand, moderately silty; contains very fine to medium sand with some medium to coarse gravel; contains reworked limestone and anorthosite.....	78.0	83.0
Sand, moderately silty; very fine sand to fine gravel; contains reworked limestone, rootlet casts, and sandstone; with anorthosite.....	83.0	88.0
Gravel, very fine to fine.....	88.0	93.0
Gravel, sandy, silty; very fine sand to fine gravel.....	93.0	98.0
Sand, very fine to fine, some medium.....	98.0	138.0

Tertiary System - Miocene Series - Ogallala Group:

Clay, silty, sandy, olive gray; sand is very fine to fine, little medium; contains trace of bentonitic clay.....	138.0	143.0
Clay, silty, sandy, olive gray; sand is very fine to fine, little medium.....	143.0	149.0
Sandstone, slightly silty; sand is very fine to fine, little medium.....	149.0	158.0
Sandstone; very silty; sand is very fine to fine, little medium; contains clay lenses.....	158.0	163.0
Clay, silty, moderately sandy, olive gray; sand is very fine to fine; contains limestone grains.....	163.0	178.0
Silt to siltstone; clayey, sandy, light yellowish brown, very calcareous; sand is very fine.....	178.0	183.0
Silt to siltstone; clayey, very calcareous, pale brown, some chalk fragments.....	183.0	194.0
Cretaceous System - Upper Cretaceous Series - Colorado Group:		
Niobrara Formation:		
Limestone, chalky,.....	194.0	203.0
Chalk, brown; below 207 ft, white.....	203.0	213.0
Chalk, white; below 213 ft, gray.....	213.0	216.0
Shale, very calcareous, black.....	216.0	228.0

PIERCE CO. T27N-2W-18BB
TH# 2-LE-98 TD 254
6/29/98 LARRY, ORSON PENA

TH#
NWS

(14-A98)

WELLS 1M & 1D
WEE TOWN 7.5 MIN QUAD

SP 10

RES 10

20

40

60

80

100

120

140

160

180

200

220

240

254 -
TD

NOT TO SCALE

Pierce, Co. 93-94

Photo J10

T-26-N R-1-W 85

Sec. 30

TH #13-A-98

SITE 3-98

1009
T1746
VI

NA

24.9

2.7

3339
T6096
IA
5.0

LE#1M WELL
(NORTH)

LE#1D WELL
(SOUTH)

30

NHEL
134.1

NC

NHEL
44.2

NHEL
146.5

10
127.0

3338
T6095
VI

NC

W NHEL

2A

973

3221

T1600

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

February 1995
DWR Form 981

FOR DEPARTMENT USE ONLY

Registration No. _____ Sequence No. _____ Registration Date: _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn NRD Telephone Number (402) 371-7313
Address 601 E Benjamin Avenue Suite 101
City Norfolk State NE Zip Code 68701 +

2. Drilling Firm Conservation & Survey Division UN-L Telephone Number (402) 472-3471
Address 113 Nebraska Hall Contractor's License No. 17003 Pump Installer License No. _____
City Lincoln State NE Zip Code 68588 + 0517

3. Permit Number(s) N/A

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☐ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Other _____
(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No B. Registration number of abandoned well: _____
C. Replacement well is _____ feet from abandoned well. D. Abandoned well last operated _____, 19____
E. Original well pump column size: _____ inches. F. Abandoned well plugged _____, 19____

5. A. Well location: NE 1/4 NE 1/4 of Section 30, Township 26 North, Range 1 East/West, Pierce County.
B. The well is 1319 feet from the North South section line and 34.5 feet from the East West section line.
(indicate one) (indicate one)
C. Street address or block, lot and subdivision, if applicable: SITE 3-98 TH # 13-A-98
(GUTZMAN)
D. Location of water use, if applicable (give legal descriptions): _____
E. If for irrigation, the land to be irrigated is _____ acres.
F. Well reference letter(s), if applicable: LE#1M (NORTH)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through E.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: less than 1 to 5 gallons per minute. Measured ☐ or Estimated ☐
B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.
D. Pumping equipment installed: _____, 19____. E. Brand/Type: _____

8. Well Construction Information.

A. Total well depth: 66 feet. B. Static water level: 31.2 feet. C. Pumping water level: --- feet.
D. Construction began: 6/24, 1998. E. Construction completed: 6/24, 1998.
F. Bore hole diameter: 8 inches.
G. Casing: Diameter 2.49 ID 2.89 OD inches. Type of material: PVC SCH 40
Wall thickness: .20 inches. Joints--Welded/Glued/Threaded/Other: --- Guides at --- ft.
Length(s) and placement(s) depth from +3 ft. to 56 ft. from --- ft. to --- ft.
H. Screen: 2.49 ID 2.89 OD in.; Type of material PVC SCH 40
Screen openings (slot size): 0.010 Trade name: --- Guides at --- ft.
Length(s) and placement(s) depth from 56 ft. to 66 ft. from --- ft. to --- ft.
I. Gravel pack interval(s) from 52.5 ft. to 66 ft. from --- ft. to --- ft. Grade size: de-icing
J. Grouted/Sealed from 0 ft. to 52.5 ft., with benseal/ez-mud
(type)
from --- ft. to --- ft., with ---
(type)
K. Drilling method: mud rotary L. Drilling fluid: quick gel
M. Well development technique (total time and method): airlift 30 minutes
N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? --- Yes X No
If yes, what will be used: ---

9. Geologic Materials Logged

DEPTH IN FEET FROM	TO	DESCRIPTION
<u>0</u>	<u>3</u>	<u>topsoil</u>
<u>3</u>	<u>15</u>	<u>silty sand</u>
<u>15</u>	<u>66</u>	<u>fine sand to coarse gravel</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>

DEPTH IN FEET FROM	TO	DESCRIPTION
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

[Signature]
Water Well Contractor's Signature

7-21-98
Date

[Signature]
Water Well Owner's Signature

8/18/98
Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration No. _____ Sequence No. _____ Registration Date: _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn NRD Telephone Number (402) 371-7313
Address 601 E Benjamin Avenue Suite 101
City Norfolk State NE Zip Code 68701 +
2. Drilling Firm Conservation & Survey Division UN-L Telephone Number (402) 472-3471
Address 113 Nebraska Hall Contractor's License No. 17003 Pump Installer License No. _____
City Lincoln State NE Zip Code 68588- + 0517
3. Permit Number(s) N/A
4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☐ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Other _____
(indicate use)
5. Replacement and abandoned well information.
A. Is this well a replacement well? ☐ Yes ☒ No B. Registration number of abandoned well: _____
C. Replacement well is _____ feet from abandoned well. D. Abandoned well last operated _____, 19____
E. Original well pump column size: _____ inches. F. Abandoned well plugged _____, 19____
6. A. Well location: SE 1/4 NE 1/4 of Section 30, Township 26 North, Range 1 East (West) Pierce County.
B. The well is 1333 feet from the North (South) section line and 33 feet from the East (West) section line.
(indicate one) (indicate one)
C. Street address or block, lot and subdivision, if applicable: SITE 3-98 TH #13-A-98
(GUTZMAN)
D. Location of water use, if applicable (give legal descriptions): _____
E. If for irrigation, the land to be irrigated is _____ acres.
F. Well reference letter(s), if applicable: LE #1D (SOUTH)
7. Pump Information.
Is pump installed at this time? ☐ Yes ☒ No
If yes, complete items A through E.
If no, complete items A and D with estimated information for those wells in which pump will be installed.
A. Actual pumping rate, if applicable: less to 5 gallons per minute. Measured ☐ or Estimated ☐
B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.
D. Pumping equipment installed: _____, 19____. E. Brand/Type: _____

8. Well Construction Information.

A. Total well depth: 176 feet. B. Static water level: 31.5 feet. C. Pumping water level: --- feet.
D. Construction began: 6/22, 1998. E. Construction completed: 6/23, 1998.
F. Bore hole diameter: 8 inches.
G. Casing: Diameter 2.49 ID 2.89 OD inches. Type of material: PVC SCH 40
Wall thickness: .20 inches. Joints--Welded/Glued/Threaded Other: --- Guides at --- ft.
Length(s) and placement(s) depth from +3 ft. to 148 ft. from --- ft. to --- ft.
H. Screen: 2.49 ID 2.89 OD in.; Type of material PVC SCH 40
Screen openings (slot size): 0.010 Trade name: --- Guides at --- ft.
Length(s) and placement(s) depth from 148 ft. to 153 ft. from --- ft. to --- ft.
I. Gravel pack interval(s) from 145 ft. to 154.5 ft. from --- ft. to --- ft. Grade size: 20/40
J. Grouted/Sealed from 154.5 ft. to 156.5 ft., with hole plug (type)
--- from 0 ft. to 145 ft., with Benseal/EZ-mud (type)
K. Drilling method: mud rotary L. Drilling fluid: quick gel
M. Well development technique (total time and method): airlift 40 minutes
N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? --- Yes X No
If yes, what will be used: ---

9. Geologic Materials Logged

DEPTH IN FEET FROM	TO	DESCRIPTION	DEPTH IN FEET FROM	TO	DESCRIPTION
<u>0</u>	<u>3</u>	<u>topsoil</u>	<u>174</u>	<u>194</u>	<u>interbedded silt and</u>
<u>3</u>	<u>15</u>	<u>silty sand</u>	<u>---</u>	<u>---</u>	<u>siltstone with clay</u>
<u>15</u>	<u>66</u>	<u>fine sand to coarse gravel</u>	<u>194</u>	<u>226</u>	<u>chalk to limestone</u>
<u>66</u>	<u>73</u>	<u>silt/clay, pink to olive</u>	<u>---</u>	<u>---</u>	<u>---</u>
<u>73</u>	<u>116</u>	<u>fine sand; silty, some clay</u>	<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>lenses</u>	<u>---</u>	<u>---</u>	<u>---</u>
<u>116</u>	<u>132</u>	<u>fine sand</u>	<u>---</u>	<u>---</u>	<u>---</u>
<u>132</u>	<u>139</u>	<u>clay, silty, sandy; olive</u>	<u>---</u>	<u>---</u>	<u>---</u>
<u>139</u>	<u>151</u>	<u>fine sand, silty</u>	<u>---</u>	<u>---</u>	<u>---</u>
<u>151</u>	<u>174</u>	<u>interbedded sand & sandstone, silty</u>	<u>---</u>	<u>---</u>	<u>---</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

[Signature]
Water Well Contractor's Signature

7-21-98
Date

[Signature]
Water Well Owner's Signature

8/18/98
Date

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project LENRD PIE	Well Number #1M (NORTH)	Date Drilled 6/24/98	Date Constructed 6/24/98	Ground Elevation 1605 (t)
County PIERCE	Qtr/Qtr/Qtr NE/SE/NE	Section 30	Township 26N	Range 1W
Drilling Co. NGS	Method MUD ROTARY	Driller GROSCH	Log By LACKEY/SMITH	Total Depth 66 FT

Borehole Diameter 8-INCHES
Survey Reference
Type/Size of Casing PVC 2.5" ID SCH 40
Type/Size of Screen PVC 2.5" ID SCH 40
Screen Slot Size 0.010
Joint Type THREADED
Type/Amount Grout/Fill BENSEAL/EZ-MUD 10 BATCHES
Type/Amount Seal HOLE PLUG 2 BAGS

Elevation Depth
From
Reference

+/- 32.6 TOP OF CASING

0 GROUND

3 TOP OF
GROUT/FILL

31.2 WATER LEVEL


8/14/98

52.5 TOP OF FILTER PACK

56 TOP OF SCREEN

66 BOTTOM OF SCREEN

66.5 BOREHOLE DEPTH



NORTH WELL

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project LENRD 1998 PHASE II	Well Number #1D (SOUTH)	Date Drilled 6/22/98	Date Constructed 6/23/98	Ground Elevation 1605 (t)
County PIERCE	Qtr/Qtr/Qtr NE/SE/NE	Section 30	Township 26N	Range 1W
Drilling Co. NGS	Method MUD ROTARY	Driller GROSCH	Log By LACKEY/SMITH	Total Depth 176 FT

Borehole Diameter 8-INCHES
Survey Reference
Type/Size of Casing PVC 2.5" ID SCH 40
Type/Size of Screen PVC 2.5" ID SCH 40
Screen Slot Size 0.010
Joint Type THREADED
Type/Amount Grout/Fill BENSEAL/EZ-MUD 10 BATCHES
Type/Amount Seal HOLE PLUG 2 BAGS

Elevation Depth
From
Reference

+/- 3 2.9 TOP OF CASING

0 GROUND

3 TOP OF
GROUT/FILL

31.5 WATER LEVEL
8/14/98


145 TOP OF FILTER PACK

148 TOP OF SCREEN

153 BOTTOM OF SCREEN
154.5 BOTTOM FILTER PACK

156.5 SEAL BOTTOM

176 BOREHOLE DEPTH



SOUTH WELL


Number 2 Wells

PIERCE COUNTY

TH # 14-A-98

#2 WELLS

VON RENTZEL SITE



T27N R2W SECTION 1 NW1/4

OSMOND 7.5 QUAD

Test Hole #14-A-98 (E-log)
(27N-2W-1bbbb)
Pierce County

Location: NW NW NW NW Sec. 1, T. 27 N., R. 2 W., approximately 40 feet south and 110 feet east of the northwest corner.

Ground elevation: 1,725 ft. (t). (Osmond, 7.5 min. quadrangle)

Depth to water: 89.8 ft. (8-14-98) Wells installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Soil: silt, very sandy, grayish brown; sand is very fine to fine, little medium.....	0.0	4.0
Silt, slightly clayey, moderately sandy, grayish brown; sand is very fine to fine, little medium...	4.0	6.0
Silt, slightly clayey, moderately sandy, dark brown; sand is very fine to fine, little medium...	6.0	12.0
Sand, very silty; sand is very fine to fine, some medium.....	12.0	17.0
Silt, sandy, moderately clayey, moderately calcareous; contains much glacial material.....	17.0	19.0
Sand, silty; sand is very fine to coarse, little very fine gravel.....	19.0	20.0
Till; clay, silty, sandy, gravelly, moderately calcareous, light olive brown.....	20.0	24.5
Gravel, medium; contains limestone, ironstone, and quartz.....	24.5	29.0
Till; clay, silty, sandy, gravelly, yellowish brown.	29.0	32.0
Sand, gravelly; very fine sand to fine gravel, trace of medium gravel; contains limestone, ironstone, quartz.....	32.0	35.0
Till; clay, silty, sandy, gravelly, moderately calcareous, yellowish brown.....	35.0	43.0
Till; clay, silty, sandy, gravelly, moderately calcareous, brownish yellow; trace dark gray below 49 ft.....	43.0	54.0
Till; clay, silty, sandy, gravelly, dark gray; some limestone grains.....	54.0	79.0
No sample.....	79.0	89.0
Till; clay, silty, sandy, gravelly, moderately calcareous, dark gray; limestone grains.....	89.0	149.0
No sample.....	149.0	162.0
Sand, very fine to very coarse.....	162.0	164.0
Sand, very fine to coarse, little very coarse sand to very fine gravel.....	164.0	169.0
Sand, very fine to coarse; below 179 ft, contains		

trace of till fragments.....	169.0	184.0
Sand, very fine to very coarse; below 189 ft, contains a trace of gravel.....	184.0	194.0
Sand, gravelly, silty; very fine sand to very fine gravel.....	194.0	199.0
Gravel, slightly sandy; fine sand to medium gravel..	199.0	200.0
Tertiary System - Miocene Series - Ogallala Group:		
Sand, very fine to medium, with some gravel; contains rootlet casts; from 209 to 214 ft, thin silt lens.....	200.0	219.0
Sand, very fine to fine, little medium; below 229 ft, slightly silty.....	219.0	259.0
Silt, slightly clayey, slightly calcareous, light gray; contains some volcanic ash.....	259.0	271.0
Clay, silty, slightly calcareous, light gray.....	271.0	274.0

WELLS 2M & 2D
OSMARD 7.5-MIN

PIERCE COUNTY
T24N, R1W, 30 NE
(13A-98) → TH 4-1-E-98
6/22/98
TD LOG 226'
LAKEY, GROCH, PINKS

SP10

DES 25

0
20
40
60
80
100
120
140
160
180
200
220
226
TD

LE #2

NOT TO SCALE

Pierce, Co. 93-94 Photo I5
T-27-N R-2-W 45 Sec. 1

TH 14-A-98

SITE 5-98

2404
T 412
2/2

WELL LE #2D
(EAST)

WELL LE #2M
(WEST)

4B 4C
5.9 6.0

NC
1/4

RW

4D
7.2

RW

4I
1/1

HEL
4 301.6

4F
128.5

4G
5.6

4H
6.9

4I
125.1

4J
6.1

576
T 714
1/1

552
T 718
1/1

HELINW
179.5

HELINW
4157.6

4C
6.0

4D
133.0

4E
6.0

HELINW
577.0

3320

SL 189 LNC 5

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

February 1995
DWR Form 981

FOR DEPARTMENT USE ONLY

Registration No. _____ Sequence No. _____ Registration Date: _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn NRD Telephone Number (402) 371-7313
Address 601 E Benjamin Avenue Suite 101
City Norfolk State NE Zip Code 68701 +

2. Drilling Firm Conservation & Survey Division UN-L Telephone Number (402) 472-3471
Address 113 Nebraska Hall Contractor's License No. 17003 Pump Installer License No. _____
City Lincoln State NE Zip Code 68588 + 0517

3. Permit Number(s) N/A

4. Purpose of well (indicate one): Dewatering (over 90 days) Domestic Geothermal Ground Heat Exchanger
Ground Water Source Heat Pump Industrial Injection Irrigation Livestock X Monitoring
Observation Public Water Supply (with spacing (46-638)) Public Water Supply (without spacing) Recovery
Other _____
(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? Yes X No B. Registration number of abandoned well: _____
C. Replacement well is _____ feet from abandoned well. D. Abandoned well last operated _____, 19____
E. Original well pump column size: _____ inches. F. Abandoned well plugged _____, 19____

6. A. Well location: NW 1/4 NW 1/4 of Section 1, Township 27 North, Range 2 East West, Pierce County.

B. The well is 40.5 feet from the North South section line and 94 feet from the East West section line.
(indicate one) (indicate one)

C. Street address or block, lot and subdivision, if applicable: SITE 5-98 TH #14-A-98
(NORTH 1/2) (SOUTH 1/2)

D. Location of water use, if applicable (give legal descriptions): _____

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: LE #2M (WEST)

7. Pump Information.

Is pump installed at this time? Yes X No

If yes, complete items A through E.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: less than 1 to 5 gallons per minute. Measured ☐ or Estimated ☐

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment installed: _____, 19____.

E. Brand/Type: _____

8. Well Construction Information.

A. Total well depth: 169 feet. B. Static water level: 89.8 feet. C. Pumping water level: --- feet.
D. Construction began: 6/25, 19 98. E. Construction completed: 6/26, 19 98.
F. Bore hole diameter: 7.5 inches.
G. Casing: Diameter 2.49 ID 2.89 OD inches. Type of material: PVC SCH 40
Wall thickness: .20 inches. Joints--Welded/Glued/Threaded Other: --- Guides at --- ft.
Length(s) and placement(s) depth from +3 ft. to 159 ft. from --- ft. to --- ft.
H. Screen: 2.49 ID 2.89 OD in.; Type of material PVC SCH 40
Screen openings (slot size): 0.010 Trade name: --- Guides at --- ft.
Length(s) and placement(s) depth from 159 ft. to 169 ft. from --- ft. to --- ft.
I. Gravel pack interval(s) from 144 ft. to 170 ft. from --- ft. to --- ft. Grade size: de-icing
J. Grouted/Sealed from 170 ft. to 179 ft., with hole plug (type)
from 0 ft. to 144 ft., with Benseal/EZ-mud (type)
K. Drilling method: mud rotary L. Drilling fluid: Quick Gel
M. Well development technique (total time and method): air lift 45 minutes
N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? --- Yes ☒ No
If yes, what will be used: ---

9. Geologic Materials Logged

DEPTH IN FEET FROM	TO	DESCRIPTION
<u>0</u>	<u>3</u>	<u>topsoil</u>
<u>3</u>	<u>6</u>	<u>silt, brown</u>
<u>6</u>	<u>17</u>	<u>silty sand; fine</u>
<u>17</u>	<u>20</u>	<u>sand & gravel</u>
<u>20</u>	<u>25</u>	<u>clay, silty</u>
<u>25</u>	<u>38</u>	<u>sand & gravel</u>
<u>38</u>	<u>160</u>	<u>clay till, sandy & gravelly</u> <u>some cobbles</u>
<u>160</u>	<u>188</u>	<u>sand & gravel</u>
<u>188</u>	<u>198</u>	<u>pink & olive silt, very sandy</u>

DEPTH IN FEET FROM	TO	DESCRIPTION

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

[Signature]
Water Well Contractor's Signature

7-26-98
Date

[Signature]
Water Well Owner's Signature

8/18/98
Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration No. _____ Sequence No. _____ Registration Date: _____
Owner Code No. _____ Receipt No. _____ NRD1. Well Owner Lower Elkhorn NRD Telephone Number (402) 371 7313
Address 601 East Benjamin Avenue Suite 101
City Norfolk State NE Zip Code 68701 +2. Drilling Firm Conservation & Survey Division Telephone Number (402) 72-3471
Address 113 Nebraska Hall Contractor's License No. 17003 Pump Installer License No. _____
City Lincoln State NE Zip Code 68588 + 05173. Permit Number(s) N/A4. Purpose of well (indicate one): Dewatering (over 90 days) Domestic Geothermal Ground Heat Exchanger
Ground Water Source Heat Pump Industrial Injection Irrigation Livestock X Monitoring
Observation Public Water Supply (with spacing (46-638)) Public Water Supply (without spacing) Recovery
Other _____
(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? Yes X No B. Registration number of abandoned well: _____
C. Replacement well is _____ feet from abandoned well. D. Abandoned well last operated _____, 19____
E. Original well pump column size: _____ inches. F. Abandoned well plugged _____, 19____6. A. Well location: NW 1/4 NW 1/4 of Section 1, Township 27 North, Range 2 East West, Pierce County.B. The well is 40 feet from the North South section line and 110 feet from the East West section line.
(indicate one) (indicate one)C. Street address or block, lot and subdivision, if applicable: SITE 5-98 TH 14-A-98
(VON RENTZEL)

D. Location of water use, if applicable (give legal descriptions): _____

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: LE #2D (EAST)

7. Pump Information.

Is pump installed at this time? Yes X No

If yes, complete items A through E.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: less than 1 to 5 gallons per minute. Measured ☐ or Estimated ☐

B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.

D. Pumping equipment installed: _____, 19____. E. Brand/Type: _____

8. Well Construction Information.

- A. Total well depth: 254 feet. B. Static water level: 90.2 feet. C. Pumping water level: --- feet.
- D. Construction began: 6/27, 1998. E. Construction completed: 6/30, 1998.
- F. Bore hole diameter: 7.5 inches.
- G. Casing: Diameter 2.49 ID 2.89 OD inches. Type of material: PVC SCH 40
 Wall thickness: .20 inches. Joints--Welded/Glued/Threaded/Other: Guides at --- ft.
 Length(s) and placement(s) depth from +4 ft. to 247 ft. from --- ft. to --- ft.
- H. Screen: 2.49 ID 2.89 OD in.; Type of material PVC SCH 40
 Screen openings (slot size): 0.010 Trade name: --- Guides at --- ft.
 Length(s) and placement(s) depth from 247 ft. to 252 ft. from --- ft. to --- ft.
- I. Gravel pack interval(s) from 244 ft. to 252 ft. from --- ft. to --- ft. Grade size: ---
- J. Grouted/Sealed from 0 ft. to 244 ft., with Benseal/EZ-mud (type)
 from --- ft. to --- ft., with --- (type)
- K. Drilling method: mud rotary L. Drilling fluid: quick gel
- M. Well development technique (total time and method): air lift 60 minutes
- N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? --- Yes X No
 If yes, what will be used: ---

9. Geologic Materials Logged

DEPTH IN FEET FROM	TO	DESCRIPTION
<u>0</u>	<u>3</u>	<u>topsoil</u>
<u>3</u>	<u>6</u>	<u>silt brown</u>
<u>6</u>	<u>17</u>	<u>silty fine sand</u>
<u>17</u>	<u>20</u>	<u>sand & gravel</u>
<u>20</u>	<u>25</u>	<u>clay silty</u>
<u>25</u>	<u>38</u>	<u>sand & gravel</u>
<u>38</u>	<u>160</u>	<u>clay till; silty, sandy, gravelly, with cobbles</u>
<u>160</u>	<u>188</u>	<u>sand & gravel</u>
<u>188</u>	<u>198</u>	<u>pink & olive silt, very sandy</u>

DEPTH IN FEET FROM	TO	DESCRIPTION
<u>198</u>	<u>248</u>	<u>Very fine sand, some cementation & silt layers</u>
<u>248</u>	<u>271</u>	<u>silty clay</u>
<u>271</u>	<u>274</u>	<u>clay shale, grey</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>
<u>---</u>	<u>---</u>	<u>---</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

[Signature]
 Water Well Contractor's Signature

2-21-98
 Date


[Signature]
 Water Well Owner's Signature

8/18/98
 Date

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project LENRD PHASE II	Well Number #2M (WEST)	Date Drilled 6/25/98	Date Constructed 6/26/98	Ground Elevation 1725 (t)
County PIERCE	Qtr/Qtr/Qtr NW/NW/NW	Section 1	Township 27N	Range 2W
Drilling Co. NGS	Method MUD ROTARY	Driller GROSCH	Log By LACKEY/SMITH	Total Depth 179 FT




WEST WELL

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project LENRD <u>PII</u>	Well Number #2D (<u>EAST</u>)	Date Drilled 6/27-29/98	Date Constructed 6/29-30/98	Ground Elevation 1725 (t)
County PIERCE	Qtr/Qtr/Qtr NW/NW/NW	Section 1	Township 27N	Range 2W
Drilling Co. NGS	Method MUD ROTARY	Driller GROSCH	Log By LACKEY/SMITH	Total Depth 254 FT



EAST WELL


Number 3 Wells

PIERCE COUNTY

TH # 7-LE-99

#3 WELLS

GANSEBOM SITE



T28N R3W SECTION 22 NW 1/4

MIDLAND QUAD

Test Hole #7-LE-99 (E-log)
(28N-3W-22bbbc)
Pierce County

Location: SW NW NW NW Sec. 22, T. 28 N., R. 3 W., approximately
 494 feet south and 23 feet east of northwest corner.
 Ground elevation: 1,673 ft. (t) (Midland, 7.5 min. quadrangle)
 Depth to water: 8.7 ft. (5/17/99) Wells installed.

Depth, in feet
 From To


Quaternary System, undifferentiated:

Top soil: silt, moderately clayey, moderately sandy, dark brown; sand is very fine.....	0.0	2.5
Silt, moderately clayey, moderately sandy, brown; sand is very fine with little fine sand, slightly more fine sand below 10 ft.....	2.5	20.5
Sand, gravelly; medium sand to fine gravel, rare medium gravel; coarse gravel below 25 ft.....	20.5	30.0
Sand, gravelly, slightly silty; fine sand to fine gravel.....	30.0	32.0
Clay, sandy, yellowish brown, sand is very fine to medium.....	32.0	33.0
Sand, slightly silty, sand is medium to coarse, rare very coarse sand to very fine gravel.....	33.0	35.0
Sand, slightly silty, brown; sand is fine to coarse; trace very coarse sand to fine gravel below 40 ft.	35.0	43.5
Silt, moderately clayey, moderately sandy, brownish yellow; sand is very fine to medium, some coarser grains below 43.5 ft.....	43.5	55.0
Sand, slightly silty; sand is very fine to coarse, brown; contains limy grains.....	55.0	60.0

Tertiary System - Miocene Series - Ogallala Group:

Sand, slightly silty; sand is very fine to medium, little coarse; olive brown.....	60.0	75.0
Silt, very sandy, light brown to olive; sand is very fine to medium.....	75.0	80.0
Sand to sandstone, silty; very fine to medium grained; olive gray; contains rootlet fragments below 85 ft.....	80.0	90.0
Sand, very fine to medium; olive gray.....	90.0	95.0
Sand to sandstone; very fine to medium grained; olive gray; contains rootlet fragments; silty below 105 ft.....	95.0	120.0
Sand, very fine to fine, some coarser grains; olive gray; contains rootlet fragments.....	120.0	132.0
Silt, very clayey, very sandy, gray; sand is very		

fine to coarse.....	132.0	135.0
Clay, silty, light yellowish brown.....	135.0	139.0
Cretaceous System - Upper Cretaceous Series - Montana Group:		
Pierre Formation:		
Chalk, white, some bentonitic clay.....	139.0	145.0
Chalk, white and yellow.....	145.0	150.0
Shale, clayey, moderately to very calcareous, light gray to yellow.....	150.0	160.0



Century GEOPHYSICAL CORP.

7-LE-99

COMPANY : Grosch
WELL : 7-LE-99
LOCATION/FIELD : Site 2
COUNTY : PIERCE
STATE : NE
SECTION : 22

OTHER SERVICES:

caliphe
downhole
None

TOWNSHIP : 28 RANGE : 3W

DATE : 04/27/99
DEPTH DRILLER : 160
LOG BOTTOM : 159.14
LOG TOP : 1.43

PERMANENT DATUM : None

KB : None

LOG MEASURED FROM: grnd

DF : None

DRL MEASURED FROM: +2

GL : 1673

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS : 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : sol

BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite

BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54

FILE : PROCESSED
TYPE : 8043A

THRESH: 2500

Midland Quad
Wells 3S, 3M, & 3D

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS





Photo E3
Sec. 22

SITE 2-99



STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313

State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805

Contractor's License No. 39070

State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____.

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____.

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well: _____

6. A. Well location: NW 1/4 of the NW 1/4 of Section 22, Township 28 North, Range 3 ☐ East ☒ West, Pierce County.
B. The well is 511 feet from the ☒ North or ☐ South section line and 33 feet from the ☐ East or ☒ West section line.
C. Street address or block, lot and subdivision, if applicable: Site 2-99 (Gansebom), TH # 7-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 3S (South) (NORTH)

2/2 8/99

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.

Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 30 feet.

B. Static water level: 9.7 feet.

C. Pumping water level: _____ feet.

☐ Estimated or ☐ Measured

D. Well Construction began: April 29, 1999.

E. Well Construction completed: June 1, 1999.

F. Bore hole diameter: 8 1/4 inches.

G. Plain Casing: Diameter 2.469 ID

2.875 OD inches.

Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+ 3.5 ft

. to 20 ft.

from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from

20 ft

to 30 ft.

from _____ ft. to

guides at 19 ft.

I. Gravel pack interval(s) from 17 ft.

to 30 ft.

from _____ ft.

to _____ ft.

Grade size: Armour coat

J. Grouted/Sealed from 0 ft.

to 3 ft.,

with Steel cover in concrete

(type)

from 3 ft.

to 17 ft.,

with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>2.5</u>	<u>Topsoil, dark brown</u>
<u>2.5</u>	<u>21</u>	<u>Clay, sandy, silty with sand lenses</u>
<u>21</u>	<u>30</u>	<u>Sand, fine & gravel, medium</u>
<u>30</u>	<u>32</u>	<u>Clay, yellowish, brown</u>
<u>32</u>	<u>41</u>	<u>Sand, fine to coarse & some gravel</u>
<u>41</u>	<u>51</u>	<u>Clay, sandy, light brown</u>
<u>51</u>	<u>65</u>	<u>Sand, coarse & gravel</u>
<u>65</u>	<u>85</u>	<u>Interbedded clayey, Silt & Sand, fine to coarse</u>
<u>85</u>	<u>90</u>	<u>Sand, coarse & gravel, coarse</u>
<u>90</u>	<u>115</u>	<u>Sand, fine with rootlets</u>
<u>115</u>	<u>130</u>	<u>Interbedded sandstone & sand</u>
<u>130</u>	<u>139</u>	<u>Clay, silty</u>

Depth in Feet		Description
From	To	
<u>139</u>	<u>160</u>	<u>Clay, chalky, white to yellow</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313

State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805

Contractor's License No. 39070

State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____.

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____.

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well: NW

6. A. Well location: NW 1/4 of the NW 1/4 of Section 22, Township 28 North, Range 3 ☐ East ☒ West, Pierce County.
B. The well is 472 feet from the ☒ North or ☐ South section line and 33 feet from the ☐ East or ☒ West section line.
C. Street address or block, lot and subdivision, if applicable: Site 2-99 (Gansebom), TH # 7-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 3M ~~(North)~~ (South)

OK

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.

Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Redifloz

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 72.5 feet.B. Static water level: 8.7 feet.C. Pumping water level: _____ feet.
☐ Estimated or ☐ MeasuredD. Well Construction began: April 28, 1999.E. Well Construction completed: June 1, 1999.F. Bore hole diameter: 8 1/4 inches.G. Plain Casing: Diameter 2.469 ID2.875 OD inches.Type of material: PVC Schedule 40.Wall thickness: 0.203 inch(es).Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

±3 ft.to 61 ft.

from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:type of material PVC Schedule 40Screen Openings (slot size) 0.010Trade Name: Titan Industries

Length(s) and placement(s) depth from

61 ft.to 71 ft.

from _____ ft. to _____ ft.

guides at 60 ft.I. Gravel pack interval(s) from 58 ft.to 72.5 ft.

from _____ ft. to _____ ft.

Grade size: Armour coatJ. Grouted/Sealed from 0 ft.to 3 ft.,with Steel cover in concrete

(type)

from 3 ft.to 58 ft.,with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotaryL. Drilling fluid: Super Gel-XM. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>2.5</u>	<u>Topsoil, dark brown</u>
<u>2.5</u>	<u>21</u>	<u>Clay, sandy, silty with sand lenses</u>
<u>21</u>	<u>30</u>	<u>Sand, fine & gravel, medium</u>
<u>30</u>	<u>32</u>	<u>Clay, yellowish brown</u>
<u>32</u>	<u>41</u>	<u>Sand, fine to coarse, some gravel</u>
<u>41</u>	<u>51</u>	<u>Clay, sandy, light brown</u>
<u>51</u>	<u>65</u>	<u>Sand, coarse & gravel</u>
<u>65</u>	<u>85</u>	<u>Interbedded clayey silt & sand, fine to coarse</u>
<u>85</u>	<u>90</u>	<u>Sand, coarse & gravel, coarse</u>
<u>90</u>	<u>115</u>	<u>Sand, fine with rootlets</u>
<u>115</u>	<u>130</u>	<u>Interbedded sandstone & sand</u>
<u>130</u>	<u>139</u>	<u>Clay, silty</u>

Depth in Feet		Description
From	To	
<u>139</u>	<u>160</u>	<u>Clay, chalky, white to yellow</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313

State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805

Contractor's License No. 39070

State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

6. A. Well location: NW 1/4 of the NW 1/4 of Section 22, Township 28 North, Range 3 ☐ East ☒ West, Pierce County.
B. The well is 498 feet from the ☒ North or ☐ South section line and 34 feet from the ☐ East or ☒ West section line.
C. Street address or block, lot and subdivision, if applicable: Site 2-99 (Gansebom), TH # 7-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 3D (Center)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.

Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No.

8. Well Construction Information.

A. Total well depth: 132 feet.B. Static water level: 9.5 feet.C. Pumping water level: _____ feet.
☐ Estimated or ☐ MeasuredD. Well Construction began: April 29, 1999.E. Well Construction completed: June 1, 1999.F. Bore hole diameter: 7 1/8 inches.G. Plain Casing: Diameter 2.469 ID2.875 OD inches.Type of material: PVC Schedule 40.Wall thickness: 0.203 inch(es).Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+ 3.5 ft.to 126 ft.

from _____ ft.

to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:type of material PVC Schedule 40Screen Openings (slot size) 0.010Trade Name: Titan Industries

Length(s) and placement(s) depth from

126 ft.to 131 ft.

from _____ ft. to

guides at 125 ft.I. Gravel pack interval(s) from 122 ft.to 132 ft.

from _____ ft.

to _____ ft.

Grade size: 10/20J. Grouted/Sealed from 0 ft.to 3 ft.,with Steel cover in concrete

(type)

from 3 ft.to 122 ft.,with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotaryL. Drilling fluid: Super Gel-XM. Well development technique (total time and method): Water jetting .75 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet

From	To	Description
<u>0</u>	<u>2.5</u>	<u>Topsoil, dark brown</u>
<u>2.5</u>	<u>21</u>	<u>Clay, silty, sandy with sand lenses</u>
<u>21</u>	<u>30</u>	<u>Sand, fine & gravel</u>
<u>30</u>	<u>32</u>	<u>Clay, yellowish brown</u>
<u>32</u>	<u>41</u>	<u>Sand, fine to coarse & some gravel</u>
<u>41</u>	<u>51</u>	<u>Clay, sandy, light brown</u>
<u>51</u>	<u>65</u>	<u>Sand, coarse & gravel</u>
<u>65</u>	<u>85</u>	<u>Interbedded clayey Silt & sand, fine to coarse</u>
<u>85</u>	<u>90</u>	<u>Sand, coarse & gravel, coarse</u>
<u>90</u>	<u>115</u>	<u>Sand, fine with rootlets</u>
<u>115</u>	<u>130</u>	<u>Interbedded sandstone & sand</u>
<u>130</u>	<u>139</u>	<u>Clay, silty</u>

Depth in Feet

From	To	Description
<u>139</u>	<u>160</u>	<u>Clay, chalky, white to yellow</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature _____

Date _____

Water Well Owner's Signature _____

Date _____

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD PII	Well Number 35	Date Drilled 4/29/99	Date Constructed 4/29/99	Ground Elevation 1675(6)
County PIERCE	Qtr/Qtr/Qtr NW NW NW	Section 22	Township 20N	Range 3W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By [Signature]	Total Depth 30

Borehole Diameter 8 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 24-ft
Type/Size of Screen 2 1/2" ID SCH 40 10-ft
Screen Slot Size 0.010
Filter Pack AX GRAVEL 7 BUCKETS
Type/Amount Grout/Fill BENSEAL/EZ-MUD N/A
Type/Amount Seal 6.5 BAGS HOLE PLUG

Elevation Depth
From
Reference

3.5 TOP OF CASING

0.0 GROUND

3 TOP OF
GROUT/FILL


8.7 WATER LEVEL

17 TOP OF FILTER PACK

20 TOP OF SCREEN

30 BOTTOM OF SCREEN

30 BOREHOLE DEPTH



NORTH WELL - -

SITE # 2-99


CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LEND PII	Well Number 3M	Date Drilled 4/28/99	Date Constructed 4/28/99	Ground Elevation 1675(±)
County PIERCE	Qtr/Qtr/Qtr NW NW NW	Section 22	Township 28N	Range 3W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By <i>Gal</i>	Total Depth 72.5

Borehole Diameter 8 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 64 ft
Type/Size of Screen 2 1/2" ID SCH 40 10-ft
Screen Slot Size 0.010
Filter Pack AX GRAVEL 6.5 BUCKETS
Type/Amount Grout/Fill BENSEAL/EE-MUD 4 BAGS ± 160 GAL.
Type/Amount Seal 56-58' 1 BAG H.P.

Elevation	Depth From Reference
<u>3</u>	TOP OF CASING
<u>0.0</u>	GROUND
<u>3</u>	TOP OF GROUT/FILL
<u>9.5</u>	WATER LEVEL
<u>58</u>	TOP OF FILTER PACK
<u>61</u>	TOP OF SCREEN
<u>71</u>	BOTTOM OF SCREEN
<u>72.5</u>	BOREHOLE DEPTH



SOUTH WELL

SITE # 2-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD P II	Well Number 3D	Date Drilled 4/29/99	Date Constructed 4/29/99	Ground Elevation 1675(E)
County PIERCE	Qtr/Qtr/Qtr NWNW NW	Section 22	Township 28 N	Range 2W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By <i>Shol</i>	Total Depth 132

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED
130 FEET
Type/Size of Screen 2 1/2" ID SCH 40
5-ft
Screen Slot Size 0.010
Filter Pack 10/20 SiSd 6-BAGS
Type/Amount Grout/Fill BENSEAL/EE-MUD 6 BAGS 240 gal.
Type/Amount Seal 118'-122' - 1BAG H.P. 3'-7' - HOLE PLUG

Elevation Depth
 From
 Reference

4 +/- TOP OF CASING

0.0 GROUND

3 TOP OF
 GROUT/FILL


9.7 WATER LEVEL

122 TOP OF FILTER PACK

126 TOP OF SCREEN

131 BOTTOM OF SCREEN

132 BOREHOLE DEPTH



CENTER WELL


Number 4 Wells

PIERCE COUNTY

TH # 1-LE-99

#4 WELLS

HILKEMAN SITE



T 25N R 1W SECTION 18 NW 1/4

WREETOWN ROAD

Test Hole #1-LE-99 (E-log)
(25N-1W-18baba)
Pierce County


Location: NE NW NE NW Sec. 18, T. 25 N., R. 1 W., approximately 1,662 feet east and 87 feet south of northwest corner.

Ground elevation: 1,560 ft. (t) (Weetown, 7.5 min. quadrangle)

Depth to water: 5.7 ft. (5/17/99). Wells installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Top soil: silt, very sandy, slightly clayey, dark grayish brown; sand is very fine to medium.....	0.0	1.0
Sand, very silty, slightly clayey, slightly calcareous, grayish brown; sand is very fine to medium..	1.0	2.0
Silt, moderately sandy, slightly clayey, moderately calcareous, gray; sand is very fine to fine, little medium; dark gray below 10 ft.....	2.0	11.0
Sand, moderately silty, gray; sand is very fine to fine.....	11.0	12.0
Silt, soil like; moderately clayey, moderately sandy, gray; sand is very fine to fine, little medium.....	12.0	15.0
Soil: silt, very clayey, moderately sandy, moderately calcareous, very dark gray; sand is very fine to fine.....	15.0	20.5
Sand, gravelly; very fine sand to fine gravel; contains many dark silicates.....	20.5	25.0
Gravel, sandy; very fine sand to coarse gravel; contains many dark silicates.....	25.0	30.0
Sand, gravelly; very fine sand to very fine gravel, little fine to medium gravel; many dark silicates.	30.0	35.5
Silt, moderately sandy, slightly clayey, slightly calcareous, dark gray; sand is very fine.....	35.5	37.0
Sand, slightly silty; sand is very fine to coarse; contains many quartz, some dark silicates, and trace limestone grains.....	37.0	40.0
Sand, slightly silty; sand is very fine to coarse, little very coarse sand to fine gravel; contains many quartz, dark silicates and feldspars grains; slightly more fine gravel with a trace of medium gravel below 45 ft.....	40.0	60.0
Sand, very fine to coarse, little very fine to fine gravel; contains quartz, red and green silicates, few limy grains, and red and green feldspars.....	60.0	76.0
Silt, very sandy, slightly clayey, slightly calcar-		

eous, olive brown; sand is very fine.....	76.0	80.0
Sand, very fine to very coarse, little fine gravel; contains much quartz, dark and green silicates....	80.0	86.0
Silt, very clayey, very sandy, light tan; sand is very fine.....	86.0	88.0
Sand, very fine to coarse, little very coarse sand to very fine gravel; quartz, feldspars, and dark silicates.....	88.0	90.0
Sand, slightly gravelly; very fine sand to fine gravel; interbedded clay lens; contains quartz, feldspars and silicates.....	90.0	95.0
Sand, gravelly; very fine sand to fine gravel, little medium gravel; contains quartz, red and dark silicates.....	95.0	100.0
Sand, very fine to coarse, little very coarse sand, rare fine gravel; contains quartz, dark and green silicates.....	100.0	105.0
Tertiary System - Miocene Series - Ogallala Group:		
Silt, very sandy, slightly clayey, light olive gray; sand is very fine to fine.....	105.0	115.0
Sand, very fine to fine, some medium; light gray....	115.0	131.0
Silt, very sandy, moderately clayey, light gray; sand is very fine to fine, some medium.....	131.0	139.0
Sand, very fine to fine; light gray.....	139.0	141.0
Silt, very sandy, slightly clayey, light brown; sand is very fine to fine; light brown gray below 141.5 ft.....	141.0	145.0
Sand, very fine to fine, trace of medium; few root- let fragments.....	145.0	156.0
Silt, very sandy, slightly clayey, light gray; sand is very fine to fine; contains interbedded silt and silty sand lenses below 160 ft.....	156.0	167.5
Silt, very sandy, slightly clayey, light gray; sand is very fine to fine.....	167.5	170.0
Sand, silty, gray; sand is very fine; contains silty clay ball fragments.....	170.0	180.0
Sandstone, in part very silty, slightly clayey, brown; sand is very fine grained.....	180.0	192.0
Cretaceous System - Upper Cretaceous Series - Colorado Group:		
Niobrara Formation:		
Chalk, white.....	192.0	195.0
Clay, in part chalk, gray; contains ironstone and chert fragments.....	195.0	196.5
Clay shale, slightly calcareous, gray; contains some sand grains; moderately calcareous below 200 ft...	196.5	205.0
Clay shale, very calcareous, dark gray; moderately calcareous below 210 ft.....	205.0	220.0



Century GEOPHYSICAL CORP.

1-1e-99

COMPANY : GROSCH
WELL : 1-1e-99
LOCATION/FIELD : site 9
COUNTY : pierce
STATE : ne
SECTION : 18

OTHER SERVICES:

caliper
Uncalib
downhole

TOWNSHIP : 25 RANGE : 1W

DATE : 04/12/99
DEPTH DRILLER : 220
LOG BOTTOM : 218.08
LOG TOP : 1.91

PERMANENT DATUM : None

KB : None
DF : None
GL : 1560

LOG MEASURED FROM: grd
DRL MEASURED FROM: +2

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : Sol

BIT SIZE : 5
MAGNETIC DECL : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite


BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54

FILE : PROCESSED
TYPE : 8043A

THRESH: 2500

Weetown Quad
Wells 4S, 4M, & 4D

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS



TEST # 1-LE-99

W SITE 9-99

Pierce, Co. 93-94
T-25-N R-1-W 60

Photo J12
Sec. 18

N1
3
91.5

NC

1321
T55
1/2

NHEL
38.6


1219
T997

NHEL
46.7

NHE
4
3.9

320
T60
1/1

NHE
14.



STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk
Telephone Number (402) 371-7313
State NE Zip Code 68701 +
2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill
Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +
3. Permit Number(s) _____
4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)
5. Replacement and abandoned well information.
A. Is this well a replacement well? ☐ Yes ☒ No
B. Replacement well is _____ feet from abandoned well
C. Original well pump column size: _____ inches.
D. Abandoned well last operated _____,
E. Location of water use of abandoned well:
F. Completion of original well abandonment on _____.
6. A. Well location: NE 1/4 of the NW 1/4 of Section 18, Township 25 North, Range 1 ☐ East ☒ West, Pierce County.
B. The well is 69 feet from the ☒ North or ☐ South section line and 1590 feet from the ☐ East or ☒ West section line.
C. Street address or block, lot and subdivision, if applicable: Site # 9-99 (Hulkeman), TH # 1-LE-99
D. Location of water use, if applicable (give legal descriptions):
E. If for irrigation, the land to be irrigated is _____ acres.
F. Well reference letter(s), if applicable: Well LE # 4S (West)
7. Pump Information.
Is pump installed at this time? ☐ Yes ☒ No
If yes, complete items A through F.
If no, complete items A and D with estimated information for those wells in which pump will be installed.
A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒
B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.
D. Pumping equipment-date installed: August, 1999. E. Brand/Type: Grundfos Rediflo2
F. Pump installed by: Contractor ☐ Owner ☒ Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 30.5 feet.

B. Static water level: 8 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: April 30, 1999.

E. Well Construction completed: June 7, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID 2.875 OD inches. Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es). Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from +1.5 ft. to 20 ft. from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in: type of material PVC Schedule 40

Screen Openings (slot size) 0.010 Trade Name: Titan Industries

Length(s) and placement(s) depth from 20 ft. to 30 ft. from _____ ft. to _____ ft. guides at _____ ft.

I. Gravel pack interval(s) from 17 ft. to 30.5 ft. from _____ ft. to _____ ft. Grade size: Armour coat

J. Grouted/Sealed from 0 ft. to 3 ft., with Steel cover in concrete
(type)

from 3 ft. to 17 ft., with Benseal/EZ-Mud
(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .25 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? ☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>13</u>	<u>Topsoil; sand, fine</u>
<u>13</u>	<u>22</u>	<u>Silt, clayey, sandy, dark gray</u>
<u>22</u>	<u>33</u>	<u>Sand, medium to coarse & gravel, medium to coarse</u>
<u>33</u>	<u>39</u>	<u>Silt, clayey, slightly sandy, dark gray</u>
<u>39</u>	<u>74</u>	<u>Sand, coarse; gravel, coarse, red & green</u>
<u>74</u>	<u>78</u>	<u>Silt, clayey</u>
<u>78</u>	<u>84</u>	<u>Sand, very coarse & some gravel</u>
<u>34</u>	<u>88</u>	<u>Clay, very sandy, light tan</u>
<u>88</u>	<u>95</u>	<u>Sand & gravel, some silt layers</u>
<u>95</u>	<u>133</u>	<u>Interbedded sand, very fine to fine & silt, light olive gray</u>
<u>133</u>	<u>142</u>	<u>Silt, sandy; sand very fine to fine</u>

Depth in Feet		Description
From	To	
<u>142</u>	<u>154</u>	<u>Sand, very fine & rootlets</u>
<u>154</u>	<u>170</u>	<u>Silt, sandy, light olive gray with some very fine sand layers</u>
<u>170</u>	<u>192</u>	<u>Sand with many thin silt layers</u>
<u>192</u>	<u>194.5</u>	<u>Clay, very silty, white to gray</u>
<u>194.5</u>	<u>220</u>	<u>Shale, chalky, iron stained on top, gray</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313

State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805

Contractor's License No. 39070

State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

6. A. Well location: NE 1/4 of the NW 1/4 of Section 18, Township 25 North, Range 1 ☐ East ☒ West, Pierce County.

B. The well is 70 feet from the ☒ North or ☐ South section line and 1603 feet from the ☐ East or ☒ West section line.

C. Street address or block, lot and subdivision, if applicable: Site # 9-99 (Hilkeman), TH # 1-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 4M (Center)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.

Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No.

8. Well Construction Information.

A. Total well depth: 77 feet.

B. Static water level: 6.0 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: April 9, 1999.

E. Well Construction completed: June 7, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID 2.875 OD inches. Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from +1.5 ft. to 66 ft. from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from 66 ft. to 76 ft. from _____ ft. to _____ ft. guides at 64 ft.

I. Gravel pack interval(s) from 60 ft. to 77 ft. from _____ ft. to _____ ft. Grade size: 10/20

J. Grouted/Sealed from 0 ft. to 3 ft., with Steel cover in concrete
 (type)

from 3 ft. to 60 ft., with Benseal/EZ-Mud
 (type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? ☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet

From	To	Description
<u>0</u>	<u>13</u>	<u>Topsoil; sand, fine</u>
<u>13</u>	<u>22</u>	<u>Silt, clayey, sandy, dark gray</u>
<u>22</u>	<u>33</u>	<u>Sand, medium to coarse & gravel, medium to coarse</u>
<u>33</u>	<u>39</u>	<u>Silt, clayey, slightly sandy, dark gray</u>
<u>39</u>	<u>74</u>	<u>Sand, coarse; gravel, coarse, red & green</u>
<u>74</u>	<u>78</u>	<u>Silt, clayey</u>
<u>78</u>	<u>84</u>	<u>Sand, very coarse & some gravel</u>
<u>84</u>	<u>88</u>	<u>Clay, very sandy, light tan</u>
<u>88</u>	<u>95</u>	<u>Sand & gravel, some silt layers</u>
<u>95</u>	<u>133</u>	<u>Interbedded sand, very fine to fine & silt, light olive gray</u>
<u>133</u>	<u>142</u>	<u>Silt, sandy; sand very fine to fine</u>

Depth in Feet

From	To	Description
<u>142</u>	<u>154</u>	<u>Sand, very fine & rootlets</u>
<u>154</u>	<u>170</u>	<u>Silt, sandy, light olive gray with some very fine sand layers</u>
<u>170</u>	<u>192</u>	<u>Sand with many thin silt layers</u>
<u>192</u>	<u>194.5</u>	<u>Clay, very silty, white to gray</u>
<u>194.5</u>	<u>220</u>	<u>Shale, chalky, iron stained on top, gray</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313
State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

6. A. Well location: NE 1/4 of the NW 1/4 of Section 18, Township 25 North, Range 1 ☐ East ☒ West, Pierce County.

B. The well is 71.5 feet from the ☒ North or ☐ South section line and 1616 feet from the ☐ East or ☒ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 9-99 (Hilkeman), TH # 1-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 4D (East)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.

Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No.

3. Well Construction Information.

A. Total well depth: 156 feet.

B. Static water level: 5.7 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: April 30, 1999.

E. Well Construction completed: June 7, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID 2.875 OD inches.

Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from +1.5 ft. to 151 ft. from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from 151 ft. from 156 ft. to _____ ft. guides at 150 ft.

I. Gravel pack interval(s) from 146 ft. to 156 ft. from _____ ft. to _____ ft. Grade size: 10/20

J. Grouted/Sealed from 0 ft. to 3 ft., with Steel cover in concrete
 (type)

from 3 ft. to 146 ft., with Benseal/EZ-Mud
 (type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting 1.0 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? ☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>13</u>	<u>Topsoil; sand, fine</u>
<u>13</u>	<u>22</u>	<u>Silt, clayey, sandy, dark gray</u>
<u>22</u>	<u>33</u>	<u>Sand, medium to coarse & gravel, medium to coarse</u>
<u>33</u>	<u>39</u>	<u>Silt, clayey, slightly sandy, dark gray</u>
<u>39</u>	<u>74</u>	<u>Sand, coarse; gravel, coarse, red & green</u>
<u>74</u>	<u>78</u>	<u>Silt, clayey</u>
<u>78</u>	<u>84</u>	<u>Sand, very coarse & some gravel</u>
<u>84</u>	<u>88</u>	<u>Clay, very sandy, light tan</u>
<u>88</u>	<u>95</u>	<u>Sand & gravel, some silt layers</u>
<u>95</u>	<u>133</u>	<u>Interbedded sand, very fine to fine & silt, light olive gray</u>
<u>133</u>	<u>142</u>	<u>Silt, sandy; sand very fine to fine</u>

Depth in Feet		Description
From	To	
<u>142</u>	<u>154</u>	<u>Sand, very fine & rootlets</u>
<u>154</u>	<u>170</u>	<u>Silt, sandy, light olive gray with some very fine sand layers</u>
<u>170</u>	<u>192</u>	<u>Sand with many thin silt layers</u>
<u>192</u>	<u>194.5</u>	<u>Clay, very silty, white to gray</u>
<u>194.5</u>	<u>220</u>	<u>Shale, chalky, iron stained on top, gray</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

CONSERVATION AND SURVEY DIVISION--UNL


WELL COMPLETION LOG

Project 1999 LENRD PII	Well Number 45	Date Drilled 4/30/99	Date Constructed 4/30/99	Ground Elevation 1560(4)
County PIERCE	Qtr/Qtr/Qtr NW NE NW	Section 18	Township 25N	Range 1W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By Jol	Total Depth 30.5

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 23-ft
Type/Size of Screen 2 1/2" ID SCH 40 10-ft
Screen Slot Size 0.010
Filter Pack AX GRAVEL 5 BUCKETS
Type/Amount Grout/Fill BENSEAL/EE-MUD 1 BAG 40 GAL
Type/Amount Seal 14-17' 1 BAG HOLE PLUG

Elevation Depth
From
Reference

3	TOP OF CASING
0.0	GROUND
3	TOP OF GROUT/FILL
8.1	WATER LEVEL
17	TOP OF FILTER PACK
20	TOP OF SCREEN
30	BOTTOM OF SCREEN
30.5	BOREHOLE DEPTH




WEST WELL

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD PJH	Well Number 4M	Date Drilled 4/30/99	Date Constructed 4/30/99	Ground Elevation 1560(4)
County PIERCE	Qtr/Qtr/Qtr NW NE NW	Section 18	Township 25N	Range 1W
Drilling Co. GROECH	Method MUD ROTARY	Driller SHOLES	Log By Jaf	Total Depth 77



CENTER WELL


TH # 1-LE-99

SITE # 9-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LEND PJF	Well Number 4D	Date Drilled 4/30/99	Date Constructed 4/30/99	Ground Elevation 1560 (±)
County PIERCE	Qtr/Qtr/Qtr NW NE NW	Section 18	Township 25 N	Range 1W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By <i>Gal</i>	Total Depth 156



EAST WELL


Number 5 Wells

TH # 6-LE-99

PIERCE COUNTY

#5 WELLS

SCHOOL/WAGNER SITE



T 25N R 4W SECTION 16 SE 1/4

TILDEN NE QUAD


Test Hole #6-LE-99 (E-log)
(25N-4W-16dddd)
Pierce County

Location: SE SE SE SE Sec. 16, T. 25 N., R. 4 W., approximately
 141 feet west and 16 feet north of southeast corner.
 Ground elevation: 1,830 ft. (t) (Tilden NE, 7.5 min. quadrangle)
 Depth to water: 119.9 ft. (5/17/99) Wells installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Top soil: silt, very sandy, slightly clayey, black; sand is very fine to medium.....	0.0	0.5
Sand, very silty, slightly clayey, brown; sand is very fine to medium.....	0.5	1.0
Silt, very clayey, moderately sandy, light yellowish brown; sand is very fine.....	1.0	5.0
Clay, silty, very sandy, light yellowish brown; sand is very fine.....	5.0	16.0
Soil: clay, silty, sandy, dark yellowish brown with yellow stain.....	16.0	20.0
Clay, silty, moderately sandy, pale brown; sand is very fine.....	20.0	31.0
Silt, very sandy, moderately clayey, pale brown; sand is very fine; trace of limy grains below 35 ft.....	31.0	46.0
Silt, slightly clayey, brown; contains some very fine sand; light brownish gray below 50 ft.....	46.0	65.0
Silt, moderately sandy, slightly clayey, light yellowish brown; sand is very fine.....	65.0	70.0
Sand, very silty, brown; sand is very fine to me- dium; less silt below 80 ft.....	70.0	85.0
Sand, moderately silty, light yellowish brown; sand is very fine to fine, little medium.....	85.0	95.0
Sand, very fine to medium, trace of coarse; light yellowish brown.....	95.0	100.0
Sand, very fine to medium, yellowish brown; slightly silty from 115 to 120 ft; trace of coarse below 120 ft.....	100.0	126.0
Sand, slightly clayey, very silty, light yellowish brown.....	126.0	131.0
Sand, gravelly, slightly silty; very fine sand to fine gravel; some medium gravel below 135 ft.....	131.0	165.0
Silt, moderately clayey, sandy, light yellowish brown; sand is very fine; very coarse below 175 ft.....	165.0	180.0

Tertiary System - Miocene Series - Ogallala Group:

Sand, very fine to medium, trace of coarse; light gray; trace of rootlets below 185 ft.....	180.0	190.0
Sand, very silty, light gray; sand is very fine to fine, trace of medium.....	190.0	225.0
Sandstone, moderately silty, light gray; sand is very fine to fine, little medium.....	225.0	280.0
Sand, very fine to fine, trace of medium; light gray.....	280.0	330.0
Sand to sandstone; slightly silty, light gray; sand is very fine to fine, trace of medium.....	330.0	335.0
Sand, very fine to fine, trace of medium; light gray.....	335.0	369.0
Sand to sandstone, slightly silty; sand is very fine to fine, trace of medium; slightly silty below 369 ft.....	369.0	410.0
Sand, slightly gravelly; principally reworked bentonitic clay, yellow shale, ironstone, quartz; little black shale below 415 ft, probably Pierre shale.....	410.0	427.0



Century GEOPHYSICAL CORP.

6-LE-99

COMPANY : Grosch
WELL : 6-LE-99
LOCATION/FIELD : Site 7
COUNTY : PIERCE
STATE : NE
SECTION : 16

OTHER SERVICES:

caliphe
downhole
None

TOWNSHIP : 25 RANGE : 4W

DATE : 04/26/99
DEPTH DRILLER : 427
LOG BOTTOM : 396.29
LOG TOP : 2.55

PERMANENT DATUM : None

LOG MEASURED FROM: grnd0
DRL MEASURED FROM: +2

KB : None
DF : None
GL : 1830

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : sol

BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite


BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54

FILE : PROCESSED
TYPE : 8043A

THRESH: 2500

Tilden NE Quad
Wells 5M & 5D

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS



NOT TO SCALE

Pierce, Co.
T-25-N R-4-W
TH #6-LE-99

93-94
15

Photo B12
Sec. 16
SITE # 7-99

1025
T1912
1/1

NHEL INW

1 15.3

NHEL INW

2 12.3

NHEL INW

3 11.7

NHEL INW

4 11.1

NHEL INW

5 47.9

HEL INW

6 153.9

6B
5.0

6C
135.0

6D
6.7

NHEL INW

7 48.8

NC

NC

NHEL

8 67.6

NC

HEL INW

9 31.3

NC

Well LE #5M

Well LE #5D

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313
State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

5. A. Well location: SE 1/4 of the SE 1/4 of Section 16, Township 25 North, Range 4 ☐ East ☒ West, Pierce County.

B. The well is 23.5 feet from the ☐ North or ☒ South section line and 97 feet from the ☒ East or ☐ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 7-99 (School), TH # 6-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 5M (East)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999. E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒ Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 167 feet.

B. Static water level: 120 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: May 3, 1999.

E. Well Construction completed: June 15, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID 2.875 OD inches. Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es). Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from +1.5 ft. to 157 ft. from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in: type of material PVC Schedule 40

Screen Openings (slot size) 0.010 Trade Name: Titan Industries

Length(s) and placement(s) depth from 157 ft. to 167 ft. from _____ ft. to _____ ft. guides at 155 ft.

I. Gravel pack interval(s) from 150 ft. to 167 ft. from _____ ft. to _____ ft. Grade size: Armour coat

J. Grouted/Sealed from 0 ft. to 3 ft., with Steel cover in concrete
 (type)

from 3 ft. to 150 ft., with Benseal/EZ-Mud
 (type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting 1.25 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? ☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>1</u>	<u>Topsoil, sandy</u>
<u>1</u>	<u>42</u>	<u>Silt, clayey, light brown to dark brown</u>
<u>42</u>	<u>72</u>	<u>Interbedded silt & sand</u>
<u>72</u>	<u>85</u>	<u>Sand, fine to medium; some silt & clay</u>
<u>85</u>	<u>93</u>	<u>Silt, clayey</u>
<u>93</u>	<u>100</u>	<u>Sand, medium</u>
<u>100</u>	<u>104</u>	<u>Silt</u>
<u>104</u>	<u>123</u>	<u>Interbedded sand & silt</u>
<u>123</u>	<u>131</u>	<u>Silt</u>
<u>131</u>	<u>166</u>	<u>Sand, coarse to gravel, medium</u>
<u>166</u>	<u>181</u>	<u>Silt, clayey, sandy</u>
<u>181</u>	<u>192</u>	<u>Sand, fine to medium</u>

Depth in Feet		Description
From	To	
<u>192</u>	<u>206</u>	<u>Silt, clayey, sandy, olive</u>
<u>206</u>	<u>225</u>	<u>Sand & sandstone, some silt</u>
<u>225</u>	<u>251</u>	<u>Interbedded silty clay & sand</u>
<u>251</u>	<u>333</u>	<u>Interbedded sand & sandstone; sand, very fine to fine, some silty</u>
<u>333</u>	<u>345</u>	<u>Interbedded silt & silty clay</u>
<u>345</u>	<u>366</u>	<u>Interbedded sand & sandstone, with silt layers</u>
<u>366</u>	<u>406</u>	<u>Sand, very silty, very fine</u>
<u>406</u>	<u>427</u>	<u>Shale, weathered; ironstone</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313
State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well: _____

6. A. Well location: SE 1/4 of the SE 1/4 of Section 16, Township 25 North, Range 4 ☐ East ☒ West, Pierce County.

B. The well is 22.5 feet from the ☐ North or ☒ South section line and 152 feet from the ☒ East or ☐ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 7-99 (School), TH # 6-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 5D (West)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 262 feet.

B. Static water level: 120.4 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: May 12, 1999.

E. Well Construction completed: June 15, 1999.

F. Bore hole diameter: 8 inches.

G. Plain Casing: Diameter 2.469 ID 2.875 OD inches. Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es). Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from +1.5 ft. to 256 ft. from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in: type of material PVC Schedule 40

Screen Openings (slot size) 0.010 Trade Name: Titan Industries

Length(s) and placement(s) depth from 256 ft. to 261 ft. from _____ ft. to _____ ft. guides at 255 ft.

I. Gravel pack interval(s) from 252 ft. to 262 ft. from _____ ft. to _____ ft. Grade size: 10/20

J. Grouted/Sealed from 0 ft. to 3 ft., with Steel cover in concrete
(type)

from 3 ft. to 252 ft., with Benseal/EZ-Mud
(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting 1.0 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? ☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		
From	To	Description
<u>0</u>	<u>1</u>	<u>Topsoil, sandy</u>
<u>1</u>	<u>42</u>	<u>Silt, clayey, light brown to dark brown</u>
<u>42</u>	<u>72</u>	<u>Interbedded silt & sand</u>
<u>72</u>	<u>85</u>	<u>Sand, fine to medium, some silt & clay</u>
<u>85</u>	<u>93</u>	<u>Silt, clayey</u>
<u>93</u>	<u>100</u>	<u>Sand, medium</u>
<u>100</u>	<u>104</u>	<u>Silt</u>
<u>104</u>	<u>123</u>	<u>Interbedded sand & silt</u>
<u>123</u>	<u>131</u>	<u>Silt</u>
<u>131</u>	<u>166</u>	<u>Sand, coarse to gravel, medium</u>
<u>166</u>	<u>181</u>	<u>Silt, clayey, sandy</u>
<u>181</u>	<u>192</u>	<u>Sand, fine to medium</u>

Depth in Feet		
From	To	Description
<u>192</u>	<u>206</u>	<u>Silt, clayey, sandy, olive</u>
<u>206</u>	<u>225</u>	<u>Sand & sandstone, some silt</u>
<u>225</u>	<u>251</u>	<u>Interbedded silty clay & sand</u>
<u>251</u>	<u>333</u>	<u>Interbedded sand & sandstone; Sand, very fine to fine, some silty</u>
<u>333</u>	<u>345</u>	<u>Interbedded silt & silty clay</u>
<u>345</u>	<u>366</u>	<u>Interbedded sand & sandstone with silt layers</u>
<u>366</u>	<u>406</u>	<u>Sand, very silty, very fine</u>
<u>406</u>	<u>427</u>	<u>Shale, weathered, ironstone</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

TH # 6-LE-99

SITE # 7-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD PII	Well Number 5M	Date Drilled 5/3/99	Date Constructed 5/3/99	Ground Elevation 1830(E)
County PIERCE	Qtr/Qtr/Qtr SE SE SE	Section 16	Township 25N	Range 4W
Drilling Co. GROSCAT	Method MUD ROTARY	Driller SHOLES	Log By <i>Gal</i>	Total Depth 167.5

Borehole Diameter

7 1/8"

Survey Reference

Type/Size of Casing

2 1/2" ID SCH 40
FLUSH/THREADED

160 ft

Type/Size of Screen

2 1/2" ID SCH 40

10-ft

Screen Slot Size

0.010

Filter Pack

AX GRAVEL

5 BUCKETS

Type/Amount Grout/Fill

BENSEAL/EZ-MUD

6 BAGS

240 GAL

Type/Amount Seal

147-150' 1-BAG

HOLE PLUG

Elevation Depth
From
Reference

3

TOP OF CASING

0.0

GROUND

3TOP OF
GROUT/FILL119.9

WATER LEVEL

150

TOP OF FILTER PACK

157

TOP OF SCREEN

147

BOTTOM OF SCREEN

167.5

BOREHOLE DEPTH

LOCKING, STEEL
PROTECTIVE COVER

TOP CAP

CONCRETE
SURFACE SEAL

GROUT OR FILL

WELL CASING

FILTER PACK

WELL SCREEN

BOTTOM CAP

6/28 DEN 1.5 hr

EAST WELL

TH # 6-LE-99

SITE # 7-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD PII	Well Number 5D	Date Drilled 5/12/98	Date Constructed 5/12/98	Ground Elevation 1830(t)
County PIERCE	Qtr/Qtr/Qtr SE SE SE	Section 16	Township 25N	Range 4W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By <i>Qaf</i>	Total Depth 262

Borehole Diameter 8 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 260-ft
Type/Size of Screen 2 1/2" ID SCH 40 5-ft
Screen Slot Size 0.010
Filter Pack 20/40 SS SD + 16 BAGS
Type/Amount Grout/Fill BENSEAL/EZ-MUD 11 BAGS 440 GAL
Type/Amount Seal N/A

Elevation Depth
From
Reference4 1/2 TOP OF CASING0.0 GROUND3 TOP OF
GROUT/FILL120.4 WATER LEVEL252 TOP OF FILTER PACK256 TOP OF SCREEN261 BOTTOM OF SCREEN262 BOREHOLE DEPTHLOCKING, STEEL
PROTECTIVE COVER

TOP CAP

CONCRETE
SURFACE SEAL

GROUT OR FILL

WELL CASING

FILTER PACK

WELL SCREEN

BOTTOM CAP

5/28 DEV 1hr

WEST WELL


Number 6 Wells

PIERCE COUNTY

TH # 5-LE-99

6 WELLS

NOESCH SITE



T26N R4W SECTION 36 SW 1/4

PIERCE NW QUAD

Test Hole #5-LE-99 (E-log)
(26N-4W-36ccbc)
Pierce County


Location: SW NW SW SW Sec. 36, T. 26 N., R. 4 W., approximately
949 feet north and 33.5 feet east of southwest corner.

Ground elevation: 1,705 ft. (t) (Pierce NW, 7.5 min. quadrangle)

Depth to water: 7.0 ft. (5/5/99) Wells installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Top soil: silt, very sandy, slightly clayey, black; sand is very fine to medium, few coarser grains...	0.0	0.5
Sand, moderately clayey; sand is very fine to medium; light brown.....	0.5	3.0
Silt, very sandy, moderately clayey, dark brown; sand is very fine to medium; brown below 5 ft.....	3.0	8.0
Sand, very silty, grayish brown; sand is very fine to medium, little coarse.....	8.0	10.0
Sand, very fine to coarse, little very fine gravel; brown.....	10.0	15.0
Sand, gravelly; very fine sand to fine gravel; brown; contains little medium gravel below 25 ft..	15.0	30.0
Sand, very fine to very coarse, little fine gravel; brown; trace of coarse gravel from 35 to 40 ft; little medium and coarse gravel below 40 ft.....	30.0	45.0
Sand, gravelly; very fine sand to fine gravel, little medium gravel; contains trace of coarse gravel below 50 ft.....	45.0	53.0
Sand, very fine to medium, little coarse to very coarse, trace of fine gravel.....	53.0	55.0
Sand, gravelly; very fine sand to fine gravel, trace of medium gravel; gray.....	55.0	60.0
Sand, gravelly; very fine sand to medium gravel; gray; contains trace of coarse gravel below 65 ft.	60.0	67.0
Clay, brown.....	67.0	70.0
Silt, moderately clayey, moderately sandy, brown; sand is very fine; moderately calcareous below 90 ft.....	70.0	95.0
Silt, moderately clayey, brown; moderately calcar- eous from 103 to 105 ft; very calcareous below 105 ft.....	95.0	110.0
Silt, very clayey, brown; slightly calcareous from 110 to 115 ft.....	110.0	128.0
Sand, very silty, slightly clayey, brown; sand is very fine to very coarse.....	128.0	130.0

Silt, moderately clayey, moderately sandy, brown; sand is very fine.....	130.0	140.0
Sand, very fine to fine; gray.....	140.0	145.0
Sand, gravelly; very fine sand to fine gravel, little medium gravel; trace of medium gravel below 155 ft; contains rare coarse gravel below 160 ft..	145.0	165.0
Tertiary System - Miocene Series - Ogallala Group:		
Sand, very fine to medium; some coarser grains from above.....	165.0	204.0
Sandstone, very fine to fine grained; gray; contains few rootlet fragments.....	204.0	230.0
Silt, very sandy, slightly clayey, olive gray; sand is very fine.....	230.0	240.0
Sandstone, silty; very fine grained, olive gray; contains trace of rootlet fragments; contains bentonite clay fragments from 265 to 270 ft.....	240.0	282.0
Sand, silty, clayey, gravelly; fine sand to medium gravel; principally reworked sandstone, bentonitic clay, quartz, dark silicates, much limestone and Niobrara fragments below 317 ft.....	282.0	319.0



Century GEOPHYSICAL CORP.

5-1e-99

COMPANY : GROSCH
WELL : 5-1e-99
LOCATION/FIELD : site 6
COUNTY : pierce
STATE : ne
SECTION : 36

OTHER SERVICES:

downhole
None
None

TOWNSHIP : 26 RANGE : 4W

DATE : 04/20/99
DEPTH DRILLER : 319
LOG BOTTOM : 317.80
LOG TOP : 2.19

PERMANENT DATUM : None

LOG MEASURED FROM: grd KB :
DRL MEASURED FROM: +2 DF : None
GL : 1705

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : Sol

BIT SIZE : 5
MAGNETIC DECL : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite

BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54


FILE : PROCESSED
TYPE : 8043A

THRESH: 2500

* PIERCE NW
~~Meadow Grove~~ Quad
Wells 6S, 6M, & 6D

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS

* *Ed 11/99*



NHEL

NOT TO SCALE

Pierce, Co. 93-94
T-26-N R-4-W 115

Photo C10
Sec. 36

TH #5-LE-99

5 NEG-99

NC

20.1

W IE 5.0

3B
1.2

3C
1.2

3471
T1655
2/3

2830
T5850
2/2

3872
T1079
1/4

TRANSFERRED
to
MADISON Co
1994

NC

NC

3870
T1497
2/4

162
T1078
1/1

NC

NC

NC

NC

3033
T1653
1/3

NC

NW

NC

2828
T1644 WELL LE #65
2/3 WELL LE #6M
WELL LE #6D

NHEL
83.4

NHELINW
2
15.4

NC

NC

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313
State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

6. A. Well location: SW 1/4 of the SW 1/4 of Section 36, Township 26 North, Range 4 ☐ East ☒ West, Pierce County.

B. The well is 965 feet from the ☐ North or ☒ South section line and 22 feet from the ☐ East or ☒ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 6-99 (Nuesch), TH # 5-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 6S (North)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999. E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒ Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 66 feet.

B. Static water level: 7.0 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: May 5, 1999.

E. Well Construction completed: June 15, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID

2.875 OD inches.

Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+1.5 ft.

to 56 ft.

from _____ ft.

to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from

56 ft.

to 66 ft.

from _____ ft. to

guides at 55 ft.

I. Gravel pack interval(s) from 52 ft.

to 56 ft.

from _____ ft.

to _____ ft.

Grade size: Armour Coat

J. Grouted/Sealed from 0 ft.

to 3 ft.,

with Steel cover in concrete

(type)

from 3 ft.

to 52 ft.,

with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>3</u>	<u>Topsoil & sand, very fine to medium</u>
<u>3</u>	<u>8</u>	<u>Silt, very sandy, dark brown</u>
<u>8</u>	<u>67</u>	<u>Sand, medium to gravel, medium</u>
<u>67</u>	<u>80</u>	<u>Clay, brown</u>
<u>80</u>	<u>128</u>	<u>Silt, light brown</u>
<u>128</u>	<u>130</u>	<u>Sand, very fine to very coarse, moderately silty</u>
<u>130</u>	<u>136</u>	<u>Silt, pale brown</u>
<u>136</u>	<u>164</u>	<u>Sand, very fine to gravel, medium</u>
<u>164</u>	<u>204</u>	<u>Sand, very fine to fine; some silt, brown</u>
<u>204</u>	<u>210</u>	<u>Silt, clayey, sandy, olive</u>
<u>210</u>	<u>230</u>	<u>Interbedded sand and sandstone</u>
<u>230</u>	<u>245</u>	<u>Interbedded silt & siltstone, sandy</u>

Depth in Feet		Description
From	To	
<u>245</u>	<u>282</u>	<u>Sandstone with some silt layers</u>
<u>282</u>	<u>317</u>	<u>Clay, gray</u>
<u>317</u>	<u>319</u>	<u>Limestone, white</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313
State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

- A. Is this well a replacement well? ☐ Yes ☒ No
C. Replacement well is _____ feet from abandoned well
E. Original well pump column size: _____ inches.
G. Location of water use of abandoned well: _____
D. Abandoned well last operated _____
F. Completion of original well abandonment on _____

6. A. Well location: SW 1/4 of the SW 1/4 of Section 36, Township 26 North, Range 4 ☐ East ☒ West, Pierce County.
B. The well is 953 feet from the ☐ North or ☒ South section line and 23 feet from the ☐ East or ☒ West section line.
C. Street address or block, lot and subdivision, if applicable: Site 6-99 (Nuesch), TH # 5-LE-99

D. Location of water use, if applicable (give legal descriptions):
E. If for irrigation, the land to be irrigated is _____ acres.
F. Well reference letter(s), if applicable: Well LE # 6M (Center)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

- A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒
B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.
D. Pumping equipment-date installed: August, 1999. E. Brand/Type: Grundfos Rediflo2
F. Pump installed by: Contractor ☐ Owner ☒ Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 160 feet.B. Static water level: 10.3 feet.C. Pumping water level: _____ feet.
☐ Estimated or ☐ MeasuredD. Well Construction began: May 10, 1999.E. Well Construction completed: June 15, 1999.F. Bore hole diameter: 7 1/8 inches.G. Plain Casing: Diameter 2.469 ID2.875 OD inches.Type of material: PVC Schedule 40.Wall thickness: 0.203 inch(es).Joints--Welded/Glued/Threaded/Other: ThreadedLength(s) and placement(s) depth from +1.5 ft. to 149 ft. from _____ ft. to _____ ft.H. Screen: 2.469 ID 2.875 OD in:type of material PVC Schedule 40Screen Openings (slot size) 0.010Trade Name: Titan IndustriesLength(s) and placement(s) depth from 149 ft. to 159 ft. from _____ ft. to _____ ft. guides at 147 ft.I. Gravel pack interval(s) from 145 ft. to 160 ft. from _____ ft. to _____ ft.Grade size: Armour coatJ. Grouted/Sealed from 0 ft. to 3 ft., with Steel cover in concrete
(type)from 3 ft. to 145 ft., with Benseal/EZ-Mud
(type)K. Drilling method: Mud rotaryL. Drilling fluid: Super Gel-XM. Well development technique (total time and method): Water jetting 1.0 hoursN. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? ☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>3</u>	<u>Topsoil & sand, very fine to medium</u>
<u>3</u>	<u>8</u>	<u>Silt, very sandy, dark brown</u>
<u>8</u>	<u>67</u>	<u>Sand, medium to gravel, medium</u>
<u>67</u>	<u>80</u>	<u>Clay, brown</u>
<u>80</u>	<u>128</u>	<u>Silt, light brown</u>
<u>128</u>	<u>130</u>	<u>Sand, very fine to very coarse, moderately silty</u>
<u>130</u>	<u>136</u>	<u>Silt, pale brown</u>
<u>136</u>	<u>164</u>	<u>Sand, very fine to gravel, medium</u>
<u>164</u>	<u>204</u>	<u>Sand, very fine to fine with some silts, brown</u>
<u>204</u>	<u>210</u>	<u>Silt, clayey, sandy, olive</u>
<u>210</u>	<u>230</u>	<u>Interbedded sand & sandstone</u>
<u>230</u>	<u>245</u>	<u>Interbedded silt & siltstone, sandy</u>

Depth in Feet		Description
From	To	
<u>245</u>	<u>282</u>	<u>Sandstone with some silt layers</u>
<u>282</u>	<u>317</u>	<u>Clay, gray</u>
<u>317</u>	<u>319</u>	<u>Limestone, white</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature _____

Date _____

Water Well Owner's Signature _____

Date _____

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313

State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805

Contractor's License No. 39070

State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

6. A. Well location: SW 1/4 of the SW 1/4 of Section 36, Township 26 North, Range 4 ☐ East ☒ West, Pierce County.

B. The well is 940 feet from the ☐ North or ☒ South section line and 23 feet from the ☐ East or ☒ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 6-99 (Nuesch), TH # 5-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 6D (South)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No. _____

3. Well Construction Information.

A. Total well depth: 281 feet.

B. Static water level: 13.4 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: May 11, 1999.

E. Well Construction completed: June 15, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID

2.875 OD inches.

Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+1.5 ft

. to 275 ft.

from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from

275 ft

to 280 ft.

from _____ ft. to

guides at 274 ft.

I. Gravel pack interval(s) from 270 ft.

to 281 ft.

from _____ ft. to _____ ft.

Grade size: 10/20

J. Grouted/Sealed from 0 ft.

to 3 ft.,

with Steel cover in concrete

(type)

from 3 ft.

to 270 ft.,

with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet

From	To	Description
<u>0</u>	<u>3</u>	<u>Topsoil & sand, very fine to medium</u>
<u>3</u>	<u>8</u>	<u>Silt, very sandy, dark brown</u>
<u>8</u>	<u>67</u>	<u>Sand, medium to gravel, medium</u>
<u>67</u>	<u>80</u>	<u>Clay, brown</u>
<u>80</u>	<u>128</u>	<u>Silt, light brown</u>
<u>28</u>	<u>130</u>	<u>Sand, very fine to very coarse, moderately silty</u>
<u>130</u>	<u>136</u>	<u>Silt, pale brown</u>
<u>36</u>	<u>164</u>	<u>Sand, very fine to medium gravel</u>
<u>164</u>	<u>204</u>	<u>Sand, very fine to fine, some silt, brown</u>
<u>204</u>	<u>210</u>	<u>Silt, clayey, sandy, olive</u>
<u>110</u>	<u>230</u>	<u>Interbedded sand & sandstone</u>
<u>230</u>	<u>245</u>	<u>Interbedded silt & siltstone, sandy</u>

Depth in Feet

From	To	Description
<u>245</u>	<u>282</u>	<u>Sandstone with some silt layers</u>
<u>282</u>	<u>317</u>	<u>Clay, gray</u>
<u>317</u>	<u>319</u>	<u>Limestone, white</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

TH # 5-LE-99

SITE # 6-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD PII	Well Number 65	Date Drilled 5/5/99	Date Constructed 5/5/99	Ground Elevation 1705(e)
County PIERCE	Qtr/Qtr/Qtr NW SW SW	Section 36	Township 26 N	Range 4 W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By [Signature]	Total Depth 66

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 60 ft
Type/Size of Screen 2 1/2" ID SCH 40 10-ft
Screen Slot Size 0.010
Filter Pack A X GRAVEL 6 BUCKETS
Type/Amount Grout/Fill BENSEAL/EZ-MUD 3 BAGS 120 GAL
Type/Amount Seal 49'-52' 1-BAG HOLE PLUG

Elevation Depth
From
Reference

47- TOP OF CASING

0.0 GROUND

3 TOP OF
GROUT/FILL

7.0 WATER LEVEL

52 TOP OF FILTER PACK

54 TOP OF SCREEN

66 BOTTOM OF SCREEN

66 BOREHOLE DEPTH

LOCKING, STEEL
PROTECTIVE COVER

TOP CAP

CONCRETE
SURFACE SEAL

GROUT OR FILL

WELL CASING

FILTER PACK

WELL SCREEN

BOTTOM CAP

NORTH WELL

TH # 5-LE-99

SITE # 6-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LEND PII	Well Number 6M	Date Drilled 5/10/99	Date Constructed 5/10/99	Ground Elevation 1705(E)
County PIERCE	Qtr/Qtr/Qtr NW SW SW	Section 36	Township 26N	Range 4W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By [Signature]	Total Depth 160

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 153-F+
Type/Size of Screen 2 1/2" ID SCH 40 10-FOOT
Screen Slot Size 0.010
Filter Pack AX GRAVEL 6 BUCKETS
Type/Amount Grout/Fill BENSEAL/EE-MUD 5 BAGS 200 GAL.
Type/Amount Seal N/A

Elevation Depth
From
Reference

47- TOP OF CASING

0.0 GROUND

3 TOP OF
GROUT/FILL


10.3 WATER LEVEL

145 TOP OF FILTER PACK

149 TOP OF SCREEN

159 BOTTOM OF SCREEN

160 BOREHOLE DEPTH



5/12 DEV 1hr

CENTER WELL

TH # 5-LE-99

SITE # 6-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LEND PII	Well Number 6D	Date Drilled 5/11/99	Date Constructed 5/11/99	Ground Elevation 1705 (4)
County PIERCE	Qtr/Qtr/Qtr NW SW SW	Section 36	Township 26N	Range 4W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By [Signature]	Total Depth 281

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 279-4+
Type/Size of Screen 2 1/2" ID SCH 40 5-FOOT
Screen Slot Size 0.010
Filter Pack 10/20 Si Sd 5 BAGS
Type/Amount Grout/Fill BENSEAL/EZ-MUD 9 BAGS 360 GAL
Type/Amount Seal N/A

Elevation Depth
From
Reference

3.5 TOP OF CASING

0.0 GROUND

3 TOP OF
GROUT/FILL

13.4 WATER LEVEL

270 TOP OF FILTER PACK

275 TOP OF SCREEN

280 BOTTOM OF SCREEN

281 BOREHOLE DEPTH

LOCKING, STEEL
PROTECTIVE COVER

TOP CAP

CONCRETE
SURFACE SEAL

GROUT OR FILL

WELL CASING

FILTER PACK

WELL SCREEN

BOTTOM CAP

5/12 DEN .5hr

SOUTH WELL


Number 7 Wells

PIERCE COUNTY

TH# 8-LE-99

#7 WELLS

RENTER SITE



T27N R4W SECTION 15 NE 1/4


PLAINVIEW QUAD

Test Hole #8-LE-99 (E-log)
(27N-4W-15abbb)
Pierce County

Location: NW NW NW NE Sec. 15, T. 27 N., R. 4 W., approximately
 2,634 feet west and 45.5 feet south of northeast corner.
 Ground elevation: 1,675 ft. (t) (Plainview, 7.5 min. quadrangle)
 Depth to water: 2.7 ft. (5/17/99) Wells installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Top soil: silt, very sandy, moderately clayey, black; sand is very fine to medium.....	0.0	4.0
Sand, very silty, sand is very fine to medium; gray; slightly silty below 10 ft.....	4.0	25.0
Sand, gravelly; medium sand to fine gravel, little medium gravel; gray.....	25.0	30.0
Sand, very fine to very coarse, little fine gravel; gray.....	30.0	35.0
Sand, gravelly; very fine sand to fine gravel; gray.	35.0	45.0
Sand, silty; sand is very fine to coarse, little fine gravel; gray.....	45.0	51.0
Silt, very sandy, moderately clayey, gray; sand is very fine to fine; contains some coarser grains...	51.0	55.0
Sand, moderately silty; sand is very fine to coarse, trace of very coarse sand to fine gravel.....	55.0	68.0
Silt, moderately clayey, moderately sandy, light yellowish brown; sand is very fine to fine.....	68.0	70.0
Clay, very sandy, silty, pale brown; sand is very fine to fine, with coarser grains from above.....	70.0	80.0
Tertiary System - Miocene Series - Ogallala Group:		
Sandstone, silty, slightly clayey; sand is very fine to fine; olive gray; contains rootlet fragments; little medium sand from 100 to 115 ft.....	80.0	155.0
Sand, medium to very coarse; principally reworked shale, some bentonite, and sandstone grains.....	155.0	161.0
Clay, very silty, very calcareous, dark olive; below 170 ft, contains sandstone.....	161.0	175.0
Gravel, fine to medium; principally reworked sand- stone fragments.....	175.0	190.0
Cretaceous System - Upper Cretaceous Series - Montana Group:		
Pierre Formation:		
Shale, clayey, very calcareous, light gray, with yellow mottling.....	190.0	195.0
Shale, clayey, very calcareous, yellow with some light gray.....	195.0	205.0

Shale, clayey, very calcareous, gray with yellow mottling.....	205.0	212.0
---	-------	-------



Century GEOPHYSICAL CORP.

8-LE-99

COMPANY : Grosch
WELL : 8-LE-99
LOCATION/FIELD : Site 1
COUNTY : PIERCE
STATE : NE
SECTION : 15

OTHER SERVICES:

Caliper
uphole1
downhole

TOWNSHIP : 27 RANGE : 4W

DATE : 05/13/99
DEPTH DRILLER : 212
LOG BOTTOM : 210.82
LOG TOP : 2.09

PERMANENT DATUM :

LOG MEASURED FROM: grnd0
DRL MEASURED FROM: +1.5

KB : None
DF : None
GL : 1675

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : sol

BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite

BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54

FILE : PROCESSED
TYPE : 8043A

THRESH: 2500

Plainview Quad
Wells 7S & 7D

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS




Photo B6
Sec. 15
SITE 1-99

3458
T 785
1/4

WELL #7D
WELL #7S

436
T 186
1/2

PC

NW

Ne-

New

PC

NHEL

157.

3128
T5669
4/5

3T308
T43
2/5

3458
T785
1/4

T787
2/2

PC

W
NHFL
240.0

NHEL/PC.W
37.9

3674
T 5439
1/1

328
T790
1/1

NHEL

70.6

10
638

NHEL

132
he 2

10

10
FF

1816

T792

TH90
1/1

11

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313

State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805

Contractor's License No. 39070

State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

6. A. Well location: NW 1/4 of the NE 1/4 of Section 15, Township 27 North, Range 4 ☐ East ☒ West, Pierce County.

B. The well is 56.5 feet from the ☒ North or ☐ South section line and 2633 feet from the ☒ East or ☐ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 1-99 (Renter), TH # 8-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE #7S (South)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.

Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No.

8. Well Construction Information.

A. Total well depth: 47 feet.B. Static water level: 3.2 feet.C. Pumping water level: _____ feet.
☐ Estimated or ☐ MeasuredD. Well Construction began: May 14, 1999.E. Well Construction completed: June 7, 1999.F. Bore hole diameter: 7 1/8 inches.G. Plain Casing: Diameter 2.469 ID2.875 OD inches.Type of material: PVC Schedule 40.Wall thickness: 0.203 inch(es).Joints--Welded/Glued/Threaded/Other: ThreadedLength(s) and placement(s) depth from +1.5 ft. to 35 ft. from _____ ft. to _____ ft.H. Screen: 2.469 ID 2.875 OD in:type of material PVC Schedule 40Screen Openings (slot size) 0.010Trade Name: Titan IndustriesLength(s) and placement(s) depth from 35 ft. to 45 ft. from _____ ft. to _____ ft. guides at 34 ft.I. Gravel pack interval(s) from 31 ft. to 47 ft. from _____ ft. to _____ ft.Grade size: Armour CoatJ. Grouted/Sealed from 0 ft. to 3 ft., with Steel cover in concrete
(type)from 3 ft. to 31 ft., with Benseal/EZ-Mud
(type)K. Drilling method: Mud rotaryL. Drilling fluid: Super Gel-XM. Well development technique (total time and method): Water jetting .25 hoursN. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? ☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>4</u>	<u>Topsoil</u>
<u>4</u>	<u>19</u>	<u>Sand, fine & gravel, fine</u>
<u>19</u>	<u>28</u>	<u>Silt, sandy</u>
<u>28</u>	<u>46</u>	<u>Sand, medium & gravel, coarse</u>
<u>46</u>	<u>82</u>	<u>Interbedded sand & gravel with silty clay layers</u>
<u>82</u>	<u>100</u>	<u>Silt, clayey with fine sand</u>
<u>100</u>	<u>110</u>	<u>Sand, fine with silt layers</u>
<u>110</u>	<u>125</u>	<u>Sand & sandstone</u>
<u>125</u>	<u>162</u>	<u>Sandstone, silty</u>
<u>162</u>	<u>190</u>	<u>Clay, silty, olive</u>
<u>190</u>	<u>196</u>	<u>Pierre shale, weathered</u>
<u>196</u>	<u>212</u>	<u>Shale, clayey</u>

Depth in Feet		Description
From	To	

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City NorfolkTelephone Number (402) 371-7313
State NE Zip Code 68701 +2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'NeillTelephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)

5. Replacement and abandoned well information.

- A. Is this well a replacement well?
- ☐
- Yes
- ☒
- No D. Abandoned well last operated _____
-
- C. Replacement well is _____ feet from abandoned well F. Completion of original well abandonment on _____
-
- E. Original well pump column size: _____ inches.
-
- G. Location of water use of abandoned well: _____

6. A. Well location:
- NW
- 1/4 of the
- NE
- 1/4 of Section
- 15
- , Township
- 27
- North, Range
- 4
- ☐
- East
- ☒
- West,
- Pierce
- County.
-
- B. The well is
- 45.5
- feet from the
- ☒
- North or
- ☐
- South section line and
- 2634
- feet from the
- ☒
- East or
- ☐
- West section line.
-
- C. Street address or block, lot and subdivision, if applicable:
- Site 1-99 (Renter), TH # 8-LE-99
-
- D. Location of water use, if applicable (give legal descriptions):
-
- E. If for irrigation, the land to be irrigated is _____ acres.
-
- F. Well reference letter(s), if applicable:
- Well LE #7D (North)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

- A. Actual pumping rate, if applicable:
- 3-8
- gallons per minute. Measured
- ☐
- or Estimated
- ☒
-
- B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.
-
- D. Pumping equipment-date installed:
- August, 1999
- . E. Brand/Type:
- Grundfos Rediflo2
-
- F. Pump installed by: Contractor
- ☐
- Owner
- ☒
- Pump Installer
- ☐
- License No. _____

8. Well Construction Information.

A. Total well depth: 152 feet.

B. Static water level: 2.7 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: May 14, 1999.

E. Well Construction completed: June 7, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID

2.875 OD inches.

Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+1.5 ft.

to 145 ft.

from _____ ft.

to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from

145 ft.

to 150 ft.

from _____ ft. to

guides at 144 ft.

I. Gravel pack interval(s) from 143 ft.

to 152 ft.

from _____ ft.

to _____ ft.

Grade size: 10/20

J. Grouted/Sealed from 0 ft.

to 3 ft.,

with Steel cover in concrete

(type)

from 3 ft.

to 143 ft.,

with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>4</u>	<u>Topsoil</u>
<u>4</u>	<u>19</u>	<u>Sand, fine& gravel, fine</u>
<u>19</u>	<u>28</u>	<u>Silt, sandy</u>
<u>28</u>	<u>46</u>	<u>Sand, medium & gravel, coarse</u>
<u>46</u>	<u>82</u>	<u>Interbedded sand & gravel with silty clay layers</u>
<u>82</u>	<u>100</u>	<u>Silt, clayey with fine sand</u>
<u>100</u>	<u>110</u>	<u>Sand, fine with silt layers</u>
<u>110</u>	<u>125</u>	<u>Sand & sandstone</u>
<u>125</u>	<u>162</u>	<u>Sandstone, silty</u>
<u>162</u>	<u>190</u>	<u>Clay, silty, olive</u>
<u>190</u>	<u>196</u>	<u>Pierre shale, weathered</u>
<u>196</u>	<u>212</u>	<u>Shale, clayey</u>

Depth in Feet		Description
From	To	

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

TH # 8-LE-99

SITE # 1-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD PII	Well Number 75	Date Drilled 5/14/99	Date Constructed 5/14/99	Ground Elevation 1675 (E)
County PIERCE	Qtr/Qtr/Qtr NW NW NE	Section 15	Township 27N	Range 4W
Drilling Co. BROSCHE	Method MUD ROTARY	Driller SHOLES	Log By [Signature]	Total Depth 47

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 38 ft
Type/Size of Screen 2 1/2" ID SCH 40 10. ft
Screen Slot Size 0.010
Filter Pack AX GRAVEL 6.5 BUCKETS
Type/Amount Grout/Fill BENSEAL/EE-MUD 1 BAG 40 GAL
Type/Amount Seal TOP SEAL 7 BAGS HOLE PLUG

Elevation Depth
From
Reference

34- TOP OF CASING

0.0 GROUND

3 TOP OF
GROUT/FILL


3.2 WATER LEVEL

31 TOP OF FILTER PACK

35 TOP OF SCREEN

45 BOTTOM OF SCREEN

47 BOREHOLE DEPTH



5/14 - DEV. 15 MIN.


SOUTH WELL

TH # 8-LE-99

SITE # 1-99

WELL COMPLETION LOG

Project 1999 LEND PII	Well Number 7D	Date Drilled 5/14/99	Date Constructed 5/14/99	Ground Elevation 1675 (±)
County PIERCE	Qtr/Qtr/Qtr NWNWNE	Section 15	Township 27N	Range 4W
Drilling Co. GROECH	Method MUD ROTARY	Driller SHOLES	Log By JOP	Total Depth 152



5/14 DEV. 1/2 HR

NORTH WELL

Number 8 Wells

GUBBELS SITE



Test Hole #3-LE-99 (E-log)
(27N-2W-22bbbb)
Pierce County

Location: NW NW NW NW Sec. 22, T. 27 N., R. 2 W., approximately
89 feet south and 35 feet east of northwest corner.
Ground elevation: 1,732 ft. (t) (Osmond, 7.5 min. quadrangle)
Depth to water: 94.0 ft. (5/14/99) Wells installed.

	<u>Depth to water</u>	
	From	To
Quaternary System, undifferentiated:		
No sample.....	0.0	1.0
Silt, moderately clayey, moderately sandy, light brown; sand is very fine.....	1.0	2.0
Sand, slightly clayey, very silty, light brown; sand is very fine to fine.....	2.0	5.0
Soil: clay, silty, slightly sandy, slightly calcareous, dark brown; sand is very fine.....	5.0	12.0
Clay, silty, sandy, brown; sand is very fine; dark brown below 16 ft.....	12.0	16.5
Till: clay, silty, sandy to gravelly, light olive brown, contains black stains; contains limestone grains; slightly calcareous below 20 ft.....	16.5	35.0
Till: clay, silty, sandy to gravelly, slightly calcareous, brown; contains limestone grains.....	35.0	52.0
Sand, very fine to medium, trace of coarse and fine gravel; gray; contains limy grains and dark silicates.....	52.0	70.0
Sand, very fine to coarse, little very coarse sand to fine gravel; gray; contains dark silicates and limy grains.....	70.0	75.0
Sand, very fine to medium; gray; contains limy grains and dark silicates.....	75.0	125.0
Sand, gravelly; very fine sand to fine gravel; gray; boulder from 133 to 134 ft.....	125.0	134.5
Sand, gravelly; medium sand to fine gravel; much granitic fragments.....	134.5	135.0
Sand, medium to very coarse, little fine gravel; gray.....	135.0	140.0
Sand, very fine to medium, little coarse.....	140.0	141.0
Silt, slightly clayey, brown.....	141.0	156.0
Sand, gravelly, silty; very fine sand to fine gravel; brownish gray.....	156.0	160.0


Tertiary System - Miocene Series - Ogallala Group:

Silt, very sandy, slightly clayey, light olive gray; sand is very fine; moderately to very sandy below 165 ft.....	160.0	171.0
Silt, very sandy, slightly clayey, light reddish brown; sand is very fine; light olive gray below 182 ft.....	171.0	195.0
Sand, silty; very fine to medium; partially consol- idated; some rootlet fragments.....	195.0	205.0
Sand, very fine to fine, little medium; olive brown; slightly silty from 225 to 230 ft; yellow stain below 230 ft.....	205.0	261.5
Sandstone, silty; very fine to medium grained.....	261.5	266.0
Silt, very clayey, very sandy, light gray; sand is very fine to medium; contains limy grains.....	266.0	270.0
Clay, silty, sandy, bentonitic, olive gray; sand is very fine to fine; rootlet fragments from 275 to 280 ft.....	270.0	285.0
Sand, gravelly; fine sand to fine gravel; principally reworked limestone, bentonitic clay, sandstone, trace rootlets, ironstone, few quartz; coarser below 305 ft.....	285.0	310.0

Cretaceous System - Upper Cretaceous Series - Montana Group:

Pierre Formation:

Shale, clayey, very calcareous, gray.....	310.0	320.0
---	-------	-------



Century GEOPHYSICAL CORP.

3-le-99

COMPANY : GROSCH
WELL : 3-le-99
LOCATION/FIELD : site 3
COUNTY : Pierce
STATE : ne
SECTION : 22

OTHER SERVICES:

caliphe
None
None

TOWNSHIP : 27 RANGE : 2W

DATE : 04/19/99
DEPTH DRILLER : 320
LOG BOTTOM : 316.31
LOG TOP : -2.01

PERMANENT DATUM : None
LOG MEASURED FROM: grd
DRL MEASURED FROM: +3

KB :
DF : None
GL : 1732

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : Sol

BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite


BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54

FILE : PROCESSED
TYPE : 8043A

THRESH: 2500

Osmond Quad
Wells 8M & 8D

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS



Pierce, Co. 93-94
T-27-N R-2-W 70

Photo H6
Sec. 22

TEST HOLE # 3-LE 99

SITE 3-99

122.8

HELINW
33.5

well LE # 8M
well LE # 8D
2/2

HELINW
3.0

3678
T 885
4/

NHELINW
3.0

2A
3.0

CRP
1984
1996
1998
HELINW
3 11.8

CRP
1986-1995-1997
HELINW
2 121.2

CRP
1991-
2000
HELINW
NW
5 4.5

CRP 1997
1987-1996
HELINW
4 5.4

HEL
2 144.0
2D 124.3

2E
6.3

2C
5.4

560
T 889
1/1

591
T 888
4/

CRP
1990-1999
HEL
5 62.1

HELINW
17 12.5
HELINW
8 4.0

VHELINW
158.0

HEL
6
No.

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313

State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805

Contractor's License No. 39070

State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

6. A. Well location: NW 1/4 of the NW 1/4 of Section 22, Township 27 North, Range 2 ☐ East ☒ West, Pierce County.

B. The well is 105 feet from the ☒ North or ☐ South section line and 35 feet from the ☐ East or ☒ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 3-99 (Gubbels), TH # 3-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 8M (North)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.

Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No.

8. Well Construction Information.

A. Total well depth: 136 feet.

B. Static water level: 94 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: May 17, 1999.

E. Well Construction completed: June 1, 1999.

F. Bore hole diameter: 8 1/4 inches.

G. Plain Casing: Diameter 2.469 ID 2.875 OD inches. Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es). Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from +1.5 ft. to 124.5 ft. from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in: type of material PVC Schedule 40

Screen Openings (slot size) 0.010 Trade Name: Titan Industries

Length(s) and placement(s) depth from 124.5 ft. to 134.5 ft. from _____ ft. to _____ ft. guides at 123 ft.

I. Gravel pack interval(s) from 121 ft. to 136 ft. from _____ ft. to _____ ft. Grade size: Armour coat

J. Grouted/Sealed from 0 ft. to 3 ft., with Steel cover in concrete
(type)

from 3 ft. to 121 ft., with Benseal/EZ-Mud
(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting 1.0 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? ☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>2</u>	<u>Topsoil, silty</u>
<u>2</u>	<u>12</u>	<u>Silt, very sandy, moderately clayey, brown</u>
<u>12</u>	<u>52</u>	<u>Clay, grayish brown, silty, sandy</u>
<u>52</u>	<u>80</u>	<u>Sand, fine to coarse with gravel</u>
<u>80</u>	<u>87</u>	<u>Sand & gravel with silt</u>
<u>87</u>	<u>136</u>	<u>Sand, fine to medium, Rock @ 133' as</u>
<u>136</u>	<u>152</u>	<u>Silt, clayey, brown</u>
<u>152</u>	<u>159.5</u>	<u>Sand with gravel</u>
<u>159.5</u>	<u>192</u>	<u>Silt, olive with some siltstone</u>
<u>192</u>	<u>199</u>	<u>Sandstone, slightly silty, rootlets</u>
<u>199</u>	<u>219</u>	<u>Sand, very silty</u>
<u>219</u>	<u>257</u>	<u>Sand, very fine, slightly silty & some sandstone</u>

Depth in Feet		Description
From	To	
<u>257</u>	<u>303</u>	<u>Clay, light gray to black</u>
<u>303</u>	<u>320</u>	<u>Clay, light gray with yellow & orange</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313

State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805

Contractor's License No. 39070

State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____.

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____.

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

6. A. Well location: NW 1/4 of the NW 1/4 of Section 22, Township 27 North, Range 2 ☐ East ☒ West, Pierce County.

B. The well is 116 feet from the ☒ North or ☐ South section line and 36 feet from the ☐ East or ☒ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 3-99 (Gubbels), TH # 3-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 8D (South)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No.

8. Well Construction Information.

A. Total well depth: 200 feet.

B. Static water level: 94.7 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: May 18, 1999.

E. Well Construction completed: June 1, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID

2.875 OD inches.

Type of material: PVC Schedule 40.

Wall thickness: .0203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from +1.5 ft. to 195 ft. from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from 195 ft. to 200 ft. from _____ ft. to _____ ft. guides at 194 ft.

I. Gravel pack interval(s) from 190 ft. to 200 ft.

from _____ ft. to _____ ft.

Grade size: 10/20

J. Grouted/Sealed from 0 ft. to 3 ft.,

with Steel cover in concrete
(type)

from 3 ft. to 190 ft.,

with Benseal/EZ-Mud
(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet

From	To	Description
<u>0</u>	<u>2</u>	<u>Topsoil, silty</u>
<u>2</u>	<u>12</u>	<u>Silt, very sandy, moderately clayey, brown</u>
<u>12</u>	<u>52</u>	<u>Clay, grayish brown, silty, sandy</u>
<u>52</u>	<u>80</u>	<u>Sand, fine to coarse with gravel</u>
<u>80</u>	<u>87</u>	<u>Sand & gravel, some silt</u>
<u>87</u>	<u>136</u>	<u>Sand, fine to medium, Rock @ 133'</u>
<u>136</u>	<u>152</u>	<u>Silt, clayey, brown</u>
<u>152</u>	<u>159.5</u>	<u>Sand with gravel</u>
<u>159.5</u>	<u>192</u>	<u>Silt, olive with some siltstone</u>
<u>192</u>	<u>199</u>	<u>Sandstone, slightly silty, rootlets</u>
<u>199</u>	<u>219</u>	<u>Sand, very silty</u>
<u>219</u>	<u>257</u>	<u>Sand, very fine, slightly silty, some sandstone</u>

Depth in Feet

From	To	Description
<u>257</u>	<u>303</u>	<u>Clay, light gray to black</u>
<u>303</u>	<u>320</u>	<u>Clay, light gray with yellow & orange</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

TH # 3-LE-99

SITE # 3-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD PII	Well Number 8M	Date Drilled 5/17/99	Date Constructed 5/17/99	Ground Elevation 1735(4)
County PIERCE	Qtr/Qtr/Qtr NW NW NW	Section 22	Township 21N	Range 2W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By [Signature]	Total Depth 136

Borehole Diameter 8 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 128-ft
Type/Size of Screen 2 1/2" ID SCH 40 10-ft
Screen Slot Size 0.010
Filter Pack AX GRAVEL 7.5 BUCKETS
Type/Amount Grout/Fill BENSEAL/EZ-MUD 8 BAGS 320 GAL
Type/Amount Seal N/A

Elevation Depth
From
Reference

3.2 TOP OF CASING

0.0 GROUND

3 TOP OF
GROUT/FILL

94.0 WATER LEVEL

121 TOP OF FILTER PACK

124.5 TOP OF SCREEN

134.5 BOTTOM OF SCREEN

136 BOREHOLE DEPTH

LOCKING, STEEL
PROTECTIVE COVER

TOP CAP

CONCRETE
SURFACE SEAL

GROUT OR FILL

WELL CASING

FILTER PACK

WELL SCREEN

BOTTOM CAP

5/18 DEV 122.

NORTH WELL

TH # 3-LE-99

SITE # 3-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD PIF	Well Number 8D	Date Drilled 5/18/99	Date Constructed 5/18/99	Ground Elevation 1735 (4)
County PIERCE	Qtr/Qtr/Qtr NW NW NW	Section 22	Township 27 N	Range 2 W
Drilling Co. GROSCHE	Method MUD ROTARY	Driller SHOLES	Log By [Signature]	Total Depth 200

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 198-ft
Type/Size of Screen 2 1/2" ID SCH 40 5-ft
Screen Slot Size 0.010
Filter Pack 10/20 Si Sand 5 BAGS
Type/Amount Grout/Fill BENSEAL/EZ-MUD 8-BAGS 320 GAL
Type/Amount Seal N/A

Elevation Depth
From
Reference

3 TOP OF CASING

0.0 GROUND

3 TOP OF
GROUT/FILL


94.7 WATER LEVEL

190 TOP OF FILTER PACK

195 TOP OF SCREEN

200 BOTTOM OF SCREEN

200 BOREHOLE DEPTH



5/18 DEW 42 hr.

SOUTH WELL


Number 9 Wells

PIERCE COUNTY

TH # 2-LE-99

9 WELLS

BRODERSON SITE



T 27 N R 17 W SECTION 17 SE 1/4


RANDOLPH SW QUAD

Test Hole #2-LE-99 (E-log)
(27N-1W-17dcdc)
Pierce County

Location: SW SE SW SE Sec. 17, T. 27 N., R. 1 W., approximately
 1,770 feet west and 48 feet north of southeast corner.
 Ground elevation: 1,662 ft. (t) (Randolph SW, 7.5 min. quadrangle).
 Depth to water: 54.5 ft. (4/20/99). Wells installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Top soil: silt, slightly clayey, sandy, dark grayish brown; sand is very fine.....	0.0	2.0
Clay, silty, sandy, dark brownish gray; sand is very fine.....	2.0	3.5
Silt, moderately clayey, slightly sandy, grayish brown; sand is very fine.....	3.5	5.0
Clay, silty, slightly sandy, brown; sand is very fine; more sand below 10 ft.....	5.0	11.5
Sand, silty, brown; sand is very fine to coarse, little fine gravel; contains ironstone and limestone fragments.....	11.5	15.0
Sand, slightly gravelly, slightly silty, brown; very fine to very coarse sand with little fine to medium gravel.....	15.0	20.0
Sand, very fine to very coarse, trace of very fine gravel; contains quartz, limestone, ironstone and silicates.....	20.0	25.0
Sand, gravelly; very fine sand to fine gravel; contains siliceous fragments, limestone and ironstone.....	25.0	26.0
Silt, very sandy, slightly clayey, light brownish gray; sand is very fine.....	26.0	30.0
Sand, very fine to medium with some fine to medium gravel; limestone, granite, and dark silicates....	30.0	36.0
No sample.....	36.0	36.5
Sand, fine to medium, gray; contains limy grains....	36.5	56.0
Sand, very fine to very coarse, little fine gravel; contains limy grains, red granite and silicates...	56.0	57.0
Silt, very clayey to clay, very silty; brownish gray.....	57.0	58.0
Gravel, very fine to coarse; granitic with silicates.....	58.0	60.0
Sand, very fine to medium, little coarse; gray; contains limy grains, granite, chert, dark silicates; few gravel grains 70 to 75 ft.....	60.0	85.0

Sand, very fine to fine; light medium gray.....	85.0	95.0
Sand, very fine to fine; gray.....	95.0	100.0
Sand, very fine to fine, little medium; gray; contains silt lens.....	100.0	105.0
Sand, fine to medium, little coarse; gray.....	105.0	107.0
Sand, silty, very fine to very coarse, little fine gravel; gray; little coarse sand below 110 ft.....	107.0	115.0
Sand, gravelly, very fine sand to fine gravel; gray; contains granitic fragments and dark silicates....	115.0	120.0
Sand, very fine to very coarse, trace of fine gravel; gray.....	120.0	123.0
Clay, silty, brown; pinkish cast below 130 ft; contains limy nodules below 135 ft.....	123.0	140.0
Silt, moderately clayey, slightly sandy, brown; sand is very fine.....	140.0	151.0
Sand, silty; sand is very fine to fine; brownish gray.....	151.0	155.0
Tertiary System - Miocene Series - Ogallala Group:		
Sand, slightly silty, gray; sand is very fine to fine, contains green silicates; contains rootlets from 160 to 165 ft; contains dark silicates below 165 ft.....	155.0	197.0
Clay, silty, pale olive; some very fine sand; moderately sandy from 200 to 205 ft; slightly sandy below 205 ft.....	197.0	220.0
Silt, slightly clayey, slightly sandy, light brownish gray; sand is very fine.....	220.0	230.0
Clay, silty, slightly sandy, light olive brown; sand is very fine; light brownish gray below 237 ft....	230.0	244.5
Cretaceous System - Upper Cretaceous Series - Colorado Group:		
Niobrara Formation:		
Limestone, gray.....	244.5	246.0
Chalk, white with yellow; much yellow below 255 ft..	246.0	259.0
Shale, clayey, very calcareous, dark brown; black below 264 ft.....	259.0	270.0



Century GEOPHYSICAL CORP.

2-1e-99

COMPANY : GROSCH
WELL : 2-1e-99
LOCATION/FIELD : site 8
COUNTY : pierce
STATE : ne
SECTION : 17

OTHER SERVICES:

caliper
uncalib
downhole

TOWNSHIP : 27 RANGE : 1W

DATE : 04/13/99
DEPTH DRILLER : 270
LOG BOTTOM : 270.44
LOG TOP : 1.43

PERMANENT DATUM : None

LOG MEASURED FROM: grd
DRL MEASURED FROM: +1.5

KB :
DF : None
GL : 1662

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : Sol

BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite


BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54

FILE : PROCESSED
TYPE : 8043C

THRESH: 2500

Randolph SW Quad
Wells 9M & 9D


ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS



Pierce, Co. 93-94
T-27-N R-1-W 45

Photo J6
Sec. 17
SITE 8-99

TH# 2-LE-99



STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City NorfolkTelephone Number (402) 371-7313State NE Zip Code 68701 +2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'NeillTelephone Number (402) 336-1805Contractor's License No. 39070State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____.

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____.

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well: _____

6. A. Well location: SW 1/4 of the SE 1/4 of Section 17, Township 27 North, Range 1 ☐ East ☒ West, Pierce County.
B. The well is 40 feet from the ☐ North or ☒ South section line and 175 feet from the ☒ East or ☐ West section line.
C. Street address or block, lot and subdivision, if applicable: Site 8-99 (Broderon), TH # 2-LE-99

D: Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 9M (South)

* DW2/LYWP / 11/99 / Jof

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.E. Brand/Type: Grundfos Rediflo2F. Pump installed by: Contractor ☐ Owner ☒Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 120 feet.

B. Static water level: 54.5 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: May 20, 1999.

E. Well Construction completed: June 1, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID 2.875 OD inches. Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es). Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from +1.5 ft. to 110 ft. from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in: type of material PVC Schedule 40

Screen Openings (slot size) 0.010 Trade Name: Titan Industries

Length(s) and placement(s) depth from 110 ft. to 120 ft. from _____ ft. to _____ ft. guides at 109 ft.

I. Gravel pack interval(s) from 106 ft. to 120 ft. from _____ ft. to _____ ft. Grade size: Armour coat

J. Grouted/Sealed from 0 ft. to 3 ft., with Steel cover in concrete
(type)

from 3 ft. to 106 ft., with Benseal/EZ-Mud
(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .75 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? ☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		
From	To	Description
<u>0</u>	<u>11.5</u>	<u>Clay, very silty, brown</u>
<u>11.5</u>	<u>26</u>	<u>Sand, medium to coarse</u>
<u>26</u>	<u>35</u>	<u>Silt</u>
<u>35</u>	<u>53</u>	<u>Sand, very fine to gravel, fine</u>
<u>53</u>	<u>57</u>	<u>Silt, sandy</u>
<u>57</u>	<u>80</u>	<u>Sand, medium to coarse with gravel</u>
<u>80</u>	<u>103</u>	<u>Sand, very fine to medium</u>
<u>103</u>	<u>123</u>	<u>Sand, medium to gravel, fine</u>
<u>123</u>	<u>140</u>	<u>Clay, silty, brown</u>
<u>140</u>	<u>152</u>	<u>Silt, reddish brown</u>
<u>152</u>	<u>163</u>	<u>Sand, silty, very fine to fine</u>
<u>163</u>	<u>196</u>	<u>Sand, very fine to fine</u>

Depth in Feet		
From	To	Description
<u>196</u>	<u>245</u>	<u>Clay, silty, olive & sandy</u>
<u>245</u>	<u>270</u>	<u>Shale, chalky, some limestone</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313

State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805

Contractor's License No. 39070

State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

6. A. Well location: SW 1/4 of the SE 1/4 of Section 17, Township 27 North, Range 1 ☐ East ☒ West, Pierce County.

B. The well is 45 feet from the ☐ North or ☒ South section line and 1758 feet from the ☒ East or ☐ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 8-99 (Broderson), TH # 2-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 9D (North)

* DWR/LYNN 11/99/ Gof

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.

Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No.

8. Well Construction Information.

A. Total well depth: 188 feet.

B. Static water level: 55.2 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: May 19, 1999.

E. Well Construction completed: June 1, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID 2.875 OD inches. Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es). Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from +1.5 ft. to 180 ft. from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in: type of material PVC Schedule 40

Screen Openings (slot size) 0.010 Trade Name: Titan Industries

Length(s) and placement(s) depth from 180 ft. to 185 ft. from _____ ft. to _____ ft. guides at 179 ft.

I. Gravel pack interval(s) from 177 ft. to 188 ft. from _____ ft. to _____ ft. Grade size: 10/20

J. Grouted/Sealed from 0 ft. to 3 ft., with Steel cover in concrete
(type)

from 3 ft. to 177 ft., with Benseal/EZ-Mud
(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? ☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>11.5</u>	<u>Clay, very silty, brown</u>
<u>11.5</u>	<u>26</u>	<u>Sand, medium to coarse</u>
<u>26</u>	<u>35</u>	<u>Silt</u>
<u>35</u>	<u>53</u>	<u>Sand, very fine to gravel, fine</u>
<u>53</u>	<u>57</u>	<u>Silt, sandy</u>
<u>57</u>	<u>80</u>	<u>Sand, medium to coarse with gravel</u>
<u>80</u>	<u>103</u>	<u>Sand, very fine to medium</u>
<u>103</u>	<u>123</u>	<u>Sand, medium to gravel, fine</u>
<u>123</u>	<u>140</u>	<u>Clay, silty, brown</u>
<u>140</u>	<u>152</u>	<u>Silt, reddish brown</u>
<u>152</u>	<u>163</u>	<u>Sand, silty, very fine to fine</u>
<u>163</u>	<u>196</u>	<u>Sand, very fine to fine</u>

Depth in Feet		Description
From	To	
<u>196</u>	<u>245</u>	<u>Clay, silty olive; sandy</u>
<u>245</u>	<u>270</u>	<u>Shale, chalky with some limestone</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date


TH # 2-LE-99

SITE # 8-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD PII	Well Number 9M	Date Drilled 5/20/99	Date Constructed 5/20/99	Ground Elevation 1665(t)
County PIERCE	Qtr/Qtr/Qtr SWSW SE	Section 17	Township 27N	Range 1W
Drilling Co. GROSCU	Method MUD ROTARY	Driller SHOLES	Log By Jaf	Total Depth 120



5/20 DEV .75 hr

SOUTH WELL

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LEND PIF	Well Number 9D	Date Drilled 5/19/99	Date Constructed 5/19/99	Ground Elevation 1665(±)
County PIERCE	Qtr/Qtr/Qtr SW SW SE	Section 17	Township 27N	Range 1W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By [Signature]	Total Depth 188

Borehole Diameter
7 1/8"

Survey Reference

Type/Size of Casing
2 1/2" ID SCH 40
FLUSH/THREADED
183-ft

Type/Size of Screen
2 1/2" ID SCH 40
5-ft

Screen Slot Size
0.010

Filter Pack
10/20 Si Sd
6.5 BAGS

Type/Amount Grout/Fill
BENSEAL/EZ-MUD
9 BAGS
360 GAL

Type/Amount Seal

N/A

Elevation Depth
From
Reference

3' TOP OF CASING

0.0 GROUND

3 TOP OF
GROUT/FILL

55.2 WATER LEVEL

177 TOP OF FILTER PACK

180 TOP OF SCREEN

185 BOTTOM OF SCREEN

188 BOREHOLE DEPTH

LOCKING, STEEL
PROTECTIVE COVER

TOP CAP

CONCRETE
SURFACE SEAL

GROUT OR FILL

WELL CASING

FILTER PACK

WELL SCREEN

BOTTOM CAP

5/20 DEV 7-1.5hr


NORTH WELL

Number 10 Wells

TH # 4-LE-99

10 WELLS

KOEHN SITE




T26N R2W SECTION 5 NW 1/4

OSMOND QUAD

Test Hole #4-LE-99 (E-log)
(26N-2W-5baab)
Pierce County

Location: NW NE NE NW Sec. 5, T. 26 N., R. 2 W., approximately
 2,099 feet east and 16 feet south of northwest corner.
 Ground elevation: 1,600 ft. (t) (Osmond, 7.5 min. quadrangle)
 Depth to water: 3.4 ft. (5/20/99) Wells installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Top soil: silt, moderately sandy, slightly clayey, black; sand is very fine.....	0.0	10.0
Silt, moderately sandy, slightly clayey, black; sand is very fine; contains trace of peat fragments....	10.0	15.0
Sand, silty; very fine to very coarse, little fine gravel; gray.....	15.0	20.0
Sand, slightly gravelly; fine sand to fine gravel, trace of medium to coarse gravel.....	20.0	25.0
Sand, very fine to very coarse, little very fine gravel; dark gray.....	25.0	35.0
Sand, gravelly; very fine sand to fine gravel, trace of medium gravel.....	35.0	40.0
Sand, very fine to very coarse, trace of very fine gravel; contains silt lens.....	40.0	46.0
Silt, very sandy, moderately clayey, light olive gray; sand is very fine.....	46.0	51.5
Sand, very fine to very coarse, trace of very fine gravel; contains organic material and limy grains.	51.5	55.0
Sand, very fine to very coarse; gray; contains limy grains; very fine to medium from 60 to 65 ft; contains little coarse sand below 65 ft.....	55.0	96.0
Tertiary System - Miocene Series - Ogallala Group:		
Silt, very clayey, pale olive.....	96.0	100.0
Clay, pale olive; moderately sandy below 105 ft; sand is very fine.....	100.0	112.0
Clay, silty, bentonitic, pale olive.....	112.0	117.0
Cretaceous System - Upper Cretaceous Series - Montana Group:		
Pierre Formation:		
Shale, clayey, pale olive with yellow stain.....	117.0	128.0
Shale, clayey, very calcareous, light gray with yellow.....	128.0	132.0
Shale, clayey, moderately calcareous, dark gray to black; noncalcareous, black below 135 ft.....	132.0	140.0



Century GEOPHYSICAL CORP.

4-1e-99

COMPANY : GROSCH
WELL : 4-1e-99
LOCATION/FIELD : site 4
COUNTY : pierce
STATE : ne
SECTION : 5

OTHER SERVICES:

downhole
None
None

TOWNSHIP : 26 RANGE : 2W

DATE : 04/20/99
DEPTH DRILLER : 140
LOG BOTTOM : 136.08
LOG TOP : -0.70

PERMANENT DATUM : None

LOG MEASURED FROM: grd KB :
DRL MEASURED FROM: +3 DF : None
GL : 1600

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : Sol


BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite

BOREHOLE FLUID : 0 FILE : PROCESSED
RM : 0 TYPE : 8043A
RM TEMPERATURE : 0
MATRIX DELTA T : 54

THRESH: 2500

Osmond Quad
Wells 10S & 10M

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS




WELL LE # 105

T-26-N R-2-W 60

Sec. 5

TH # 4-LE-99

STATE 4-99



STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313
State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

5. A. Well location: NE 1/4 of the NW 1/4 of Section 5, Township 26 North, Range 2 ☐ East ☒ West, Pierce County.

B. The well is 4 feet from the ☒ North or ☐ South section line and 2123 feet from the ☐ East or ☒ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 4-99 (Koehn), TH # 4-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 10S (West)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.

Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 31 feet.B. Static water level: 4.4 feet.C. Pumping water level: _____ feet.
☐ Estimated or ☐ MeasuredD. Well Construction began: May 20, 1999.E. Well Construction completed: June 7, 1999.F. Bore hole diameter: 7 1/8 inches.G. Plain Casing: Diameter 2.469 ID2.875 OD inches.Type of material: PVC Schedule 40.Wall thickness: 0.203 inch(es).Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+ 1.5 ftto 21 ft.

from _____ ft.

to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:type of material PVC Schedule 40Screen Openings (slot size) 0.010Trade Name: Titan Industries

Length(s) and placement(s) depth from

21 ftto 31 ft.

from _____ ft. to

guides at 19 ft.I. Gravel pack interval(s) from 17 ft.to 31 ft.

from _____ ft.

to _____ ft.

Grade size: Armour coatJ. Grouted/Sealed from 0 ft.to 3 ft.,with Steel cover in concrete

(type)

from 3 ft.to 17 ft.,with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotaryL. Drilling fluid: Super Gel-XM. Well development technique (total time and method): Water jetting .75 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet

From	To	Description
<u>0</u>	<u>12</u>	<u>Silt, moderately clayey, black</u>
<u>12</u>	<u>34</u>	<u>Sand, coarse & gravel, fine with silt lenses</u>
<u>34</u>	<u>51</u>	<u>Silt, clayey, light gray with sandy layers</u>
<u>51</u>	<u>59</u>	<u>Sand, fine to gravel, fine</u>
<u>59</u>	<u>93</u>	<u>Sand, very fine to medium</u>
<u>93</u>	<u>109</u>	<u>Silt, very clayey, olive with some thin siltstone lenses</u>
<u>109</u>	<u>140</u>	<u>Clay, shaley, light gray with yellow & orange</u>

Depth in Feet

From To Description

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313
State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

- A. Is this well a replacement well? ☐ Yes ☒ No D. Abandoned well last operated _____
C. Replacement well is _____ feet from abandoned well F. Completion of original well abandonment on _____
E. Original well pump column size: _____ inches.
G. Location of water use of abandoned well:

5. A. Well location: NE 1/4 of the NW 1/4 of Section 5, Township 26 North, Range 2 ☐ East ☒ West, Pierce County.
B. The well is 4 feet from the ☒ North or ☐ South section line and 2129 feet from the ☐ East or ☒ West section line.
C. Street address or block, lot and subdivision, if applicable: Site 4-99 (Koehn), TH # 4-LE-99
D. Location of water use, if applicable (give legal descriptions):
E. If for irrigation, the land to be irrigated is _____ acres.
F. Well reference letter(s), if applicable: Well LE #10M (East)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

- A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒
B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.
D. Pumping equipment-date installed: August, 1999. E. Brand/Type: Grundfos Rediflo2
F. Pump installed by: Contractor ☐ Owner ☒ Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 91 feet.

B. Static water level: 3.4 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: May 20, 1999.

E. Well Construction completed: June 7, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID

2.875 OD inches.

Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+1.5 ft

. to 86 ft.

from _____ ft.

to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from

86 ft

to 91 ft.

from _____ ft. to

guides at 85 ft.

I. Gravel pack interval(s) from 83.5 ft.

to 91.5 ft.

from _____ ft.

to _____ ft.

Grade size: 10/20

J. Grouted/Sealed from 0 ft.

to 3 ft.,

with Steel cover in concrete

(type)

from 3 ft.

to 83.5 ft.,

with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .75 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet

From	To	Description
<u>0</u>	<u>12</u>	<u>Silt, black, moderately clayey</u>
<u>12</u>	<u>34</u>	<u>Sand, coarse & gravel, fine with silt lenses</u>
<u>34</u>	<u>51</u>	<u>Silt, clayey, light gray with sand lenses</u>
<u>51</u>	<u>59</u>	<u>Sand, fine to gravel, fine</u>
<u>59</u>	<u>93</u>	<u>Sand, very fine to medium</u>
<u>93</u>	<u>109</u>	<u>Silt, very clayey, olive with thin siltstone layers</u>
<u>109</u>	<u>140</u>	<u>Clay, shaley, light gray with yellow & orange</u>

Depth in Feet

From To Description

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date


CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LEND PII	Well Number 105	Date Drilled 5/20/99	Date Constructed 5/20/99	Ground Elevation 1600(±)
County PIERCE	Qtr/Qtr/Qtr NE NE NW	Section 5	Township 26N	Range 2W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By <i>[Signature]</i>	Total Depth 32

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 24-ft
Type/Size of Screen 2 1/2" ID SCH 40 10-ft
Screen Slot Size 0.010
Filter Pack 4X GRAVEL 5.5 BUCKETS 1 BAG 10/20 SiSd
Type/Amount Grout/Fill BENSEAL/EZ-MUD 1 BAG
Type/Amount Seal 11'-17'-2 BAGS HOLE PLUG

Elevation	Depth From Reference
<u>341</u>	TOP OF CASING
<u>0.0</u>	GROUND
<u>3</u>	TOP OF GROUT/FILL
<u>4.4</u>	WATER LEVEL
<u>17</u>	TOP OF FILTER PACK
<u>21</u>	TOP OF SCREEN
<u>31</u>	BOTTOM OF SCREEN
<u>32</u>	BOREHOLE DEPTH



5/20 DEW .75 hr

WEST WELL.

TH # 4-LE-99

SITE # 4-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD PIF	Well Number 10M	Date Drilled 5/20/99	Date Constructed 5/20/99	Ground Elevation 1600 (t)
County PIERCE	Qtr/Qtr/Qtr NE NE NW	Section 5	Township 26N	Range 2W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By Jol	Total Depth 91.5

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 90 ft
Type/Size of Screen 2 1/2" ID SCH 40 5-ft
Screen Slot Size 0.010
Filter Pack Si Sd 10/20 2 BAGS 20/40 4 BAGS
Type/Amount Grout/Fill BENSEAL/EZ-MUD 4 BAGS 160 GAL
Type/Amount Seal N/A

Elevation Depth
From
Reference

4+/- TOP OF CASING

0.0 GROUND

3 TOP OF
GROUT/FILL


3.4 WATER LEVEL

83.5 TOP OF FILTER PACK

86 TOP OF SCREEN

91 BOTTOM OF SCREEN

91.5 BOREHOLE DEPTH



5/20 DEN .75 hrs

EAST WELL


Number 11 Wells

PIERCE COUNTY

TH # 9-LE-99

11 WELLS

FLESNER SITE



T26N R3W SECTION 15 SW1/4

PIERCE NW QUAD

Test Hole #9-LE-99 (E-log)
(26N-3W-15cccb)
Pierce County

Location: NW SW SW SW Sec. 15, T. 26 N., R. 3 W., approximately
 353 feet north and 50 feet east of southwest corner.

Ground elevation: 1,753 ft. (t) (Pierce NW, 7.5 min. quadrangle)

Depth to water: 122 ft. (5/27/99) Wells installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Top soil: no sample.....	0.0	5.0
Silt, very sandy, slightly clayey, moderately cal- careous, brown; sand is very fine.....	5.0	27.0
Silt, very sandy, slightly clayey, moderately calcar- eous, very dark brown.....	27.0	60.0
Clay, very sandy, silty, very dark brown with olive tint; sand is very fine; grayish brown from 65 to 80 ft; dark grayish brown below 80 ft.....	60.0	95.0
Clay, very sandy, silty, light olive brown; sand is very fine.....	95.0	100.0
Clay, very sandy, silty, dark grayish brown; sand is very fine with few coarser grains; brown below 105 ft.....	100.0	120.0
No sample(losing a lot of water).....	120.0	125.0
Clay, very sandy, silty, moderately calcareous, pale olive; sand is very fine; slightly calcareous below 130 ft.....	125.0	135.0
Clay, very sandy, silty, olive gray; sand is very fine.....	135.0	145.0
Clay, waxey, olive, some limy areas; olive gray below 155 ft.....	145.0	160.0
Sand, very silty to silt, very sandy; moderately calcareous, gray; sand is very fine to medium; very calcareous below 165 ft.....	160.0	170.0
No sample.....	170.0	175.0
Sand, silty, slightly clayey; sand is very fine to medium; greenish gray; contains shell fragments; pale olive below 181 ft.....	175.0	189.0
Sand, gravelly; very fine sand to fine gravel; con- tains shell fragments; 196.5 to 197 ft, boulder...	189.0	200.0
Sand, slightly silty; very fine to coarse, little fine gravel; contains shell fragments; slightly finer texture below 210 ft.....	200.0	215.0
Sand, gravelly, silty; very fine sand to fine gravel, trace of medium; contains shell fragments.	215.0	225.0

Sand, slightly silty; sand is very fine to very coarse with a trace of fine to medium gravel; no medium gravel below 230 ft.....	225.0	235.0
Sand, very fine to coarse, little very coarse.....	235.0	240.0
Sand, very fine to very coarse with a trace gravel..	240.0	245.0
Sand, gravelly; very fine sand to fine gravel.....	245.0	250.0
Sand, very fine to very coarse with a trace of gravel; slightly more fine gravel from 255 to 260 ft; contains a trace of medium gravel below 260ft.	250.0	267.0
Tertiary System - Miocene Series - Ogallala Group:		
Sand to sandstone, silty; sand is very fine to fine; pale olive; contains rootlets fragments below 275 ft.....	267.0	290.0
Sand, very silty to silt, very sandy; slightly clayey, sand is very fine, olive; very fine to medium sand below 295 ft.....	290.0	305.0
Sand, very fine to fine, little medium; principally reworked rootlets, sandstone and clay fragments...	305.0	330.0
Silt, moderately sandy, slightly clayey, very calcareous, pale yellow; sand is very fine.....	330.0	340.0
Silt, moderately sandy, moderately clayey, very calcareous, light yellowish brown; sand is very fine; contains limy grains; many limy grains below 356 ft.....	340.0	360.0
Limestone, gray; very hard.....	360.0	362.0



Century GEOPHYSICAL CORP.

9-LE-99

COMPANY : Grosch
WELL : 9-LE-99
LOCATION/FIELD : Site 5
COUNTY : PIERCE
STATE : NE
SECTION : 15

OTHER SERVICES:

downhole
None
None

TOWNSHIP : 26 RANGE : 3W

DATE : 05/21/99
DEPTH DRILLER : 362
LOG BOTTOM : 363.14
LOG TOP : 2.59

PERMANENT DATUM : None
LOG MEASURED FROM: grnd
DRL MEASURED FROM: +1

KB : None
DF : None
GL : ~~1745~~ 1753 *

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : sol

BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite

BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54


FILE : PROCESSED
TYPE : 8043A

THRESH: 2500

Pierce NW Quad
Wells 11M & 11D

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS

* 9-2 11/99



NOT TO SCALE

Pierce, Co. 93-94
T-26-N R-3-W 60
TH # 9-LE-99

Photo E9
Sec. 15
Site 5-99

903
T1508
1/1

770
T1317
2/2

HELINW
4
8.0

NHELINW
2
10.3

NHELINW
5
8.2

NC

NHELINW
1
155.1

NHELINW
3
21.0

NHELINW
6
50.4

~~2346~~ ~~2297~~ 3893
T1314
1/2

861
T1480
2/3

1A
4.5

1B
5.0

Well # LE IIM
Well # LE IID

NHELINW

139.4

10

119.7

1C

5.2

STIP

NC

1E
5.0

517.91

NHELINW

13.1

517.92

NC

NHELINW
2
140.4

3468
T1509
1/1

NHELINW
2
31.3

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk
Telephone Number (402) 371-7313
State NE Zip Code 68701 +
2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill
Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +
3. Permit Number(s) _____
4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)
5. Replacement and abandoned well information.
A. Is this well a replacement well? ☐ Yes ☒ No
C. Replacement well is _____ feet from abandoned well
E. Original well pump column size: _____ inches.
G. Location of water use of abandoned well: _____
D. Abandoned well last operated _____
F. Completion of original well abandonment on _____
6. A. Well location: SW 1/4 of the SW 1/4 of Section 15, Township 26 North, Range 3 ☐ East ☒ West, Pierce County.
B. The well is 379 feet from the ☐ North or ☒ South section line and 51 feet from the ☐ East or ☒ West section line.
C. Street address or block, lot and subdivision, if applicable: Site 5-99 (Flesner), TH 9-LE-99
D. Location of water use, if applicable (give legal descriptions):
E. If for irrigation, the land to be irrigated is _____ acres.
F. Well reference letter(s), if applicable: Well # LE 11M (North)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

- A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒
- B. Pump column diameter: _____ inches.
- C. Length of pump column: _____ feet.
- D. Pumping equipment-date installed: August, 1999.
- E. Brand/Type: Grundfos Rediflo2
- F. Pump installed by: Contractor ☐ Owner ☒ Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 270 feet.

B. Static water level: 112 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: May 26, 1999.

E. Well Construction completed: June 11, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID

2.875 OD inches.

Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+1.5 ft

. to 255.5 ft.

from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from

255.5 ft

to 265.5 ft.

from _____ ft. to

guides at 254 ft.

I. Gravel pack interval(s) from 243 ft.

to 270 ft.

from _____ ft. to _____ ft.

Grade size: Armour coat

J. Grouted/Sealed from 0 ft.

to 3 ft.,

with Steel cover in concrete

(type)

from 3 ft.

to 243 ft.,

with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>27</u>	<u>Silt, clay, light brown</u>
<u>27</u>	<u>80</u>	<u>Clay, some silty blue clay</u>
<u>80</u>	<u>112</u>	<u>Silt with clay lenses, yellow</u>
<u>112</u>	<u>119</u>	<u>Clay; silt, gray</u>
<u>119</u>	<u>124</u>	<u>Sand, fine; took water</u>
<u>124</u>	<u>150</u>	<u>Clay, sandy, gray</u>
<u>150</u>	<u>166</u>	<u>Clay, silty, green-gray</u>
<u>166</u>	<u>191</u>	<u>Sand, fine, some gravel, silt layers @ 172', 182', 190'</u>
<u>191</u>	<u>250</u>	<u>Sand, medium to gravels, medium, green</u>
<u>250</u>	<u>267</u>	<u>Sand, coarse to gravel, medium, red & yellow</u>
<u>267</u>	<u>275</u>	<u>Silt, clayey, sandy, olive</u>
<u>275</u>	<u>290</u>	<u>Sand & sandstone, silty</u>

Depth in Feet		Description
From	To	
<u>290</u>	<u>307</u>	<u>Silt, clayey</u>
<u>307</u>	<u>328</u>	<u>Sand & sandstone; sand, very fine to fine</u>
<u>328</u>	<u>361</u>	<u>Silt, very clayey, pink & olive</u>
<u>361</u>	<u>362</u>	<u>Rock</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313
State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)

5. Replacement and abandoned well information.

- A. Is this well a replacement well? ☐ Yes ☒ No
C. Replacement well is _____ feet from abandoned well
E. Original well pump column size: _____ inches.
D. Abandoned well last operated _____,
F. Completion of original well abandonment on _____,
G. Location of water use of abandoned well:

6. A. Well location: SW 1/4 of the SW 1/4 of Section 15, Township 26 North, Range 3 ☐ East ☒ West, Pierce County.
B. The well is 353 feet from the ☐ North or ☒ South section line and 50 feet from the ☐ East or ☒ West section line.
C. Street address or block, lot and subdivision, if applicable: Site 5-99 (Flesner), TH # 9-LE-99
D. Location of water use, if applicable (give legal descriptions):
E. If for irrigation, the land to be irrigated is _____ acres.
F. Well reference letter(s), if applicable: Well LE # 11D (South)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No
If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

- A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒
B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.
D. Pumping equipment-date installed: August, 1999. E. Brand/Type: Grundfos Rediflo2
F. Pump installed by: Contractor ☐ Owner ☒ Pump Installer ☐ License No.

8. Well Construction Information.

A. Total well depth: 321 feet.

B. Static water level: 112 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: May 24, 1999.

E. Well Construction completed: June 11, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID

2.875 OD inches.

Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+1.5 ft

. to 315 ft.

from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from

315 ft

to 320 ft.

from _____ ft. to

guides at 314 ft.

I. Gravel pack interval(s) from 305 ft.

to 321 ft.

from _____ ft. to _____ ft.

Grade size: 10/20

J. Grouted/Sealed from 0 ft.

to 3 ft.,

with Steel cover in concrete

(type)

from 3 ft.

to 305 ft.,

with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet

From	To	Description
<u>0</u>	<u>27</u>	<u>Silt, clayey, light brown</u>
<u>27</u>	<u>80</u>	<u>Clay, some silty blue clay</u>
<u>80</u>	<u>112</u>	<u>Silt with clay lenses, yellow</u>
<u>112</u>	<u>119</u>	<u>Clay; silt, gray</u>
<u>119</u>	<u>124</u>	<u>Sand, fine; took water</u>
<u>124</u>	<u>150</u>	<u>Clay, sandy, gray</u>
<u>150</u>	<u>166</u>	<u>Clay, silty, green-gray</u>
<u>166</u>	<u>191</u>	<u>Sand, fine with some gravel silt layers @</u>
		<u>172', 182' and 190'</u>
<u>191</u>	<u>250</u>	<u>Sand, medium to gravels, medium, green</u>
<u>250</u>	<u>267</u>	<u>Sand, coarse to gravel, medium, red &</u>
		<u>yellow</u>
<u>267</u>	<u>275</u>	<u>Silt, clayey, sandy, olive</u>
<u>275</u>	<u>290</u>	<u>Sand & sandstone, silty</u>

Depth in Feet

From	To	Description
<u>290</u>	<u>307</u>	<u>Silt, clayey</u>
<u>307</u>	<u>328</u>	<u>Sand & sandstone; sand, very fine to fine</u>
<u>328</u>	<u>361</u>	<u>Silt, very clayey, pink & olive</u>
<u>361</u>	<u>362</u>	<u>Rock</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD PJE	Well Number 11M	Date Drilled 5/26/99	Date Constructed 5/26/99	Ground Elevation 1745(t)
County PIERCE	Qtr/Qtr/Qtr SW SW SW	Section 15	Township 26N	Range 3W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By Jaf	Total Depth 270

Borehole Diameter
7 1/8"

Survey Reference

Type/Size of Casing
2 1/2" ID SCH 40
FLUSH/THREADED
257 ft.Type/Size of Screen
2 1/2" ID SCH 40
10-ftScreen Slot Size
0.010Filter Pack
AX GRAVEL
7 BUCKETS
* PLUS UPPER FMType/Amount Grout/Fill
BENSEAL/EE-MUD
10 BAGS
400 GALType/Amount Seal
TOP 1-BAG
HOLE PLUGElevation Depth
From
Reference

41 ADDED TOP OF CASING

0.0 GROUND

3 TOP OF
GROUT/FILL

112.5 WATER LEVEL

* 243 TOP OF FILTER PACK

255.5 TOP OF SCREEN

265.5 BOTTOM OF SCREEN

270 BOREHOLE DEPTH

LOCKING, STEEL
PROTECTIVE COVER

TOP CAP

CONCRETE
SURFACE SEAL

GROUT OR FILL

WELL CASING

FILTER PACK

WELL SCREEN

BOTTOM CAP

5/27 DEV 1.5 hr

* FM CASING 243'
IS LAST REG


NORTH WELL

TH # 9-LE-99

SITE # 5-99

WELL COMPLETION LOG

Project 1999 LEND PII	Well Number 11D	Date Drilled 5/24 & 25	Date Constructed 5/25/99	Ground Elevation 1745(±)
County PIERCE	Qtr/Qtr/Qtr SW SW SW	Section 15	Township 26N	Range 3W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By Jol	Total Depth 321



SOUTH WELL


Number 12 Wells

MADISON COUNTY

TH # 10-LE-99

12 WELLS

UECKER SITE



T24N R3W SECTION 17 SW1/4

MEADOW GROVE QUAD

Test Hole #10-LE-99 (E-log)
(24N-3W-17cccc)
Madison County

Location: SW SW SW SW Sec. 17, T. 24 N., R. 3 W., approximately
 99 feet north and 29 feet east of southwest corner.


Ground elevation: 1,630 ft. (t) (Meadow Grove, 7.5 min. quadrangle)

Depth to water: 19.0 ft. (6/16/99) Wells Installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Top soil: silt, slightly clayey, very sandy, dark brown; sand is very fine to fine, little medium...	0.0	5.0
Sand, very fine to medium, reddish.....	5.0	25.0
Silt, very sandy, slightly clayey, brown: sand is very fine to fine.....	25.0	30.0
Sand, gravelly; very fine sand to fine gravel.....	30.0	35.0
Sand, very fine to very coarse, little fine gravel..	35.0	44.5
Tertiary System - Miocene Series - Ogallala Group:		
Sand to sandstone, silty; sand is very fine; pale yellow; light gray below 50 ft; contains trace of rootlets; contains trace medium sand below 55 ft..	44.5	60.0
Sand to sandstone, silty; sand is very fine to fine; white.....	60.0	65.0
Sand, slightly silty, gray; very fine to medium; very fine to fine, little medium below 70 ft.....	65.0	73.0
Sand to sandstone, moderately silty; sand is very fine to fine; pale olive; contains rare rootlets.....	73.0	90.0
Sand, very fine to medium; light gray; contains rare rootlets; moderately silty from 134.5 to 145 ft; contains a little coarse below 160 ft.....	90.0	165.0
Sand to sandstone; very fine to medium grained with a little coarse; light gray; contains rootlets and clay fragments; contains less sandstone below 170 ft.....	165.0	186.0
Sand, slightly silty; sand is very fine to fine; light olive; contains reworked clay fragments and rootlets.....	186.0	195.0
Sand to sandstone, very fine to medium grained, little coarse; contains reworked siltstone, claystone, and rootlets.....	195.0	210.0
Sand, very fine to very coarse, little fine gravel; principally reworked claystone, limestone, rootlets, and chert.....	210.0	216.0
Cretaceous System - Upper Cretaceous Series - Colorado Group:		

Niobrara Formation:

Chalk, white with yellow, some chert.....	216.0	220.0
Shale, clayey, very calcareous, dark brown; contains some white speckling.....	220.0	239.0



Century GEOPHYSICAL CORP.

10-LE-99

COMPANY : Grosch
WELL : 10-LE-99
LOCATION/FIELD : Site 5
COUNTY : madison
STATE : NE
SECTION : 17

OTHER SERVICES:

downhole

None

None

TOWNSHIP : 24 RANGE : 3W

DATE : 06/02/99
DEPTH DRILLER : 239
LOG BOTTOM : 237.98
LOG TOP : 1.05

PERMANENT DATUM : None

LOG MEASURED FROM: grnd0

DRL MEASURED FROM: +1.5

KB : None

DF : None

GL : 1630

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A

FIELD OFFICE : Norfolk

RECORDED BY : sol

BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite

BOREHOLE FLUID : 0

RM : 0

RM TEMPERATURE : 0

MATRIX DELTA T : 54


FILE : PROCESSED

TYPE : 8043A

THRESH: 2500

Meadow Grove Quad
Wells 12S, 12D, & 12DD

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS



Madison Co

1993

Photo B-4

T-24-N R-3-W

20

Section 17

Not to Scale

TH #10-LE-99

SITE 10-99

1. NHEL/MW
125.1

3895
3338 864
T-8941
MT-9001

4
36.4

A2
5.4

NC

5.4
6.0
1. HEL/MW
251.5

8.2
2.1
T-8942
MT-9001

3.
10.4

17

Well LE #12 DD
Well LE #12 D
Well LE #12 S

2. HEL/MW
278.1

7.
10.8

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313

State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805

Contractor's License No. 39070

State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

6. A. Well location: SW 1/4 of the SW 1/4 of Section 17, Township 24 North, Range 3 ☐ East ☒ West, Madison County.

B. The well is 79 feet from the ☐ North or ☒ South section line and 27 feet from the ☐ East or ☒ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 10-99 (Uecker), TH # 10-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 12S (South)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.

Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No.

8. Well Construction Information.

A. Total well depth: 42 feet.B. Static water level: 19 feet.C. Pumping water level: _____ feet.
☐ Estimated or ☐ MeasuredD. Well Construction began: June 3, 1999.E. Well Construction completed: June 18, 1999.F. Bore hole diameter: 7 1/8 inches.G. Plain Casing: Diameter 2.469 ID2.875 OD inches.Type of material: PVC Schedule 40.Wall thickness: 0.203 inch(es).Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+1.5 ft. to 31.5 ft.

from _____ ft.

to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:type of material PVC Schedule 40Screen Openings (slot size) 0.010Trade Name: Titan Industries

Length(s) and placement(s) depth from

31.5 ftto 41.5 ft.

from _____ ft. to

guides at 30 ft.I. Gravel pack interval(s) from 27 ft.to 42 ft.

from _____ ft.

to _____ ft.

Grade size: Armour coatJ. Grouted/Sealed from 0 ft.to 3 ft.,with Steel cover in concrete

(type)

from 3 ft.to 27 ft.,with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotaryL. Drilling fluid: Super Gel-XM. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>19</u>	<u>Topsoil & sand, fine to medium</u>
<u>19</u>	<u>30</u>	<u>Silt, sandy, very fine, tan to red</u>
<u>30</u>	<u>46</u>	<u>Sand, fine to gravel, medium</u>
<u>46</u>	<u>66</u>	<u>Sand, very fine to fine with rootlets & silt layers</u>
<u>66</u>	<u>72</u>	<u>Sand, fine</u>
<u>72</u>	<u>83</u>	<u>Silt, very sandy, light olive</u>
<u>83</u>	<u>133</u>	<u>Interbedded sandstone & sand</u>
<u>133</u>	<u>145</u>	<u>Clay, very silty to very sandy</u>
<u>145</u>	<u>186</u>	<u>Interbedded sand and sandstone with some silt layers & clay</u>
<u>186</u>	<u>216</u>	<u>Interbedded sand, sandstone, claystone, silty</u>
<u>216</u>	<u>225</u>	<u>Clay, shaley, chalky, yellow</u>

Depth in Feet		Description
From	To	
<u>225</u>	<u>239</u>	<u>Chalk, clayey, dark gray</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature _____

Date _____

Water Well Owner's Signature _____

Date _____

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk
Telephone Number (402) 371-7313
State NE Zip Code 68701 +
2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill
Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +
3. Permit Number(s) _____
4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)
5. Replacement and abandoned well information.
A. Is this well a replacement well? ☐ Yes ☒ No
C. Replacement well is _____ feet from abandoned well
E. Original well pump column size: _____ inches.
G. Location of water use of abandoned well: _____
D. Abandoned well last operated _____
F. Completion of original well abandonment on _____
6. A. Well location: SW 1/4 of the SW 1/4 of Section 17, Township 24 North, Range 3 ☐ East ☒ West, Madison County.
B. The well is 85 feet from the ☐ North or ☒ South section line and 29 feet from the ☐ East or ☒ West section line.
C. Street address or block, lot and subdivision, if applicable: Site 10-99 (Uecker), TH # 10-LE-99
D. Location of water use, if applicable (give legal descriptions):
E. If for irrigation, the land to be irrigated is _____ acres.
F. Well reference letter(s), if applicable: Well LE # 12D (Center)
7. Pump Information.
Is pump installed at this time? ☐ Yes ☒ No
If yes, complete items A through F.
If no, complete items A and D with estimated information for those wells in which pump will be installed.
A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒
B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.
D. Pumping equipment-date installed: August, 1999. E. Brand/Type: Grundfos Rediflo2
F. Pump installed by: Contractor ☐ Owner ☒ Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 133 feet.

B. Static water level: 19.4 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: June 3, 1999.

E. Well Construction completed: June 18, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID

2.875 OD inches.

Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+1.5 ft.

to 127 ft.

from _____ ft.

to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from

127 ft.

to 132 ft.

from _____ ft. to

guides at 126 ft.

I. Gravel pack interval(s) from 122 ft.

to 133 ft.

from _____ ft.

to _____ ft.

Grade size: 10/20

J. Grouted/Sealed from 0 ft.

to 3 ft.,

with Steel cover in concrete

(type)

from 3 ft.

to 122 ft.,

with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>19</u>	<u>Topsoil & sand, fine to medium</u>
<u>19</u>	<u>30</u>	<u>Silt, sandy, very fine, tan to red</u>
<u>30</u>	<u>46</u>	<u>Sand, fine to gravel, medium</u>
<u>46</u>	<u>66</u>	<u>Sand, very fine to fine with rootlets & silt layers</u>
<u>66</u>	<u>72</u>	<u>Sand, fine</u>
<u>72</u>	<u>83</u>	<u>Silt, very sandy, light olive</u>
<u>83</u>	<u>133</u>	<u>Interbedded sandstone & sand</u>
<u>133</u>	<u>145</u>	<u>Clay, very silty to very sandy</u>
<u>145</u>	<u>186</u>	<u>Interbedded sand & sandstone with some silt layers & clay</u>
<u>186</u>	<u>216</u>	<u>Interbedded sand, sandstone & claystone, silty</u>
<u>216</u>	<u>225</u>	<u>Clay, shaley, chalky, yellow</u>
<u>225</u>	<u>239</u>	<u>Chalk, clayey, dark gray</u>

Depth in Feet		Description
From	To	

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313

State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805

Contractor's License No. 39070

State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

6. A. Well location: SW 1/4 of the SW 1/4 of Section 17, Township 24 North, Range 3 ☐ East ☒ West, Madison County.

B. The well is 98 feet from the ☐ North or ☒ South section line and 28 feet from the ☐ East or ☒ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 10-99 (Uecker), TH # 10-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 12DD (North)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.

Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No.

8. Well Construction Information.

A. Total well depth: 179 feet.

B. Static water level: 20.7 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: June 2, 1999.

E. Well Construction completed: June 18, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID 2.875 OD inches. Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es). Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from +1.5 ft. to 174 ft. from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in: type of material PVC Schedule 40

Screen Openings (slot size) 0.010 Trade Name: Titan Industries

Length(s) and placement(s) depth from 174 ft. to 179 ft. from _____ ft. to _____ ft. guides at 172 ft.

I. Gravel pack interval(s) from 168 ft. to 179 ft. from _____ ft. to _____ ft. Grade size: 10/20

J. Grouted/Sealed from 0 ft. to 3 ft., with Steel cover in concrete
(type)

from 3 ft. to 168 ft., with Benseal/EZ-Mud
(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting 1.0 hour

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? ☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>19</u>	<u>Topsoil & sand, fine to medium</u>
<u>19</u>	<u>30</u>	<u>Silt, sandy, very fine, tan to red</u>
<u>30</u>	<u>46</u>	<u>Sand, fine to gravel, medium</u>
<u>46</u>	<u>66</u>	<u>Sand, very fine to fine with rootlets & silt layers</u>
<u>66</u>	<u>72</u>	<u>Sand, fine</u>
<u>72</u>	<u>83</u>	<u>Silt, very sandy, light olive</u>
<u>83</u>	<u>133</u>	<u>Interbedded sandstone & sand</u>
<u>133</u>	<u>145</u>	<u>Clay, very silty to very sandy</u>
<u>145</u>	<u>186</u>	<u>Interbedded sand & sandstone with some silt layers and clay</u>
<u>186</u>	<u>216</u>	<u>Interbedded sand, sandstone & claystone, silty</u>
<u>216</u>	<u>225</u>	<u>Clay, shaley, chalky, yellow</u>
<u>225</u>	<u>239</u>	<u>Chalk, clayey, dark gray</u>

Depth in Feet		Description
From	To	

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

SITE # 10-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENRD P II	Well Number 12 S	Date Drilled 6/3/99	Date Constructed 6/3/99	Ground Elevation 1630(6)
County MADISON	Qtr/Qtr/Qtr SW SW SW	Section 17	Township 24 N	Range 3W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By <i>Gal</i>	Total Depth 42

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED 35 ft
Type/Size of Screen 2 1/2" ID SCH 40 10-FOOT
Screen Slot Size 0.010
Filter Pack AX GRAVEL 6 BUCKETS
Type/Amount Grout/Fill BENSEAL/EZ-MUD 1 BAG 40 GAL.
Type/Amount Seal TOP PLUG

Elevation Depth
From
Reference3.2 TOP OF CASING0.0 GROUND3 TOP OF
GROUT/FILL19.0 WATER LEVEL27 TOP OF FILTER PACK31.5 TOP OF SCREEN41.5 BOTTOM OF SCREEN42 BOREHOLE DEPTHLOCKING, STEEL
PROTECTIVE COVER

TOP CAP

CONCRETE
SURFACE SEAL

GROUT OR FILL

WELL CASING

FILTER PACK

WELL SCREEN

BOTTOM CAP

SOUTH WELL

SITE # 10-99

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LENERD PII	Well Number 12D	Date Drilled 6/3/99	Date Constructed 6/3/99	Ground Elevation 1630 (E)
County MADISON	Qtr/Qtr/Qtr SW SW SW	Section 17	Township 24 N	Range 3W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By <i>Pol</i>	Total Depth 133

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FUSH/THREADED 130 ft
Type/Size of Screen 2 1/2" ID SCH 40 5-FOOT
Screen Slot Size 0.010
Filter Pack 10/20 Si Sd 4 BAGS
Type/Amount Grout/Fill BENSEAL/EZ-MUD 6 BAGS 240 GAL
Type/Amount Seal N/A

Elevation Depth
From
Reference

 3 TOP OF CASING

 0.0 GROUND

 3 TOP OF
GROUT/FILL


 19.4 WATER LEVEL

 122 TOP OF FILTER PACK

 127 TOP OF SCREEN

 132 BOTTOM OF SCREEN

 133 BOREHOLE DEPTH




CENTER WELL

WELL COMPLETION LOG

Project 1999 LEND PII	Well Number 12 DD	Date Drilled 6/2/99	Date Constructed 6/2/99	Ground Elevation 1430(4)
County MADISON	Qtr/Qtr/Qtr SW SW SW	Section 17	Township 24 N	Range 3 W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By Jof	Total Depth 180

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID PVC SCH 40 177'-ft
Type/Size of Screen 2 1/2" ID SCH 40 THREADED FLUSH 5-FOOT
Screen Slot Size 0.010
Filter Pack 10/20 Si Sd 4 BAGS * CAVE
Type/Amount Grout/Fill BENSEAL/EZ-MIX 9 BAGS 360 GAL.
Type/Amount Seal BOTTOM PLUG 1/2 BAG H.P.



* NATURAL PACK ALSO

NORTH WELL


Number 13 Well

MADISON COUNTY

TH# 11-LE-99

13 WELL

STOLLE SITE



T24N R3W SECTION 29 NW44

MEADOW GROVE QUAD

Test Hole #11-LE-99 (E-log)
(24N-3W-29bccc)
Madison County

Location: SW SW SW NW sec. 29, T. 24 N., R. 3 W., approximately
 2,500 feet south and 35 feet east of northwest corner.

Ground elevation: 1,612 ft. (t) (Meadow Grove, 7.5 min. quadrangle)

Depth to water: 0.7 ft. (6/16/99) Well installed.

Depth, in feet
 From To

Quaternary System, undifferentiated:

Top soil: silt, very sandy, slightly clayey, black; sand is very fine.....	0.0	2.0
Silt, clayey, very sandy, tan to gray.....	2.0	10.0
Silt, very sandy, slightly clayey, moderately cal- careous, black; sand is very fine; contains bone fragment.....	10.0	16.5
No sample.....	16.5	20.0
Sand, very fine to medium, trace coarse; contains shell fragments; trace of very fine gravel and shell fragments below 30 ft.....	20.0	35.0
Sand, gravelly; very fine sand to medium gravel; contains shell fragments.....	35.0	40.0
Sand, very fine to coarse; contains shell fragments; contains trace of very coarse sand below 45 ft....	40.0	50.0
Sand, very fine to coarse, trace of very coarse; contains shell fragments.....	50.0	60.0
Sand, gravelly; very fine sand to fine gravel; trace of medium gravel below 65.5 ft.....	60.0	69.5


Tertiary System - Miocene Series - Ogallala Group:

Silt, very sandy, slightly clayey, very calcareous, pale yellow; sand is very fine with trace of fine.	69.5	72.5
Sand, silty, olive gray; sand is very fine to fine, little medium, trace of coarse; limy grains.....	72.5	88.0
Silt, very sandy, slightly clayey, light gray with olive tint; sand is very fine to fine; contains limy grains.....	88.0	115.0
Sand, very fine to fine; light olive gray; contains rootlets; some sandstone lenses.....	115.0	125.5
Silt, very clayey, very sandy, yellow; sand is very fine to fine; contains reworked sandstone, chalky clay, and ironstone fragments.....	125.5	135.0

Cretaceous System - Upper Cretaceous Series - Colorado Group:

Niobrara Formation:

Shale, very calcareous, yellow.....	135.0	160.0
-------------------------------------	-------	-------



Century GEOPHYSICAL CORP.

11-LE-99

COMPANY : Grosch
WELL : 11-LE-99
LOCATION/FIELD : Site 11
COUNTY : madison
STATE : NE
SECTION : 29

OTHER SERVICES:

downhole
None
None

TOWNSHIP : 24 RANGE : 3W

DATE : 06/03/99
DEPTH DRILLER : 160
LOG BOTTOM : 160.67
LOG TOP : 1.31

PERMANENT DATUM : None

LOG MEASURED FROM: grnd
DRL MEASURED FROM: +1

KB : None
DF : None
GL : 1612

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : sol

BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite


BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54

FILE : PROCESSED
TYPE : 8043A


THRESH: 2500

Meadow Grove Quad
Well 13S

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS



Madison Co 1993 Photo C-4
T-24-N R-3-W 30 Section 29
Not to Scale
TH # 11-LE-99 SITE 11-99



STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313
State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(Indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____.

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____.

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well:

6. A. Well location: SW 1/4 of the NW 1/4 of Section 29, Township 24 North, Range 3 ☐ East ☒ West, Madison County.

B. The well is 2500 feet from the ☒ North or ☐ South section line and 35 feet from the ☐ East or ☒ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 11-99 (Stolle), TH 11-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 13S

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.

Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 33 feet.

B. Static water level: 0.7 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: June 4, 1999.

E. Well Construction completed: June 18, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID

2.875 OD inches.

Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+1.5 ft

to 20 ft.

from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from

20 ft

to 30 ft.

from _____ ft. to

guides at 19 ft.

I. Gravel pack interval(s) from 17 ft.

to 33 ft.

from _____ ft. to _____ ft.

Grade size: Armour coat

J. Grouted/Sealed from 0 ft.

to 3 ft.,

with Steel cover in concrete

(type)

from 3 ft.

to 17 ft.,

with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .5 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>16</u>	<u>Topsoil & clay, very silty, brown to black</u>
<u>16</u>	<u>29</u>	<u>Sand, fine to gravel, fine</u>
<u>29</u>	<u>33</u>	<u>Silt, sandy, fine to medium sand</u>
<u>33</u>	<u>40</u>	<u>Gravel, coarse, some medium sand</u>
<u>40</u>	<u>68</u>	<u>Sand, medium to gravel, coarse, some silt layers</u>
<u>68</u>	<u>73</u>	<u>Clay, silty, pale yellow</u>
<u>73</u>	<u>87</u>	<u>Interbedded fine sand & sandstone, some olive silt layers</u>
<u>87</u>	<u>115</u>	<u>Interbedded claystone & silty sandstone</u>
<u>115</u>	<u>125</u>	<u>Sandstone, silty</u>
<u>125</u>	<u>135</u>	<u>Chalk, weathered, clayey, yellow</u>
<u>135</u>	<u>160</u>	<u>Chalk, clayey, very calcareous</u>

Depth in Feet		Description
From	To	

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature


Date

TH # 11-LE-99

SITE # 11-99

WELL COMPLETION LOG

Project 1999 LEND PII	Well Number 135	Date Drilled 6/4/99	Date Constructed 6/4/99	Ground Elevation 1612(±)
County MADISON	Qtr/Qtr/Qtr SW SW NW	Section 29	Township 24 N	Range 3 W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By Jap	Total Depth 33




Number 14 Wells

MADISON COUNTY

TH # 12-LE-99

14 WELLS

POSAR SITE



T22N R2W SECTION 8 NE 1/4

BATTLE CREEK QUAD

Test Hole #12-LE-99 (E-log)
(22N-2W-8adda)
Madison County

Location: NE SE SE NE Sec. 8, T. 22 N., R. 2 W., approximately
 1,989 feet south and 33 feet west of northeast corner.
 Ground elevation: 1,755 ft. (t) (Battle Creek, 7.5 min. quadrangle)
 Depth to water: 110.7-ft.(6/16/99) Wells installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Top soil: silt, slightly clayey, slightly calcareous, dark brown; contains some very fine sand....	0.0	5.0
Silt, moderately clayey, slightly calcareous, yellowish brown; contains very fine sand, some yellow stain below 10 ft.....	5.0	40.0
Silt, moderately clayey, slightly sandy, slightly calcareous, dark brown; sand is very fine to medium.....	40.0	45.0
Silt, very sandy, slightly clayey, brown; sand is very fine to medium; contains limy grains; some yellow stain below 55 ft.....	45.0	60.0
Silt, very sandy, slightly clayey, brown; sand is very fine to medium.....	60.0	65.0
Silty sand to sandy silt, slightly clayey, yellowish brown; sand is very fine to medium.....	65.0	70.0
Sand, silty, slightly clayey, reddish brown; sand is very fine to medium, rare coarse below 75 ft.....	70.0	82.0
Silty sand to sandy silt, slightly clayey, gray; sand is very fine to medium.....	82.0	90.0
Silt, very sandy, olive gray; sand is very fine to fine; moderately sandy below 100 ft.....	90.0	105.5
Sand, very fine to fine; light gray; rare coarse sand to very fine gravel grains below 110 ft.....	105.5	115.0
Sand, very fine to medium, rare coarse grains, gray.	115.0	125.0
Sand, very fine to very coarse, contains trace of fine gravel; greenish gray.....	125.0	130.0
Sand, gravelly; medium sand to fine gravel; greenish gray; silty below 134.5 ft.....	130.0	140.0
Sand, very fine to fine.....	140.0	158.0
Silt, very sandy, bluish gray; sand is very fine; contains much coarse.....	158.0	160.0
Silt, moderately to very clayey, very sandy, moderately calcareous; sand is very fine to fine; contains shell fragments below 170 ft.....	160.0	173.0
Sand, very fine to fine; gray; contains much dark		

silicates.....	173.0	180.5
Silt, very clayey, moderately to very sandy, very calcareous, bluish gray; sand is very fine to fine; very sandy with abundant shell fragments below 187 ft.....	180.5	200.0
Sand, very fine to coarse, little very coarse; gray to greenish gray; contains abundant shell fragments.....	200.0	205.0
Sand, very fine to coarse; gray; contains trace of shell fragments.....	205.0	210.0
Sand, very fine to fine; gray; contains shell fragments.....	210.0	215.0
Sand, very fine to medium, little coarse; gray.....	215.0	220.0
Sand, very fine to very coarse, little fine gravel; gray; contains less fine gravel from 230 to 235 ft.....	220.0	240.0
Sand, slightly gravelly; very fine sand to fine gravel, trace medium gravel; gray; slightly more gravel below 255 ft.....	240.0	270.0
Gravel, sandy; coarse sand to fine gravel; gray.....	270.0	275.0
Gravel, sandy; very coarse sand to medium gravel; little coarse gravel below 280 ft; gray.....	275.0	290.0
Gravel, sandy; medium sand to medium gravel; gray; contains rare coarse gravel below 295 ft.....	290.0	300.0
Gravel, sandy, silty; contains coarse sand to medium gravel.....	300.0	310.0
Tertiary System - Miocene Series - Ogallala Group:		
Sand, very fine to very coarse; gray; contains limy grains and shell fragments.....	310.0	315.0
Sand, very fine to medium, little coarse; gray; contains shell fragments and limy grains.....	315.0	320.0
Sand, very fine to fine, some medium; gray; contains shell fragments and limy grains.....	320.0	330.0
Sand, very fine to very coarse; gray; much limy grains and shells; rare gravel limestone below 340 ft.....	330.0	345.0
Sand, very fine to coarse, little very coarse; gray; contains shell fragments and limy grains.....	345.0	370.0
Gravel, sandy; very fine sand to very fine gravel, little fine gravel; principally reworked limestone.....	370.0	373.0
Sand, very fine to coarse, trace of very coarse; contains limy shale.....	373.0	375.0
Cretaceous System - Upper Cretaceous Series - Colorado Group:		
Niobrara Formation:		
Shale, clayey, very calcareous, light gray.....	375.0	400.0



Century GEOPHYSICAL CORP.

12-LE-99

COMPANY : Grosch
WELL : 12-LE-99
LOCATION/FIELD : Site 13
COUNTY : madison
STATE : NE
SECTION : 8

OTHER SERVICES:

downhole
None
None

TOWNSHIP : 22 RANGE : 2W

DATE : 06/08/99
DEPTH DRILLER : 400
LOG BOTTOM : 399.45
LOG TOP : 2.75

PERMANENT DATUM : None

LOG MEASURED FROM: grnd
DRL MEASURED FROM: +1.5
KB : None
DF : None
GL : 1755

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : sol

BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite


BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54

FILE : PROCESSED
TYPE : 8043A

THRESH: 2500

Battle Creek Quad
Wells 14S & 14D

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS



7-78

Madison Co 1993

Photo H-7

T-22-N R-2-W 40

Section 8

1. HEL/NW
17.3

Not to Scale

TH #12-LE-99

SITE 13-99

1101

T-2490

1. HEL/NW
6.7

1140

T-238

1. HEL/NW
155.8

1. HEL/NW
131.6

Well LE #14 D
Well LE #14 S

8

3271
T-1390

1131

T-213

1. HEL/W
118.3

1. HEL/NW
146.9

4. NHEL/W
25.5

NC

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District Telephone Number (402) 371-7313
Address 601 E Benjamin Avenue Suite 102
City Norfolk State NE Zip Code 68701 +
2. Drilling Firm Grosch Irrigation Telephone Number (402) 336-1805
Address RR1 Box 77J Contractor's License No. 39070
City O'Neill State NE Zip Code 68763 +
3. Permit Number(s) _____
4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)
5. Replacement and abandoned well information.
A. Is this well a replacement well? ☐ Yes ☒ No D. Abandoned well last operated _____,
C. Replacement well is _____ feet from abandoned well F. Completion of original well abandonment on _____,
E. Original well pump column size: _____ inches.
G. Location of water use of abandoned well: _____
6. A. Well location: SE 1/4 of the NE 1/4 of Section 8, Township 22 North, Range 2 ☐ East ☒ West, Madison County.
B. The well is 1993 feet from the ☒ North or ☐ South section line and 32 feet from the ☒ East or ☐ West section line.
C. Street address or block, lot and subdivision, if applicable: Site 13-99 (Pojar), TH # 12-LE-99
D. Location of water use, if applicable (give legal descriptions):
E. If for irrigation, the land to be irrigated is _____ acres.
F. Well reference letter(s), if applicable: Well LE # 14S (South)
7. Pump Information.
Is pump installed at this time? ☐ Yes ☒ No
If yes, complete items A through F.
If no, complete items A and D with estimated information for those wells in which pump will be installed.
A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒
B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.
D. Pumping equipment-date installed: August, 1999. E. Brand/Type: Grundfos Rediflo2
F. Pump installed by: Contractor ☐ Owner ☒ Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 154 feet.

B. Static water level: 110.7 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: June 9, 1999.

E. Well Construction completed: June 18, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID

2.875 OD inches.

Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es).

Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+1.5 ft

to 144 ft.

from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:

type of material PVC Schedule 40

Screen Openings (slot size) 0.010

Trade Name: Titan Industries

Length(s) and placement(s) depth from

144 ft

to 154 ft.

from _____ ft. to _____ ft.

guides at 142 ft.

I. Gravel pack interval(s) from 138 ft.

to 154 ft.

from _____ ft. to _____ ft.

Grade size: 10/20

J. Grouted/Sealed from 0 ft.

to 3 ft.,

with Steel cover in concrete
(type)

from 3 ft.

to 138 ft.,

with Benseal/EZ-Mud
(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .75 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>42</u>	<u>Topsoil & silt, clayey, light to dark yellow brown</u>
<u>42</u>	<u>54</u>	<u>Silt, very sandy, sand, fine to medium</u>
<u>54</u>	<u>81</u>	<u>Clay & silt, some sandy layers, yellow brown with iron staining</u>
<u>81</u>	<u>104</u>	<u>Gravel, fine with medium to coarse sand</u>
<u>104</u>	<u>115</u>	<u>Gravel, fine with medium sand</u>
<u>115</u>	<u>133</u>	<u>Sand, fine to medium & gravel, fine with clay lenses</u>
<u>133</u>	<u>136</u>	<u>Clay, sandy</u>
<u>136</u>	<u>157</u>	<u>Sand, fine with fine gravel at base</u>
<u>157</u>	<u>172</u>	<u>Clay, silty, blue-gray</u>
<u>172</u>	<u>179</u>	<u>Sand, medium</u>
<u>179</u>	<u>191</u>	<u>Clay, blue-gray with shells</u>
<u>191</u>	<u>197</u>	<u>Sand, fine to medium</u>

Depth in Feet		Description
From	To	
<u>197</u>	<u>201</u>	<u>Clay, blue-gray with shells</u>
<u>201</u>	<u>311</u>	<u>Gravel, fine to coarse, some sand, thin silty clay layers</u>
<u>311</u>	<u>361</u>	<u>Interbedded claystone & siltstone with some sand</u>
<u>361</u>	<u>373</u>	<u>Interbedded very fine to fine sand & sandstone, some limestone lenses</u>
<u>373</u>	<u>400</u>	<u>Chalk, clayey, light gray with limestone layers</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313
State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

- A. Is this well a replacement well? ☐ Yes ☒ No
C. Replacement well is _____ feet from abandoned well
E. Original well pump column size: _____ inches.
G. Location of water use of abandoned well:
- D. Abandoned well last operated _____,
F. Completion of original well abandonment on _____.

6. A. Well location: SE 1/4 of the NE 1/4 of Section 8, Township 22 North, Range 2 ☐ East ☒ West, Madison County.
B. The well is 1989 feet from the ☒ North or ☐ South section line and 33 feet from the ☒ East or ☐ West section line.
C. Street address or block, lot and subdivision, if applicable: Site 13-99 (Pojar), TH # 12-LE-99
D. Location of water use, if applicable (give legal descriptions):
E. If for irrigation, the land to be irrigated is _____ acres.
F. Well reference letter(s), if applicable: Well LE # 14D (North)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

- A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒
B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.
D. Pumping equipment-date installed: August, 1999. E. Brand/Type: Grundfos Rediflo2
F. Pump installed by: Contractor ☐ Owner ☒ Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 294 feet.

B. Static water level: 120.8 feet.

C. Pumping water level: _____ feet.
☐ Estimated or ☐ Measured

D. Well Construction began: June 9, 1999.

E. Well Construction completed: June 18, 1999.

F. Bore hole diameter: 7 1/8 inches.

G. Plain Casing: Diameter 2.469 ID 2.875 OD inches. Type of material: PVC Schedule 40.

Wall thickness: 0.203 inch(es). Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from +1.5 ft. to 285 ft. from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in: type of material PVC Schedule 40

Screen Openings (slot size) 0.010 Trade Name: Titan Industries

Length(s) and placement(s) depth from 285 ft. to 290 ft. from _____ ft. to _____ ft. guides at 283 ft.

I. Gravel pack interval(s) from 278 ft. to 294 ft. from _____ ft. to _____ ft. Grade size: Armour coat

J. Grouted/Sealed from 0 ft. to 3 ft., with Steel cover in concrete
(type)

from 3 ft. to 278 ft., with Benseal/EZ-Mud
(type)

K. Drilling method: Mud rotary

L. Drilling fluid: Super Gel-X

M. Well development technique (total time and method): Water jetting .75 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system? ☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>42</u>	<u>Topsoil & silt, clayey, light to dark yellow brown</u>
<u>42</u>	<u>54</u>	<u>Silt, very sandy & sand, fine to medium</u>
<u>54</u>	<u>81</u>	<u>Clay & silt, some sandy layers, yellow brown with iron staining</u>
<u>81</u>	<u>104</u>	<u>Clay, silty, gray, some sand lenses</u>
<u>104</u>	<u>115</u>	<u>Gravel, fine with medium to coarse sand</u>
<u>115</u>	<u>133</u>	<u>Sand, fine to medium & gravel, fine, with clay lenses</u>
<u>133</u>	<u>136</u>	<u>Clay, sandy</u>
<u>136</u>	<u>157</u>	<u>Sand, fine with fine gravel at the base</u>
<u>157</u>	<u>172</u>	<u>Clay, silty, blue-gray</u>
<u>172</u>	<u>179</u>	<u>Sand, medium</u>
<u>179</u>	<u>191</u>	<u>Clay, blue-gray with shells</u>
<u>191</u>	<u>197</u>	<u>Sand, fine to medium</u>

Depth in Feet		Description
From	To	
<u>197</u>	<u>201</u>	<u>Clay, blue-gray with shells</u>
<u>201</u>	<u>311</u>	<u>Gravel, fine to coarse</u>
<u>311</u>	<u>361</u>	<u>Interbedded claystone & siltstone with some sand</u>
<u>361</u>	<u>373</u>	<u>Interbedded very fine to fine sand & sandstone with some limestone lenses</u>
<u>373</u>	<u>400</u>	<u>Chalk, clayey, light gray</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

CONSERVATION AND SURVEY DIVISION--UNL

WELL COMPLETION LOG

Project 1999 LEND PII	Well Number 145	Date Drilled 6/9/99	Date Constructed 6/10/99	Ground Elevation 1755(4)
County MADISON	Qtr/Qtr/Qtr SESE NE	Section 8	Township 22N	Range 2W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By <i>Gal</i>	Total Depth 154

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID SCH 40 FLUSH/THREADED
147 ft
Type/Size of Screen 2 1/2" ID SCH 40
10-FT
Screen Slot Size 0.010
Filter Pack 10/20 Si Sd 5 BAGS 1 BUCKET AX
Type/Amount Grout/Fill BENSEAL/EZ-MUD 6 BAGS 240 GAL
Type/Amount Seal
TOP SEAL 6/10/99

Elevation Depth
From
Reference

3.2 TOP OF CASING

0.0 GROUND

3 TOP OF
GROUT/FILL

110.7 WATER LEVEL

* 139 TOP OF FILTER PACK

144 TOP OF SCREEN

154 BOTTOM OF SCREEN

BOREHOLE DEPTH

LOCKING, STEEL
PROTECTIVE COVER

TOP CAP

CONCRETE
SURFACE SEAL

GROUT OR FILL **

WELL CASING

FILTER PACK

WELL SCREEN

BOTTOM CAP

* NATURAL PACK
CAVING FM

** TOPPED 10ft OFF
U/ HOLE PLUG

6/10 DEV .75 hr

SOUTH WELL

SITE# 13-99

Project 1999 LENRD PII	Well Number 14D	Date Drilled 6/9/99	Date Constructed 6/9/99	Ground Elevation 1755(t)
County MADISON	Qtr/Qtr/Qtr SE SE NE	Section 8	Township 22 N	Range 2 W
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By <i>Joel</i>	Total Depth 294

7 1/8"

Elevation	Depth From Reference
-----------	----------------------------

2 1/2" ID PVC SCH 40

289-ft

Type/Size of Screen
2 1/2" ID SCH 40
THREADED FLUSH

5-FOOT

0.510

AX GRAVEL
9 BUCKETS

BENSAC/EZ-MUD
13 BAGS
520 GAL

BOTTOM PLUG

TDP PLUG

3.5 TOP OF CASING

O.O GROUND

3 TOP OF
GROUT/FILL

120.8 WATER LEVEL

278 TOP OF FILTER PACK

285 TOP OF SCREEN

290 BOTTOM OF SCREEN

294 SEAL TOP

N/A SEAL BOTTOM

400 BOREHOLE DEPTH

**LOCKING, STEEL
PROTECTIVE COVER**

TOP CAP

CONCRETE SURFACE SEAL

GROUT OR FILL

WELL CASING

FILTER PACK

WELL SCREEN

BOTTOM CAP

- BENTONITE PLUG } THICK
- GRAVEL FILL } MUD + CLAY

GRAVEL FILL

6/10 DEV .75 hr

NORTH WELL


Number 15 Wells

STANTON COUNTY

TH #13-LE-99

#15 WELLS

DICKE SITE



T22N R1E SECTION 18 SWY4

MADISON NE QUAD

Test Hole #13-LE-99 (E-log)
(22N-1E-18cbbc)
Stanton County


Location: SW NW NW SW Sec. 18, T. 22 N., R. 1 E., approximately
 2,168 feet north and 26 feet east of southwest corner.
 Ground elevation: 1,610 ft. (t) (Madison NE, 7.5 min. quadrangle)
 Depth to water: 72.1 ft. (6/24/99) Wells installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Top soil: silt, slightly clayey, sandy, dark brown; sand is very fine.....	0.0	3.0
Sand, very fine to medium; light brown.....	3.0	5.0
Sand, silty; sand is very fine to fine; brown; yel- lowish brown below 10 ft.....	5.0	15.5
Silt, moderately clayey, moderately sandy, slightly calcareous, yellowish brown; sand is very fine....	15.5	22.0
Silt, moderately clayey, moderately sandy, slightly calcareous, dark bluish gray; sand is very fine...	22.0	35.0
Silt, moderately clayey, moderately sandy, slightly calcareous, very dark gray.....	35.0	40.0
Silt, moderately clayey, moderately sandy, slightly calcareous, dark greenish gray; sand is very fine; moderately calcareous below 50 ft.....	40.0	64.0
Till: clay, silty, sandy, moderately calcareous, greenish gray.....	64.0	72.0
Till: clay, silty, sandy, gravelly, moderately cal- careous, dark gray.....	72.0	142.0
Sand, very silty; sand is very fine to coarse; dark gray.....	142.0	145.0
Sand, gravelly; fine sand to fine gravel; dark gray.	145.0	150.0
Gravel, sandy; medium sand to coarse gravel; dark gray.....	150.0	155.0
Gravel, coarse to very coarse.....	155.0	176.0
Silt, very clayey, very calcareous, greenish gray; contains shell fragments.....	176.0	185.0
Gravel, fine to medium; contains interbedded silty clay lenses.....	185.0	190.0
Clay, silty, sandy, moderately calcareous, olive gray; sand is very fine to fine (much gravel from above).....	190.0	197.0
Gravel, sandy; coarse sand to fine gravel, some medium gravel.....	197.0	209.0
Clay, silty, yellow; pinkish tint from 220 to 225 ft; some dark brown shale clay below 230 ft.....	209.0	235.0

Cretaceous System - Upper Cretaceous Series - Colorado Group:

Niobrara Formation:

Clay, shaley, chalky, yellow to orange yellow.....	235.0	240.0
Shale, clayey, moderately calcareous, light gray....	240.0	245.0



Century GEOPHYSICAL CORP.

13-LE-99

COMPANY : Grosch
WELL : 13-LE-99
LOCATION/FIELD : Site 16
COUNTY : Stanton
STATE : NE
SECTION : 18

OTHER SERVICES:

downhole
None
None

TOWNSHIP : 22 RANGE : 1E

DATE : 06/10/99
DEPTH DRILLER : 245
LOG BOTTOM : 245.07
LOG TOP : -8.56

PERMANENT DATUM : None

LOG MEASURED FROM: grnd

KB : None

DF : None

DRL MEASURED FROM: +1.5

GL : ~~1605~~ 1610 *

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : sol

BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite

BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54


FILE : PROCESSED
TYPE : 8043A

THRESH: 2500

Madison NE Quad
Wells 15S & 15M

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS

* epd 11/99



NOT TO SCALE

STANTON COUNTY 1987
T-22-N R-1-E 10
TH #13-LE-99

PHOTO A-9
SEC. 18
SITE 16-99

1241 NHEL/NW 1.12.6

T-1482

NHEL/NW
2.43

151.0
152.0
ERP

Well LE #15M
Well LE #15S

NHEL/NW
152.0

151.0
150.0
ERP

1143
T-1482

18

NHEL/NW
2.19.5

NHEL
4.131.7

NHEL/NW
3.27.3

NHEL
2.54

1239
T-1415

1338
T-1415

1174
T-1415

1220
T-1415

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City NorfolkTelephone Number (402) 371-7313
State NE Zip Code 68701 +2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'NeillTelephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s)

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other
(indicate use)

5. Replacement and abandoned well information.

- A. Is this well a replacement well?
- ☐
- Yes
- ☒
- No D. Abandoned well last operated _____,
-
- C. Replacement well is _____ feet from abandoned well F. Completion of original well abandonment on _____,
-
- E. Original well pump column size: _____ inches.
-
- G. Location of water use of abandoned well:

5. A. Well location:
- NW
- 1/4 of the
- SW
- 1/4 of Section
- 18
- , Township
- 22
- North, Range
- 1
- East
- ☒
- West
- ☐
- Stanton
- County.
-
- B. The well is
- 2168
- feet from the
- ☐
- North or
- ☒
- South section line and
- 26
- feet from the
- ☐
- East or
- ☒
- West section line.
-
- C. Street address or block, lot and subdivision, if applicable:
- Site 16-99 (Dicke) TH# 13-LE-99
-
- D. Location of water use, if applicable (give legal descriptions):
-
- E. If for irrigation, the land to be irrigated is _____ acres.
-
- F. Well reference letter(s), if applicable:
- Well LE#15S(South)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

- A. Actual pumping rate, if applicable:
- 3-8
- gallons per minute. Measured
- ☐
- or Estimated
- ☒
-
- B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.
-
- D. Pumping equipment-date installed:
- August, 1999
- . E. Brand/Type:
- Grundfos Rediflo2
-
- F. Pump installed by: Contractor
- ☐
- Owner
- ☒
- Pump Installer
- ☐
- License No.

8. Well Construction Information.

A. Total well depth: 155 feet.B. Static water level: 80.6 feet.C. Pumping water level: _____ feet.
☐ Estimated or ☐ MeasuredD. Well Construction began: June 11, 1999.E. Well Construction completed: June 28, 1999.F. Bore hole diameter: 7 1/8 inches.G. Plain Casing: Diameter 2.469 ID2.875 OD inches.Type of material: PVC Schedule 40.Wall thickness: 0.203 inch(es).Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+2 ftto 143.5 ft.

from _____ ft.

to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:type of material PVC Schedule 40Screen Openings (slot size) 0.010Trade Name: Titan Industries

Length(s) and placement(s) depth from

143.5 ftto 153.5 ft.

from _____ to _____ ft.

guides at 140 ft.I. Gravel pack interval(s) from 140.5 ft. to 155 ft.

from _____ ft. to _____ ft.

Grade size: 10/20J. Grouted/Sealed from 0 ft. to 3 ft.,with Steel cover in concrete

(type)

from 3 ft.to 140.5 ft.,with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotaryL. Drilling fluid: Super Gel-XM. Well development technique (total time and method): Water jetting .5 Hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>3</u>	<u>Topsoil, silt, sandy dark brown</u>
<u>3</u>	<u>14</u>	<u>Sand, fine-medium, silty some clay</u>
<u>14</u>	<u>21</u>	<u>Silt, clayey, yellow brown</u>
<u>21</u>	<u>40</u>	<u>Clay, silty, dark brown-gray</u>
<u>40</u>	<u>60</u>	<u>Clay, slightly silty, dark green-gray</u>
<u>60</u>	<u>72</u>	<u>Clay, silty, slightly sandy, some gravel, yellow brown</u>
<u>72</u>	<u>141</u>	<u>Clay, silty, some limestone pebbles & sand, dark gray</u>
<u>141</u>	<u>175</u>	<u>Sand & Gravel, coarse sand to coarse gravel</u>

Depth in Feet		Description
From	To	
<u>175</u>	<u>186</u>	<u>Clayey silt to silty clay, green</u>
<u>186</u>	<u>190</u>	<u>Gravel, fine-medium, red</u>
<u>190</u>	<u>196</u>	<u>Clay, silty, sandy</u>
<u>196</u>	<u>208</u>	<u>Gravel, medium-coarse some silt layers</u>
<u>208</u>	<u>234</u>	<u>Clay, yellow-pink</u>
<u>234</u>	<u>245</u>	<u>Clay, shaley, chalky, light gray</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature _____

Date _____

Water Well Owner's Signature _____

Date _____

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD

1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City Norfolk

Telephone Number (402) 371-7313
State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
Address RR1 Box 77J
City O'Neill

Telephone Number (402) 336-1805
Contractor's License No. 39070
State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other

(indicate use)

5. Replacement and abandoned well information.

- A. Is this well a replacement well? ☐ Yes ☒ No
C. Replacement well is _____ feet from abandoned well
E. Original well pump column size: _____ inches.
G. Location of water use of abandoned well:
- D. Abandoned well last operated _____,
F. Completion of original well abandonment on _____,

6. A. Well location: NW 1/4 of the SW 1/4 of Section 18, Township 22 North, Range 1 ☒ East ☐ West, Stanton County.
B. The well is 2195 feet from the ☐ North or ☒ South section line and 28 feet from the ☐ East or ☒ West section line.
C. Street address or block, lot and subdivision, if applicable: Site 16-99 (Dicke) TH# 13-LE-99
D. Location of water use, if applicable (give legal descriptions):
E. If for irrigation, the land to be irrigated is _____ acres.
F. Well reference letter(s), if applicable: Well LE # 15M(North)

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

- A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒
B. Pump column diameter: _____ inches. C. Length of pump column: _____ feet.
D. Pumping equipment-date installed: August, 1999. E. Brand/Type: Grundfos Rediflo2
F. Pump installed by: Contractor ☐ Owner ☒ Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 214 feet.B. Static water level: 72.1 feet.C. Pumping water level: _____ feet.
☐ Estimated or ☐ MeasuredD. Well Construction began: June 22, 1999.E. Well Construction completed: June 28, 1999.F. Bore hole diameter: 7 1/8 inches.G. Plain Casing: Diameter 2.469 ID2.875 OD inches.Type of material: PVC Schedule 40.Wall thickness: 0.203 inch(es).Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+1.5 ft. to 204 ft.

from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:type of material PVC Schedule 40Screen Openings (slot size) 0.010Trade Name: Titan Industries

Length(s) and placement(s) depth from

204 ftto 209 ft.

from _____ ft. to _____ ft.

guides at 202 ft.I. Gravel pack interval(s) from 196 ft.to 214 ft.

from _____ ft. to _____ ft.

Grade size: Local GravelJ. Grouted/Sealed from 0 ft.to 3 ft.,with Steel cover in concrete

(type)

from 3 ft.to 196 ft.,with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotaryL. Drilling fluid: Super Gel-XM. Well development technique (total time and method): Water jetting .75 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>3</u>	<u>Topsoil, silt, sandy dark brown</u>
<u>3</u>	<u>14</u>	<u>Sand, fine-medium, silty some clay</u>
<u>14</u>	<u>21</u>	<u>Silt, clayey, yellow brown</u>
<u>21</u>	<u>40</u>	<u>Clay, silty, dark brown-gray</u>
<u>40</u>	<u>60</u>	<u>Clay, slightly silty, dark green-gray</u>
<u>60</u>	<u>72</u>	<u>Clay, silty, slightly sandy, some gravel, yellow brown</u>
<u>72</u>	<u>141</u>	<u>Clay, silty, some limestone pebbles & sand, dark gray</u>
<u>141</u>	<u>175</u>	<u>Sand & Gravel, coarse sand to coarse gravel</u>

Depth in Feet		Description
From	To	
<u>175</u>	<u>186</u>	<u>Clayey silt to silty clay, green</u>
<u>186</u>	<u>190</u>	<u>Gravel, fine-medium, red</u>
<u>190</u>	<u>196</u>	<u>Clay, silty, sandy</u>
<u>196</u>	<u>208</u>	<u>Gravel, medium-coarse some silt layers</u>
<u>208</u>	<u>234</u>	<u>Clay, yellow-pink</u>
<u>234</u>	<u>245</u>	<u>Clay, shaley, chalky, light gray</u>

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

TH # 13-LE-99

SITE # 16-99

WELL COMPLETION LOG

Project 1999 LEND PII	Well Number 155	Date Drilled 6/11/99	Date Constructed 6/11/99	Ground Elevation 1605(±)
County STANTON	Qtr/Qtr/Qtr NW NW SW	Section 18	Township 22N	Range 15
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES	Log By Jof	Total Depth 155

Borehole Diameter 7 1/8"
Survey Reference
Type/Size of Casing 2 1/2" ID PVC SCH 40 147 ft
Type/Size of Screen 2 1/2" ID SCH 40 THREADED FLUSH 10-FOOT
Screen Slot Size 0.010
Filter Pack AX GRAVEL & LOCAL GRAVEL W/ NATURAL PACK
Type/Amount Grout/Fill BENSAL/EZ-MUD 6.5 BAGS 260 GALLONS
Type/Amount Seal BOTTOM SEAL 1/2 BAGS H.P.

Elevation Depth
From
Reference

3 1/2' TOP OF CASING

0.0 GROUND

3 TOP OF
GROUT/FILL

80.6 WATER LEVEL

140.5 TOP OF FILTER PACK

143.5 TOP OF SCREEN

153.5 BOTTOM OF SCREEN

155 SEAL TOP

158 SEAL BOTTOM

208
245 BOREHOLE DEPTH

LOCKING, STEEL
PROTECTIVE COVER

TOP CAP

CONCRETE
SURFACE SEAL

GROUT OR FILL

WELL CASING

FILTER PACK

WELL SCREEN

BOTTOM CAP

BENTONITE PLUG

GRAVEL FILL

6/22 DEV .5 hr


SOUTH WELL

SITE # 16-99

WELL COMPLETION LOG

Borehole Diameter	7 1/8"
Survey Reference	
Type/Size of Casing	2 1/2" ID SCH 40 FLUSH / THREADED 206 ft
Type/Size of Screen	2 1/2" ID SCH 40 5-FOOT
Screen Slot Size	0.010
Filter Pack	4X GRAVEL 6.5 BUCKETS PLUS NATURAL PACK
Type/Amount Grout/Fill	BENSEAL/EZ-MUD 9 BAGS 360 GALLONS
Type/Amount Seal	TOP 1 BAG HOLE PLUG

214 BOREHOLE DEPTH



6/22 DEV .75 HR

NORTH WELL

Number 16 Well

STANTON COUNTY

TH # 14-LE-99

16 WELL

JOHNSON SITE




T 23N R 1E SECTION 20 SE 1/4

MADISON NE QUAD

Test Hole #14-LE-99 (E-log)
(23N-1E-20dbbb)
Stanton County

Location: NW NW NW SE Sec. 20, T. 23 N., R. 1 E., approximately
 2,501 feet north and 2,612 feet east of southwest corner.
 Ground elevation: 1,492 ft. (t) (Madison NE, 7.5 min. quadrangle)
 Depth to water: 5.1 ft. (6/24/99) Well installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Top soil: no sample.....	0.0	0.6
Sand, very fine to fine, little medium; brown.....	0.6	5.0
Sand, very fine to medium; silty sand layer from 8 to 9 ft, brown.....	5.0	10.0
Sand, very fine to medium, trace of coarse; brown; rare very fine gravel below 15 ft.....	10.0	20.0
Sand, very fine to coarse, trace of very coarse; gray; contains trace of very fine to fine gravel below 25 ft.....	20.0	30.0
Sand, very fine to medium, some coarse; gray.....	30.0	35.0
Sand, very fine to very coarse, trace of very fine gravel, rare fine to medium gravel.....	35.0	40.0
Gravel, sandy; fine sand to fine gravel, trace of medium gravel, contains rare coarse gravel; gray..	40.0	45.0
Sand, very fine to very coarse, trace of fine gravel.....	45.0	47.0
Cretaceous System - Upper Cretaceous Series - Colorado Group:		
Niobrara Formation:		
Shale, clayey, very calcareous, light gray with yellow.....	47.0	60.0
Shale, clayey, very calcareous, light gray; contains pyrite.....	60.0	80.0



Century GEOPHYSICAL CORP.

14-LE-99

COMPANY : Grosch
WELL : 14-LE-99
LOCATION/FIELD : Site 15
COUNTY : Stanton
STATE : NE
SECTION : 20

OTHER SERVICES:

down3
down1&2
None

TOWNSHIP : 23 RANGE : 1E

DATE : 06/23/99
DEPTH DRILLER : 80
LOG BOTTOM : 79.68
LOG TOP : 1.09

PERMANENT DATUM : None

KB : None

LOG MEASURED FROM: grnd

DF : None

DRL MEASURED FROM: +2

GL : 1490

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : sol

BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite


BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54

FILE : PROCESSED
TYPE : 8043A

THRESH: 2500

Madison NE Quad
Well 16M

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS



NOT TO SCALE

STANTON COUNTY
T-23-N R-1-E
TH #14-LE-99

1987
16

Photo B-6
Sec. 20
SITE 15-99

2. NHEL/NW
25.0

460

T-1607

NH
2.103

NH
1.32.5

3.84 NH/NW

NH
5.0

NH
7.5.7

NH
1.78.5

307

T-371

Well LE # 16M

4. NH
111.0

5. NH/NW
13.5

NH
4.1

NH
10.0

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
Owner Code No. _____ Receipt No. _____ NRD1. Well Owner Lower Elkhorn Natural Resources District
Address 601 E Benjamin Avenue Suite 102
City NorfolkTelephone Number (402) 371-7313State NE Zip Code 68701 +2. Drilling Firm Grosch Irrigation
Address RRI Box 77J
City O'NeillTelephone Number (402) 336-1805Contractor's License No. 39070State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one):
- ☐
- Dewatering (over 90 days)
- ☐
- Domestic
- ☐
- Geothermal
- ☐
- Ground Heat Exchanger
-
- ☐
- Ground Water Source Heat Pump
- ☐
- Industrial
- ☐
- Injection
- ☐
- Irrigation
- ☐
- Livestock
- ☒
- Monitoring
-
- ☒
- Observation
- ☐
- Public Water Supply (with spacing (46-638))
- ☐
- Public Water Supply (without spacing)
- ☐
- Recovery
-
- ☐
- Aquaculture
- ☐
- Other
-
- (indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well: _____

5. A. Well location: NW 1/4 of the SE 1/4 of Section 20, Township 23 North, Range 1 ☒ East ☐ West, Stanton County.B. The well is 2501 feet from the ☐ North or ☒ South section line and 2612 feet from the ☒ East or ☐ West section line.C. Street address or block, lot and subdivision, if applicable: Site 15-99 (Johnson), TH # 14-LE-99

D: Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 16M

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute.Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.E. Brand/Type: Grundfos Rediflo2F. Pump installed by: Contractor ☐ Owner ☒Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 43 feet.B. Static water level: 5.1 feet.C. Pumping water level: _____ feet.
☐ Estimated or ☐ MeasuredD. Well Construction began: June 23, 1999.E. Well Construction completed: June 28, 1999.F. Bore hole diameter: 7 1/8 inches.G. Plain Casing: Diameter 2.469 ID2.875 OD inches.Type of material: PVC Schedule 40.Wall thickness: 0.203 inch(es).Joints--Welded/Glued/Threaded/Other: ThreadedLength(s) and placement(s) depth from +1 ft. to 32 ft.

from _____ ft. to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:type of material PVC Schedule 40Screen Openings (slot size) 0.010Trade Name: Titan IndustriesLength(s) and placement(s) depth from 32 ftto 42 ft.

from _____ ft. to _____ ft.

guides at 30 ft.I. Gravel pack interval(s) from 29 ft. to 43 ft.

from _____ ft. to _____ ft.

Grade size: local screenJ. Grouted/Sealed from 0 ft. to 3 ft.,with Steel cover in concrete

(type)

from 3 ft. to 29 ft.,with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotaryL. Drilling fluid: Super Gel-XM. Well development technique (total time and method): Water jetting 1 hour

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>0.5</u>	<u>Top soil, Silty, sandy</u>
<u>0.5</u>	<u>17</u>	<u>Sand, fine & gravel, fine with tan silty, sand layers</u>
<u>17</u>	<u>22</u>	<u>Silt, moderately sandy, tan to black</u>
<u>22</u>	<u>30</u>	<u>Gravel, fine to medium, black & green</u>
<u>30</u>	<u>33</u>	<u>Clay, silty, gray</u>
<u>33</u>	<u>45</u>	<u>Gravel, fine to coarse, black & green with red & tan gravel @ base</u>
<u>45</u>	<u>59</u>	<u>Clay, chalky, orange yellow</u>
<u>59</u>	<u>80</u>	<u>Chalk, clayey, gray to dark gray</u>

Depth in Feet		Description
From	To	

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature


Date

TH # 14-LE-99

SITE # 15-99

WELL COMPLETION LOG

Project 1999 LEND PII	Well Number 16M	Date Drilled 6/23/99	Date Constructed 6/23/99	Ground Elevation 1490(L)
County STANTON	Qtr/Qtr/Qtr NW NW SE	Section 20	Township 23N	Range 1E
Drilling Co. GROCH	Method MUD ROTARY	Driller SHOLES	Log By Jof	Total Depth 43



6/23 DEV 1.25 hr


Number 17 Well

STANTON COUNTY

TH # 15-LE-99

17 WELL

NIXON SITE



T 23N R1E SECTION 16 SW 1/4

MADISON NE QUAD


Test Hole #15-LE-99 (E-log)
(23N-1E-16ccbb)
Stanton County

Location: NW NW SW SW Sec. 16, T. 23 N., R. 1 E., approximately
1,292 feet north and 36 feet east of southwest corner.

Ground elevation: 1,485 ft. (t) (Madison NE, 7.5 min. quadrangle)

Depth to water: 2.8 ft. (6/25/99) Well installed.

	<u>Depth, in feet</u>	
	From	To
Quaternary System, undifferentiated:		
Top soil: silt, very sandy, slightly clayey, dark brown; sand is very fine, some fine,.....	0.0	5.0
Sand, silty; very fine to fine; dark brown.....	5.0	10.0
Sand, very fine to very coarse, trace of fine gravel; gray; rare medium gravel below 15 ft.....	10.0	20.0
Sand, very fine to very coarse, little fine gravel..	20.0	25.0
Sand, very fine to coarse, little very coarse sand to very fine gravel.....	25.0	30.0
Sand, gravelly; very fine sand to fine gravel, rare medium gravel; contains few calcareous grains.....	30.0	52.0
Cretaceous System - Upper Cretaceous Series - Colorado Group:		
Niobrara Formation:		
Shale, clayey, very calcareous, light greenish gray; some white speckling from 60 to 65 ft.....	52.0	70.0



Century GEOPHYSICAL CORP.

15-LE-99

COMPANY : grosch
WELL : 15-LE-99
LOCATION/FIELD : Site 14
COUNTY : STANTON
STATE : NE
SECTION : 16

OTHER SERVICES:

Down
None
None

TOWNSHIP : 23 RANGE : 1E

DATE : 06/24/99
DEPTH DRILLER : 70
LOG BOTTOM : 69.53
LOG TOP : 1.00

PERMANENT DATUM : None
LOG MEASURED FROM: grd=0
DRL MEASURED FROM: +2

KB : None
DF : None
GL : 1485

CASING DIAMETER : 0
CASING TYPE : None
CASING THICKNESS: 0

LOGGING UNIT : 208A
FIELD OFFICE : Norfolk
RECORDED BY : Sol

BIT SIZE : 5
MAGNETIC DECL. : 0
MATRIX DENSITY : 2.71
NEUTRON MATRIX : Dolomite


BOREHOLE FLUID : 0
RM : 0
RM TEMPERATURE : 0
MATRIX DELTA T : 54

FILE : PROCESSED
TYPE : 8043A

THRESH: 2500

Madison NE Quad
Well 17M

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS



3

NOT TO SCALE

STANTON COUNTY
T-23-N R-1-E
TH #15-LE-99

1987
28

Photo B-6
Sec. 16
SITE 14-99

E2160

OT
Antelope
County

16

NHEL

1.99.2

1638

Well LE #17M

NHEL

6.388

1763

T-481

NHEL

1.18.6

T-6581

NHEL

33.8

NHEL

4.43.6

2495

T-6580

12. NHEL
9.9

NHEL

38.2

2097

T-363

1651

T-464

NHEL

3.21.3

NHEL

2.60

NHEL/NW

1.28.6

1550

T-5717

STATE OF NEBRASKA
DEPARTMENT OF WATER RESOURCES
WATER WELL REGISTRATION

FOR DEPARTMENT USE ONLY

Registration Date: _____ Sequence No. _____ Registration No. _____
 Owner Code No. _____ Receipt No. _____ **NRD**

1. Well Owner Lower Elkhorn Natural Resources District
 Address 601 E Benjamin Avenue Suite 102
 City Norfolk

Telephone Number (402) 371-7313

State NE Zip Code 68701 +

2. Drilling Firm Grosch Irrigation
 Address RR1 Box 77J
 City O'Neill

Telephone Number (402) 336-1805

Contractor's License No. 39070

State NE Zip Code 68763 +

3. Permit Number(s) _____

4. Purpose of well (indicate one): ☐ Dewatering (over 90 days) ☐ Domestic ☐ Geothermal ☐ Ground Heat Exchanger
☐ Ground Water Source Heat Pump ☐ Industrial ☐ Injection ☐ Irrigation ☐ Livestock ☒ Monitoring
☒ Observation ☐ Public Water Supply (with spacing (46-638)) ☐ Public Water Supply (without spacing) ☐ Recovery
☐ Aquaculture ☐ Other _____
 (indicate use)

5. Replacement and abandoned well information.

A. Is this well a replacement well? ☐ Yes ☒ No

D. Abandoned well last operated _____,

C. Replacement well is _____ feet from abandoned well

F. Completion of original well abandonment on _____,

E. Original well pump column size: _____ inches.

G. Location of water use of abandoned well: _____

5. A. Well location: SW 1/4 of the SW 1/4 of Section 16, Township 23 North, Range 1 ☒ East ☐ West, Stanton County.

B. The well is 1292 feet from the ☐ North or ☒ South section line and 36 feet from the ☐ East or ☒ West section line.

C. Street address or block, lot and subdivision, if applicable: Site 14-99 (Nixon), TH # 15-LE-99

D. Location of water use, if applicable (give legal descriptions):

E. If for irrigation, the land to be irrigated is _____ acres.

F. Well reference letter(s), if applicable: Well LE # 17M

7. Pump Information.

Is pump installed at this time? ☐ Yes ☒ No

If yes, complete items A through F.

If no, complete items A and D with estimated information for those wells in which pump will be installed.

A. Actual pumping rate, if applicable: 3-8 gallons per minute. Measured ☐ or Estimated ☒

B. Pump column diameter: _____ inches.

C. Length of pump column: _____ feet.

D. Pumping equipment-date installed: August, 1999.

E. Brand/Type: Grundfos Rediflo2

F. Pump installed by: Contractor ☐ Owner ☒

Pump Installer ☐ License No. _____

8. Well Construction Information.

A. Total well depth: 46 feet.B. Static water level: 2.8 feet.

C. Pumping water level: _____ feet.

☐ Estimated or ☐ MeasuredD. Well Construction began: June 24, 1999.E. Well Construction completed: June 28, 1999.F. Bore hole diameter: 7 1/8 inches.G. Plain Casing: Diameter 2.469 ID2.875 OD inches.Type of material: PVC Schedule 40.Wall thickness: 0.203 inch(es).Joints--Welded/Glued/Threaded/Other: Threaded

Length(s) and placement(s) depth from

+2 ft.. to 35.5 ft.

from _____ ft.

to _____ ft.

H. Screen: 2.469 ID 2.875 OD in:type of material PVC Schedule 40Screen Openings (slot size) 0.010Trade Name: Titan Industries

Length(s) and placement(s) depth from

35.5 ftto 45.5 ft.

from _____ ft. to _____ ft.

guides at 33 ft.I. Gravel pack interval(s) from 32 ft.to 46 ft.

from _____ ft. to _____ ft.

Grade size: 10/20 & gravelJ. Grouted/Sealed from 0 ft.to 3 ft.,with Steel cover in concrete

(type)

from 3 ft.to 32 ft.,with Benseal/EZ-Mud

(type)

K. Drilling method: Mud rotaryL. Drilling fluid: Super Gel-XM. Well development technique (total time and method): Water jetting 0.75 hours

N. Will chemicals, fertilizer or antifreeze be injected or utilized in the system?

☐ Yes ☒ No

If yes, what will be used:

9. Geologic Materials Logged

Depth in Feet		Description
From	To	
<u>0</u>	<u>3</u>	<u>Topsoil, Silt, dark brown</u>
<u>3</u>	<u>8</u>	<u>Silt, sandy, dark brown to black</u>
<u>8</u>	<u>19</u>	<u>Sand, fine to coarse & gravel, black & green</u>
<u>19</u>	<u>31</u>	<u>Sand, fine to medium; some gravel</u>
<u>31</u>	<u>50</u>	<u>Gravel, medium to coarse; some fine to medium sand</u>
<u>50</u>	<u>70</u>	<u>Chalk, clayey to clay, chalkey, light to medium gray</u>

Depth in Feet		Description
From	To	

(Additional sheets may be submitted)

10. I am familiar with the information submitted on this registration, and to the best of my knowledge it is true.

Water Well Contractor's Signature

Date

Water Well Owner's Signature

Date

WELL COMPLETION LOG

Project 1999 LEND FII	Well Number 17M	Date Drilled 6/24/99	Date Constructed 6/24/99	Ground Elevation 1485(E)
County STANTON	Qtr/Qtr/Qtr NW SW SW	Section 16	Township 23 N	Range 1E
Drilling Co. GROSCH	Method MUD ROTARY	Driller SHOLES, BEN	Log By Jol	Total Depth 46

